CITY OF COLWOOD



3300 Wishart Road | Colwood | BC V9C 1R1 | 250 294-8153 planning@colwood.ca | www.colwood.ca

File: DP000031 - Townhouse Development at 3494 Wishart Rd

DEVELOPMENT PERMIT DP000031

THIS PERMIT, issued JANUARY 20, 2025, is,

ISSUED BY:

CITY OF COLWOOD, a municipality incorporated under the Local Government Act,

3300 Wishart Road, Victoria, BC, V9C 1R1

(the "City")

PURSUANT TO:

Section 490 of the Local Government Act , RSBC 2015, Chapter 1

ISSUED TO:

CEDAR HILL LIVING LTD 800-1070 DOUGLAS ST VICTORIA BC V8W 2C4

(the "Permittee")

This Form and Character, Natural Hazards (Steeply Sloped) and Environmental (Hillside)
Development Permit applies to those lands within the City of Colwood described below, and any
and all buildings, structures, and other development thereon:

LOT 3, SECTION 62, ESQUIMALT LAND DISTRICT, PLAN VIP10219 3494 WISHART RD

(the "Lands")

- This Development Permit regulates the development and alterations of the Land, and supplements the "Colwood Land Use Bylaw, 1989" (Bylaw No. 151), to ensure the Form and Character, Natural Hazard, and Environmental considerations for the development to 50 townhomes and associated site improvements are consistent with the design and environmental guidelines for areas designated as "Neighbourhood Intensive Residential" in the City of Colwood Official Community Plan (Bylaw No. 1700).
- This Development Permit is <u>NOT</u> a Building Permit or a subdivision approval.
- This Development Permit is issued subject to compliance with all of the bylaws of the City of Colwood that apply to the development of the Lands, except as specifically supplemented by this Permit.

- 5. The Director of Development Services or their delegate may approve minor variations to the schedules attached to and forming part of this Development Permit, provided that such minor variations are consistent with the overall intent of the original plans and do not alter the form and character of the development authorized by those plans.
- If the Permittee does not substantially start the construction permitted by this Permit within 24
 months of the date of this Permit, the Permit shall lapse and be of no further force and effect.
- 7. The development is to be constructed in accordance with the following plans and specifications, which are attached to and form as part of this permit:

Schedule 1	Architectural Drawings prepared by Walking Stick Drafting dated October 25, 2024
Schedule 2	Landscape Plan prepared by LADR Landscape Architects dated November 25, 2024
Schedule 3	Landscape Cost Estimate prepared by LADR Landscape Architects dated January 2, 2025
Schedule 4	Environmental Impact Assessment prepared by Corvidae Environmental Consulting Inc, dates May 2023
Schedule 5	Habitat Restoration and Enhancement Plan prepared by Corvidae Environmental Consulting Inc, dated August 19, 2024
Schedule 6	Tree Management Plan prepared by Talmack Urban Forestry Consultants Limited dated October 25, 2024
Schedule 7	Geotechnical Assessment prepared by Ryzuk Geotechnical, dated October 1, 2024
Schedule 8	Civil Design Drawings prepared by OnPoint Project Engineers Ltd, dated January 3, 2025
Schedule 9	Sediment and Erosion Control Plan prepared by Walking Stick Developments Inc.

8. This Development Permit authorizes the construction of 50 townhomes along with any associated site works. The Lands shall not be altered, nor any buildings or structures constructed, except in accordance with the following conditions:

GENERAL

- 8.1. This Permit shall not be construed as relieving the Permittee from compliance with any of the requirements contained within the Section 219 covenants registered as "CB1327234" as amended.
 - 8.1.1. Irrespective of the issuance of this Development Permit, the Lands shall not be cleared, blasted or built upon until the City is in receipt of a Building Permit application for the site, and the City provides written authorization to proceed with land alterations.
- 8.2. This Permit does not authorize off-site works; additional permits are required.

FORM AND CHARACTER CONDITIONS

Building Features

8.3. The form and character of the buildings to be constructed on the Lands shall conform to the Architectural Drawings prepared by Walking Stick Drafting (Schedule 1).

- 8.4. Any future additions of telecommunications antennas or equipment to the exterior of the buildings and/or structures included in this Permit shall be architecturally integrated into the buildings and/or structures they are mounted on or screened from views so as not to be visually obtrusive, to the satisfaction of the Director of Development Services or their delegate.
- 8.5. All mechanical roof elements, including mechanical equipment, elevator housings, and vents shall be visually screened with sloped roofs or parapets, or other forms of solid screening to the satisfaction of the Director of Development Services or their delegate.
- 8.6. No future construction/installation of unenclosed or enclosed outdoor storage areas or recycling/refuse collection shall be undertaken without the issuance of a further Development Permit or amendment to this Permit.

Signage

8.7. This Development Permit does not include any signage approvals. A separate sign permit will be required for any marketing signage.

Landscaping

- 8.8. The design and construction of the proposed landscaping shall be in substantial compliance with the Landscape Plan prepared by LADR Landscape Architects (**Schedule 2**).
- 8.9. Prior to the issuance of a building permit, the Permittee shall provide the City with a written letter of engagement from a registered landscape architect agreeing to:
 - 8.9.1. Supervise and install the landscape work in accordance with the approved Landscape Plan prepared by LADR Landscape Architects (Schedule 2); and
 - 8.9.2. Perform a final inspection and submit an inspection report to the City confirming substantial compliance with the approved landscape plan.
- 8.10. Prior to the issuance of a Building Permit, the Permittee has provided to the City in the form of an irrevocable letter of credit or certified cheque, security in the amount of \$218,539.97 based on 110% of the Landscape Cost Estimate (\$198,672.70) prepared by LADR Landscape Architects (Schedule 3), which amount, or a portion therefore, as the case may be, shall be returned, no sooner than 1 year from the date of planting, upon receipt of a signed statement of substantial completion from a registered landscape architect, to the satisfaction of the Director of Development Services.
- 8.11. Prior to returning the landscape deposit, the Permittee shall obtain a one-year warranty of the landscape works from the landscape contractor. This warranty shall be transferrable to subsequent owners of the property within the warranty period. The warranty must include provision for a further one-year warranty on materials.

ENVIRONMENTAL CONDITIONS

General

8.12. Where required, Federal and Provincial environmental approvals shall be obtained prior to any works occurring on the Lands.

- 8.13. Development on the Lands shall comply with the recommendations contained in the Environmental Impact Assessment prepared by Corvidae Environmental Consulting (Schedule 4).
- 8.14. A security deposit of \$13,943.60, based on 110% of the Restoration Cost Estimate (\$12,676) prepared by Corvidae Environmental Consulting Inc. (Schedule 5) has been accepted prior to the issuance of this Development Permit. The environmental security deposit will be held until a satisfactory final inspection report prepared by the project's biologist is submitted to the City, no sooner than one year from the date restoration work is completed, confirming that the restoration works remain in substantial compliance with the Habitat Restoration and Enhancement Plan (Schedule 5) and Landscape Plan (Schedule 2).
- 8.15. Invasive species removal should be completed outside of the migratory bird window (prior to March 15th or after August 31st; Government of Canada 2018). If invasive species removal is scheduled within the migratory bird window, a QEP should conduct nest search surveys a maximum of 2-3 days prior to the start of activities. If an active nest is discovered during nest search or clearing activities, the nest will be subject to site-specific mitigation measures until the young have naturally fledged/left the area. Multiple nest sweeps may be required.
- 8.16. All recommendations in the Habitat Restoration and Enhancement Plan (Schedule 5) must be followed including the placement of additional rocks or logs in sunny areas to add habitat features for reptiles as determined by the project biologist.
- 8.17. A QEP must be on-site to direct the invasive species removal, and all invasive vegetation removal must be done by hand and using hand-held equipment, or a mini excavator with a skilled operator.
- 8.18. No clearing or site preparation shall occur until all qualified professionals (registered biologist, qualified environmental professional, arborist, etc.), as applicable, have been retained to oversee impacts on the site and ensure compliance with the recommendations contained in Schedules 4, 6 and 7. Prior to the issuance of this Development Permit, the Permittee has provided the City with written letters of engagement from all qualified professionals, as applicable, agreeing to:
 - 8.18.1. Oversee impacts on the site and ensure compliance with the recommendations contained in **Schedules 4, 6 and 7**; and
 - 8.18.2. Perform a final inspection and submit an inspection report to the City confirming substantial compliance with Schedules 4, 6 and 7.
- 8.19. Signage identifying the environmentally sensitive and conservation areas is to be installed as per the Environmental Impact Assessment prepared by Corvidae Environmental Consulting Ltd (Schedule 4).
- 8.20. Environmental restoration and enhancement work shall be completed in substantial compliance with Schedule 5 to the satisfaction of the Director of Development Services.

Erosion and Sediment Control

8.21. Erosion and sediment control shall be in accordance with the approved Erosion and Sediment

Contral Plan prepared by Walking Stick Developments Inc (Schedule 9).

Tree Management

- 8.22. Trees located on the Lands shall be retained in accordance with the approved Tree Management Plan prepared by Talmack Urban Foresty (Schedule 6) and only varied with written consent from the Director of Development Services.
- 8.23. If any replacement tree does not survive for 1 year after initial planting, the Permittee shall, within 6 months, replace the tree with a replacement tree in accordance with the Tree Management Plan prepared by Talmack Urban Forestry (Schedule 6) and the Landscape Plan prepared by LADR Landscape Architects (Schedule 3) and shall thereafter maintain the replacement tree for a period of 1 year.
- 8.24. The project Arborist must meet with the site foreman or supervisor before any site clearing, tree removal, demolition, or other construction activity occurs and to confirm the locations of the tree protection barrier fencing.
- 8.25. Tree fencing must be installed prior to any land alterations. A City of Colwood Development Services Planner must conduct a site visit prior to the issuance of a blasting permit or any other land alterations. The Director of Development Services, or their delegate, must provide written authorization to proceed with land alterations after tree fencing has been installed.
- 8.26. Protection fencing must be used around planned greenspaces to prevent soil compaction and preserve planting areas for trees.
- 8.27. Play structure must not be built directly beside tree #578.
- 8.28. Hydraulic rock breakers/excavators must be instead of blasting while building the road beside the private amenity area per the recommendations of the arborist report.
- 8.29. Arborist supervision is required while excavating within the critical root zone (CRZ) of any retained trees.
- 8.30. Rock blasting shall not be used within the influencing distance of any offsite trees. Hydraulic rocking breaker or excavators must be used under the supervision of the project arborist if within the CRZ.
- 8.31. No back-breaking beyond the building outlines of Area 2 while blasting. The use of line drilling and pre-shearing must be used.

Nesting and Migratory Birds

8.32. It is the property owner's responsibility to ensure that physical works are compliant with the federal Migratory Birds Convention Act, 1994 and the provincial Wildlife Act with respect to bird nests. Both of these acts prohibit the disturbance or destruction of active nests and eggs.

HAZARD LANDS

8.33. All works shall adhere to the assessment and recommendations contained in the Geotechnical Report prepared by Ryzuk Geotechnical (Schedule 7) and be in substantial compliance with the Civil Works prepared OnPoint Project Engineers Ltd. (Schedule 8) and be completed under the guidance and approval of a Geotechnical Engineer.

- 8.34. This permit does not authorize any blasting on the site; additional permits are required.
- 8.35. No retaining walls over 1.2m in height are permitted.

VARIANCES

- 9.0. The Colwood Official Community Plan (Bylaw No. 1700) Policy 11.2.2.3 promotes the application of Site Adaptive Planning and design principles on all Hillside development sites. This approach emphasizes minimizing ecosystem disturbance, preserving habitat areas, and integrating existing natural features, such as rock outcrops, cliffs, and tree strands. It also aims to enhance pedestrian connections while safeguarding tree protection. Additionally, Section 18.4 reinforces the commitment to implementing a Site Adaptive Framework for new developments, with the primary goal of reducing landscape disruption in identified Hillside development areas. Hillside Objective (t) prioritizes minimizing blasting and re-contouring, while Section 22.1 Hillside Guideline (k) specifies the importance of avoiding unnecessary tree and vegetation removal during service installation for each development phase. Considering these policies and based on the authority in Section 490(1)(a) of the Local Government Act, the Subdivision and Development Servicing Bylaw (No. 2000) is hereby varied as follows:
 - Vary SSD-R24 (Typical Cross Section Limited Local 18m ROW) along Delora Drive to decrease the east sidewalk from 2.0m to 1.5m and permit the 2.0m sidewalk on the westside at curb instead of separated.

ISSUED ON THIS 20^{14} DAY OF JANUARY, 2025

YAZMIN HERNANDEZ, MCIPP RPP

DIRECTOR OF DEVELOPMENT SERVICES

3494 Wishart Townhouse Development **Project Statistics**

Schedule 1

Area 2

Zoning Analysis

	Permitted/ Required	Proposed
Minimum Site Area Road Dedication Area	11,500 Sq M	12,552 Sq M 1,140 Sq M
Conservation Area	1,000 Sq M	1,002 Sq M
Attached Housing Units	50	50
Parking	100	100
(2 spaces/dwelling)	利利 西斯特	1 350000
Guest Parking (.1 per unit)	5	7(incl HC)
HC Parking	5 2	2
Regular Stall Dimension:	2.5 m x 5.5 m	
HC Stall Dimension:	4.1 m x 5.5 m	
Municipal Spaces (Delora Drive)	0	4
Standard Bike Stall Dimensions	.6 m x 1.8 m	
Oversized Bike Stall Dimensions	.9 m x 3 m	
Long Term Bike Stalls (Std)	42	42
Long Term Bike Stalls (Oversized)	5 (10% of units	
Oversized stalls located in all garages	of buildings 14 and	d 15 (qty: 8).
% of Long Term Stalls with 110V Access	50%	100%
Short Term Bike Stalls (Std)	5	5
Short Term Bike Stalls (Oversized)	1	5 1 2
Short Term Stalls with EV Access	2	2
Short term stalls include a 2.1 m overh	nead structure	

534 Sq M

554 Sq M

Amenity Area (3 Sq M/Bedroom)

Area 1

	Permitted/ Required	Proposed		Permitted/ Required	Proposed
Zone:	CD39		Zone:	CD39	
Finished Area		6,665 Sq M	Finished Area		1447 Sq M
FAR:	0.7	.675	FAR:	0.7	.547
Height:	11.0 M	10.70 M	Height:	11.0	9.51
Minimum Lot Area	9.000 Sa M	9.879 Sq M	Minimum Lot Area	2,500 Sq M	2643 Sq M
Lot Coverage	Control throat Control	2717 Sq M	Lot Coverage		544 Sq M
Maximum Lot Coverage	35%	27.5%	Maximum Lot Coverage	30%	20.6 %
Minimum Lot Frontage	60 m	60.58 m	Minimum Lot Frontage	60 m	60.58 m
Setbacks			Setbacks		
Front - Wishart	6.0m	6.01 m	Front - Delora Dr	6.0 m	6.0 m
Front - Delora Dr	1.5 m	1.50 m	Interior Side (North)	1.5 m	1.5 m
Interior Side (North)	1.5 m	1.51 m	Interior Side (South)	9.5 m	9.51 m
Interior Side (South)	3.0 m	3.0 m	Rear	18.0 m	20.5 m

		Floor Area (Excludin			Garage) - Square Fee	ige) - Square Feet			Bedrooms/Bldg	Area
Building#	Unit Description	Level 1	Level 2	Level 3	Building Total	Unit Total	Units/Building	Coverage Sq M	Bedrooms/Blug	Area
1	3 Bedroom + Bonus, 2.5 Bath	860	1,298	1,296	3,454	1,727	2	120.6	6	2
2	3 Bedroom + Bonus, 2.5 Bath	1,720	2,596	2,592	6,908	1,727	4	241.2	12	2
3	3 Bedroom + Bonus, 2.5 Bath	1,299	1,958	1,953	5,210	1,737	3	182.0	9	2
4	3 Bedroom + Den, 2.5 Bath	926	1,073	1,287	3,286	1,643	2	137.8	6	1
5	3 Bedroom + Bonus, 2.5 Bath	1,708	2,578	2,558	6,844	1,711	4	239.6	12	1
6	4 Bedroom, 2.5 Bath	1,852	2,510	3,000	7,362	1,841	4	309.4	16	1
7	3 Bedroom + Bonus, 2.5 Bath	854	1,289	1,279	3,422	1,711	2	119.8	6	1
8	4 Bedroom, 2.5 Bath	926	1,255	1,500	3,681	1,841	2	154.7	6	1
9	3 Bedroom + Bonus, 2.5 Bath	1,281	1,934	1,918	5,133	1,711	3	179.8	9	1
10	4 Bedroom, 2.5 Bath	926	1,255	1,500	3,681	1,841	2	154.7	8	1
11	4 Bedroom, 2.5 Bath	926	1,255	1,500	3,681	1,841	2	154.7	8	1
12	4 Bedroom, 2.5 Bath	1,852	2,510	3,000	7,362	1,841	4	309.4	16	1
13	4 Bedroom, 3.5 Bath	847	1,287	1,278	3,412	1,706	2	119.9	8	1
14	4 Bedroom, 3.5 Bath	1,694	2,574	2,556	6,824	1,706	4	239.2	16	1
15	4 Bedroom, 3.5 Bath	1,694	2,574	2,556	6,824	1,706	4	239.2	16	1
16	4 Bedroom, 3.5 Bath	1,694	2,574	2,556	6,824	1,706	4	239.2	16	1
17	4 Bedroom, 3.5 Bath	847	1,287	1,278	3,412	1,706	2	119.9	8	1

Area 1 Finished Area 1 Finished Area 1 Gross Lot Area 2 Finished Area 2 Finished Area 2 Gross Lot Total Bedrooms

Drawing List

A2.5 Strata Road Phase 1 East Section View A3.01 Building 1 Floor Plan 1 A3.02 Building 2 Floor Plan 2 - Lvl 1 A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 2 - Lvl 2 & 3 A3.05 Building 4 Floor Plan 4 A3.06 Floor Plan 5 - Lvl 1 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 A3.08 Building 6 & 8, Floor Plan 7 & 8 + Floor Plan 8 & 8 + Lvl 1 A3.10 Building 10, 11 & 12 Floor Plan 7 & 7 * Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8 * - Lvl 2 & 3 A4.01 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8 * - Lvl 2 & 3 A4.01 Building 1 Exterior Elevations A4.03 Building 1 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations		Description
A1.0 Overall Site Plan A1.1 Strata Road - Site Plan A1.2 Delora Drive - Site Plan A1.3 Site Plan - Retaining Wall Layout A2.0 North Section View - Delora Drive A2.1 East Section View - Phase 3 Strata Road A2.2 East Section View - Phase 3 Strata Road A2.2 Phase 2/3 Strata Road Transition A2.3 North Section View - Strata Road Phase 2/3 Strata Road Transition A2.4 North Section View - Strata Road Phase A2.5 Strata Road Phase 1 East Section View A3.01 Building 1 Floor Plan 1 A3.02 Building 1 Floor Plan 2 - Lvl 1 A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 3 - Lvl 2 & 3 A3.05 Building 4 Floor Plan 4 A3.06 Floor Plan 5 - Lvl 2 & 3 Building 5, 7 & 9 Floor Plan 5 - Lvl 1 A3.07 Floor Plan 5 - Lvl 2 & 3 Building 6 & 8, Floor 6 & 6* Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 A3.12 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 1, Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations	A0.0	Cover Page, Project Statistics
A1.1 Strata Road - Site Plan A1.2 Delora Drive - Site Plan A1.3 Site Plan - Retaining Wall Layout A2.0 North Section View - Delora Drive A2.1 East Section View - Phase 3 Strata Road A2.2 Phase 2/3 Strata Road Transition A2.3 North Section View - Phase 3 Strata Road A2.2 Phase 2/3 Strata Road Transition A2.4 North Section View - Strata Road Phase A2.5 Strata Road Phase 1 East Section View A3.01 Building 1 Floor Plan 1 A3.02 Building 2 Floor Plan 2 - Lvl 1 A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 3 - Lvl 1 A3.05 Building 4 Floor Plan 4 A3.06 Floor Plan 5 - Lvl 2 & 3 A3.07 Floor Plan 5 - Lvl 1 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 Building 6 & 8, Floor 6 & 6* Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 11, 4, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A3.12 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 1, Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.04 Building 1 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 6 Exterior Elevations A4.05 Building 6 Exterior Elevations A4.05 Building 6 Exterior Elevations	A0.1	Subdivision & Existing Site Plan
A1.1 Strata Road - Site Plan A1.2 Delora Drive - Site Plan A1.3 Site Plan - Retaining Wall Layout A2.0 North Section View - Delora Drive A2.1 East Section View - Phase 3 Strata Road A2.2 Phase 2/3 Strata Road Transition A2.3 North Section View - Phase 3 Strata Road A2.2 Phase 2/3 Strata Road Transition A2.4 North Section View - Strata Road Phase A2.5 Strata Road Phase 1 East Section View A3.01 Building 1 Floor Plan 1 A3.02 Building 2 Floor Plan 2 - Lvl 1 A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 3 - Lvl 1 A3.05 Building 4 Floor Plan 4 A3.06 Floor Plan 5 - Lvl 2 & 3 A3.07 Floor Plan 5 - Lvl 1 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 Building 6 & 8, Floor 6 & 6* Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 11, 4, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A3.12 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 1, Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.04 Building 1 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 6 Exterior Elevations A4.05 Building 6 Exterior Elevations A4.05 Building 6 Exterior Elevations		1 10 100 NO 10 10 10 10 10 10 10 10 10 10 10 10 10
A1.2 Delora Drive - Site Plan A1.3 Site Plan - Retaining Wall Layout A2.0 North Section View - Delora Drive A2.1 East Section View - Phase 3 Strata Road A2.2 Phase 2/3 Strata Road Transition A2.3 North Section View Phase 2/3 Strata Road Transition A2.4 North Section View Phase 2/3 Strata Road Transition A2.4 North Section View Phase 2/3 Strata Road Transition A2.5 Strata Road Phase 1 East Section View A3.01 Building 1 Floor Plan 1 East Section View A3.02 Building 2 Floor Plan 2 - Lvl 1 A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 2 - Lvl 2 & 3 A3.05 Building 5 F Roa 9 Floor Plan 5 - Lvl 2 & 3 Building 5 F Roa 9 Floor Plan 5 - Lvl 1 Building 5 F Roa 9 Floor Plan 5 - Lvl 1 Building 6 & R Building 6 & R Building 6 & R Building 10, 11 & 12 Floor Plan 7 & Z** - Lvl 1 Building 10, 11 & 12 Floor Plan 7 & Z** - Lvl 1 Building 13, 14, 15, 16 & 17 Floor Plan 8 & R** - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & R** - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & R** - Lvl 2 & 3 Building 1 Exterior Elevations A4.01 Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations	-	
A1.3 Site Plan - Retaining Wall Layout A2.0 North Section View - Delora Drive A2.1 East Section View - Phase 3 Strata Road A2.2 East Section View - Phase 3 Strata Road A2.2 East Section View - Phase 2/3 Strata Road Transition A2.3 North Section View - Phase 2/3 Strata Road Transition A2.4 North Section View - Strata Road Phase A2.5 Strata Road Phase 1 East Section View A3.01 Building 1 Floor Plan 1 A3.02 Building 2 Floor Plan 2 - Lvl 1 A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 4 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 A3.07 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 A3.08 Building 6, 7 & 9 Floor Plan 5 - Lvl 1 A3.07 Building 6, 7 & 9 Floor Plan 7 - Lvl 2 & 3 A3.08 Building 6, 7 & 9 Floor Plan 7 - Lvl 2 & 3 A3.08 Building 6, 7 & 9 Floor Plan 7 & 7* - Lvl 1 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 1 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 A3.10 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.04 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations		
A2.0 North Section View - Delora Drive A2.1 East Section View - Phase 3 Strata Road A2.2 East Section View - Phase 3 Strata Road A2.2 East Section View - Phase 2/3 Strata Road Transition A2.3 Phase 2/3 Strata Road Transition A2.4 North Section View - Strata Road Phase A2.5 Strata Road Phase 1 East Section View A3.01 Building 1 Floor Plan 1 A3.02 Building 2 Floor Plan 2 - Lvl 1 A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 3 A3.05 Building 4 Floor Plan 4 A3.06 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 A3.08 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 Building 6 & 8, Floor 6 & 6* Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 A3.11 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 A3.12 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 5 Exterior Elevations A4.05 Building 6 Exterior Elevations	-	
A2.1 East Section View - Phase 3 Strata Road A2.2 Phase 2/3 Strata Road Transition A2.3 North Section View Phase 2/3 Strata Road Transition A2.4 North Section View - Strata Road Phase A2.5 Strata Road Phase 1 Fast Section View A3.01 Building 1 Floor Plan 1 Floor Plan 2 - Lvl 1 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 2 - Lvl 2 & 3 A3.05 Building 3 Floor Plan 3 - Lvl 2 & 3 A3.06 Floor Plan 5 - Lvl 2 & 3 Building 5, 7 & 9 Floor Plan 5 - Lvl 1 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 Building 6 & 8, Floor 6 & 6* Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 8* - Lvl 1 Building 11, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 16, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 16, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 16, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 16, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 16, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 16, 16, 16, 16 Building 16, 17 Building 17 Building 17 Building 18, 17 Building 18, 18	A1.3	Site Plan - Retaining Wall Layout
A2.1 East Section View - Phase 3 Strata Road A2.2 Phase 2/3 Strata Road Transition A2.3 North Section View Phase 2/3 Strata Road Transition A2.4 North Section View - Strata Road Phase A2.5 Strata Road Phase 1 Fast Section View A3.01 Building 1 Floor Plan 1 Floor Plan 2 - Lvl 1 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 2 - Lvl 2 & 3 A3.05 Building 3 Floor Plan 3 - Lvl 2 & 3 A3.06 Floor Plan 5 - Lvl 2 & 3 Building 5, 7 & 9 Floor Plan 5 - Lvl 1 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 Building 6 & 8, Floor 6 & 6* Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 8* - Lvl 1 Building 11, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 16, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 16, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 16, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 16, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 16, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 16, 16, 16, 16 Building 16, 17 Building 17 Building 17 Building 18, 17 Building 18, 18	A2.0	North Section View - Delora Drive
A2.2 East Section View - Phase 2/3 Strata Road Transition A2.3 Phase 2/3 Strata Road Transition A2.4 North Section View Phase 2/3 Strata Road Transition A2.4 North Section View - Strata Road Phase A2.5 Strata Road Phase 1 East Section View A3.01 Building 1 Floor Plan 1 A3.02 Building 2 Floor Plan 2 - Lvl 1 A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 4 Building 5, 7 & 9 Floor Plan 5 - Lvl 1 A3.07 Floor Plan 5 - Lvl 1 A3.08 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 A3.08 Floor Plan 5 - Lvl 2 & 3 A3.08 Building 6 & 8, Floor 6 & 6* Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 1 A3.10 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 1 Building 10, 11 & 12 Floor Plan 7 & 8* - Lvl 1 A3.10 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A3.11 Floor Plan 8 & 8* - Lvl 1 A3.12 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building Exterior Colour Scheme Layout A4.02 Building 2 Exterior Elevations A4.03 Building 3 Exterior Elevations A4.04 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations		
A2.2 Phase 2/3 Strata Road Transition A2.3 North Section View Phase 2/3 Strata Road Transition A2.4 North Section View - Strata Road Phase A2.5 Strata Road Phase 1 East Section View A3.01 Building 1 Floor Plan 1 A3.02 Building 2 Floor Plan 2 - Lvl 1 A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 3 A3.05 Building 4 Floor Plan 4 A3.06 Floor Plan 5 - Lvl 2 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 Building 6 & 8, Floor 6 & 6* Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 Building 10, 11 & 12 Floor Plan 7 & 8* - Lvl 2 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A3.12 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 12 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 5 Exterior Elevations A4.05 Building 6 Exterior Elevations	1 2000	
A2.3 North Section View Phase 2/3 Strata Road Transition A2.4 North Section View - Strata Road Phase A2.5 Strata Road Phase 1 East Section View A3.01 Building 1 Floor Plan 1 East Section View A3.02 Building 2 Floor Plan 2 - Lvl 1 East Section View A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 East Section View A3.04 Building 3 Floor Plan 2 - Lvl 2 & 3 East Section View A3.05 East Section View Plan 5 East Section View A3.06 East Section View Plan 5 East Section View East East Section View East East Section View East East East Section View East East East Section View East East East East East Section View East East East East East East East East	A2.2	
A2.3 Phase 2/3 Strata Road Transition A2.4 North Section View - Strata Road Phase A2.5 Strata Road Phase I East Section View A3.01 Building 1 Floor Plan 1 A3.02 Building 2 Floor Plan 2 - Lvl 1 A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.05 Building 2 Floor Plan 3 A3.05 Building 5, 7 & 9 Floor Plan 5 - Lvl 1 A3.07 Floor Plan 5 - Lvl 2 & 3 A3.08 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 A3.08 Building 6, 7 & 9 Floor Plan 5 - Lvl 2 & 3 A3.08 Building 6, 7 & 9 Floor Plan 7 & VI 2 & 3 A3.09 Floor Plan 1 & 12 Floor Plan 7 & 7* - Lvl 1 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 A3.10 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 A3.11 Floor Plan 7 & 7* - Lvl 2 & 3 A3.12 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building Exterior Colour Scheme Layout A4.02 Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.04 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations	535490	
A2.4 North Section View - Strata Road Phase A2.5 Strata Road Phase 1 East Section View A3.01 Building 1 Floor Plan 1 A3.02 Building 2 Floor Plan 2 - Lvl 1 8 A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 3 A3.05 Building 4 Floor Plan 4 A3.06 Building 4 Floor Plan 4 A3.06 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 A3.08 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 A3.08 Building 6 & 8, Floor 6 & 6* A3.09 Floor Plan 7 & 7* - Lvl 2 & 3 A3.10 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 A3.12 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 12 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations	A2.3	
A2.5 Strata Road Phase 1 East Section View A3.01 Building 1 Floor Plan 1 A3.02 Building 2 Floor Plan 2 - Lvl 1 A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 2 - Lvl 2 & 3 A3.05 Building 4 Floor Plan 4 A3.06 Building 4 Floor Plan 4 A3.06 Floor Plan 5 - Lvl 1 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 A3.08 Building 6 & 8, Floor Plan 5 - Lvl 2 & 3 A3.08 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 8* - Lvl 2 & 3 A3.10 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A3.11 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 12 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.04 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations	A2.4	North Section View - Strata Road Phase 2
A3.01 Building 1 Floor Plan 1 A3.02 Building 2 Floor Plan 2 - Lvl 1 A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 3 - Lvl 2 & 3 A3.05 Building 3 Floor Plan 4 A3.06 Floor Plan 5 - Lvl 2 & 3 Building 5, 7 & 9 Floor Plan 5 - Lvl 1 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 Building 6 & 8, Floor 6 & 6* Building 6 & 8, Floor Plan 7 & 7* - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 8* - Lvl 1 Building 10, 11 & 12 Floor Plan 8 & 8* - Lvl 2 & 3 A3.11 Floor Plan 8 & 8* - Lvl 2 & 3 A3.12 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 10, 11 & 15 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 1 Exterior Elevations A4.03 Building 1 Exterior Elevations A4.04 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations	_	
A3.02 Building 2 Floor Plan 2 - Lvl 1 A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 3 A3.05 Building 4 Floor Plan 4 Building 4 Floor Plan 4 A3.06 Building 5 , 7 & 9 Floor Plan 5 - Lvl 2 & 3 A3.07 Floor Plan 5 - Lvl 2 & 3 A3.08 Building 6 & 8 , Floor 6 & 6* A3.09 Floor Plan 7 & 7* - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 3 Exterior Elevations A4.05 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations		A
A3.03 Building 2 Floor Plan 2 - Lvl 2 & 3 A3.04 Building 3 Floor Plan 2 - Lvl 2 & 3 A3.05 Building 4 Floor Plan 4 A3.06 Building 5, 7 & 9 Floor Plan 5 - Lvl 1 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 A3.08 Building 6 & 8, Floor Plan 5 - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 8, 7* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A3.10 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 16, 16, 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 16, 16, 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 16, 16, 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 16, 16, 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 16, 16, 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 16, 16, 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 16, 16, 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 16, 16, 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 16, 16, 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 15, 16, 17 Floor Plan 8 & 8* - Lvl 2 & 3	A3.01	
A3.04 Building 3 Floor Plan 3 A3.05 Building 4 Floor Plan 4 A3.06 Floor Plan 5 7 & 9 Floor Plan 5 - Lvl 1 A3.07 Floor Plan 5 - Lvl 2 & 3 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 A3.08 Floor Plan 5 - Lvl 2 & 3 Building 6 & 8, Floor 6 & 6* Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 8* - Lvl 1 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 12, Exterior Colour Scheme Layout A4.02 Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations	A3.02	
A3.05 Building 4 Floor Plan 4 Building 5, 7 & 9 Floor Plan 5 - Lvl 1 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 Building 6 & 8, Floor 6 & 6* Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 1 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 2 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations	A3.03	Building 2 Floor Plan 2 - Lvl 2 & 3
A3.06 Building 5, 7 & 9 Floor Plan 5 - Lvl 1 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 A3.08 Building 6 & 8, Floor 6 & 6* A3.09 Floor 9lan 7 & 7* - Lvl 1 A3.10 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A3.11 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 12 Exterior Elevations A4.01 Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 3 Exterior Elevations A4.05 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 3 Exterior Elevations	A3.04	Building 3 Floor Plan 3
A3.06 Floor Plan 5 - Lvl 1 Building 5, 7 & 9 Floor Plan 5 - Lvl 2 & 3 A3.08 Building 6 & 8, Floor 6 & 6* Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A3.11 Floor Plan 8 & 8* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations	A3.05	Building 4 Floor Plan 4
Floor Plan 5 - Lvl 1	A3.06	Building 5, 7 & 9
A3.07 Floor Plan 5 - Lvl 2 & 3 Building 6 & 8, Floor 6 & 6* Floor 8 6* Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 1 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 13, 14, 15, 26 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 Building 1 Exterior Colour Scheme Layout Building 1 Building 2 Exterior Elevations A4.03 Building 3 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations		Floor Plan 5 - Lvl 1
Roor Plan 5 - Lvl 2 & 3	A 2 0 7	Building 5, 7 & 9
A3.08 Floor 6 & 6* Building 10, 11 & 12 Floor Plan 7 & 27* - Lvl 1 Building 10, 11 & 12 Floor Plan 7 & 27* - Lvl 2 & 3 Building 10, 11 & 12 Floor Plan 7 & 27* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 13, 14, 15, 36 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building Exterior Colour Scheme Layout A4.02 Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations	M3.U7	Floor Plan 5 - Lvl 2 & 3
Floor 6 & 6*	A3 08	Building 6 & 8,
A3.09 Floor Plan 7 & 7* - Lvl 1 Building 10, 11 & 12 Floor Plan 7 & 7* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 A3.12 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building Exterior Colour Scheme Layout Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations	A3.06	Floor 6 & 6*
Floor Plan 7 & 7* - Lvl 1	A3.00	Building 10, 11 & 12
A3.10 Floor Plan 7 & 7* - Lvl 2 & 3 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building Exterior Colour Scheme Layout A4.02 Building 1 Exterior Elevations A4.03 Building 1 Exterior Elevations A4.04 Building 2 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations	A3.09	Floor Plan 7 &7* - Lvl 1
Floor Plan 7 & 7* - Lvl 2 & 3 A3.11 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 1 A3.12 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building Exterior Colour Scheme Layout A4.02 Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 3 Exterior Elevations	A3 10	Building 10, 11 & 12
A3.11 Floor Plan 8 & 8* - Lvl 1 A3.12 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building Exterior Colour Scheme Layout A4.02 Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations	10.10	Floor Plan 7 & 7* - Lvl 2 & 3
Floor Plan 8 & 8* - Lvl 1 Building 13, 14, 15, 16 & 17 Floor Plan 8 & 8* - Lvl 2 & 3 A4.01 Building Exterior Colour Scheme Layout A4.02 Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations	A3 11	
A4.01 Building Exterior Colour Scheme Layout A4.02 Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 3 Exterior Elevations	11.65	Floor Plan 8 & 8* - Lvl 1
A4.01 Building Exterior Colour Scheme Layout A4.02 Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations A4.05 Building 4 Exterior Elevations	42 12	Building 13, 14, 15, 16 & 17
A4.02 Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations	m3/JE	Floor Plan 8 & 8* - Lvl 2 & 3
A4.02 Building 1 Exterior Elevations A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations	A4.01	Building Exterior Colour Schome I wout
A4.03 Building 2 Exterior Elevations A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations		
A4.04 Building 3 Exterior Elevations A4.05 Building 4 Exterior Elevations	nime) manufacture	OWNERS OF THE PROPERTY OF THE
A4.05 Building 4 Exterior Elevations		
Control of the Contro	-	
MYLOU DUNUNING 3 EXTERIOR Elevations	-	The state of the s
A4.07 Building 8 Exterior Elevations		
A4.07 Building 8 Exterior Elevations A4.08 Building 12 Exterior Elevations	Name and Address of the Owner, where	
A4.09 Building 14 Exterior Elevations A4.09 Building 14 Exterior Elevations	-	The state of the s



PROFESSIONAL SEA	ALS
------------------	-----

Issued/Re	vised	
	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R
Drawn by:		




Sheet No:	A 0.0
Drawing Title:	Project Statistics
Scale:	

Project:

3494 Wishard Road Colwood BC

		rea 1 Finished Area 1 Finished Area 1 G	ross Lot Area 2 Finished Area 2 Finis	shed Area 2 Gross Lot Total Bedrooms		M4.03 Building 14 Excellor Elevator
V 32 N 200007400 720	-	Area Sq Ft Area Sq M Covera 71,748 6,665.6	e Sq M Area Sq Ft Area Sq 2,717.3 15,572 1,4	M Coverage Sq M 446.7 543.8 178		
	_	71	1			1+
			00000	2000	ATTEN ATTENDED	** **
	V MARY MAN	AN AN XX		DOODO	1 07	
		PH "ALLAN		7		
	The state of the s			To be seen a service where	8 4	450
3	Amenicans			8		
	The land of	THE STATE OF THE S				
		0 0 0 10	10			The second second
				9	X027	
			100		1	O TO
	16	14	1			a constant
						E 17 &
			11	ara l	6	Town t
2				7		la Ba
						Wist
						3
			S	Land Committee of the c		(1)
						4-PV Pers Tree
				CARTON AND		Tree
			12			4 4 3 +
	17 15	13		0		
				2		# For Ren
						W. C.
The state of the state of	Rand Card	MAKETA		271-1		
			THE WAR	HAD AND AND		
	and the control	+ 11 / 1			8 t t 40	# # # # # # # # # # # # # # # # # # #

Subdivision & Existing Site Plan






PROFESSIONAL SEALS

	Date	Description
15307	200000000000000000000000000000000000000	Control Control
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R1

Drawn by:



Sheet No:	A 0.1
Drawing Title:	Subdivision Plan Existing Site Plan
Scale:	Scale 1:400

Project:

3494 Wishard Road Colwood BC

Overall Site Plan



Refer to Landscape Plan for detailed tree planting quantity and species information.

Legend

Private Green Space

Private Amenity Space

Municipal Road Dedication


Wood Chip Trail

Environmental Conservation Area



PROFESSIONAL SEALS

	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R1



Sheet No:	A 1.0
Drawing Title:	Site Plan (Area 1 & 2)
Scale:	Scale 1:300

Project:

3494 Wishard Road Colwood BC


Site Plan - Strata Road (Phase 2 & 3)





PROFESSIONAL SEALS

Date	Description
08/07/2023	Rezoning
09/19/2023	Rezoning R1
08/09/2024	Development Permit
10/25/2024	Development Permit R1
	09/19/2023 08/09/2024



Sheet No:	A 1.1
Drawing Title:	Site Plan Area 1
Scale:	Scale 1:225

Project:

Drawn by:

3494 Wishard Road Colwood BC

Site Plan - Delora Drive (Phase 1)




Site Concept Plan Area 2 Scale 1:225



PROFESSIONAL SEALS

1 08/07/2023 Rezoning 2 09/19/2023 Rezoning R1		Date	Description
	1	08/07/2023	Rezoning
	2	09/19/2023	Rezoning R1
3 08/09/2024 Development Perm	3	08/09/2024	Development Permit
4 10/25/2024 Development Permit	4	10/25/2024	Development Permit R1

Drawn by:



Sheet No:	A 1.2
Drawing Title:	Site Plan Area 2
Scale:	Scale 1:200

Project:

3494 Wishard Road Colwood BC


Site Plan - Retaining Wall Layout





PROFESSIONAL SEALS

Issued/Re	evised	
	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R
Drawn by:		




Sheet No:	A 1.3
Drawing Title:	Retaining Wall Layout
Scale:	Scale 1:300

Project:

3494 Wishard Road Colwood BC

Delora Drive - North Section View








PROFESSIONAL SEALS

	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R




Sheet No:	A 2.0
Drawing Title:	North Section View - Delora Drive
Scale:	


Project:

3494 Wishard Road Colwood BC

Strata Road Phase 3 - East Section View




Strata Rd Phase 3
Scale 1:100





PROFESSIONAL SEALS

	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R*



Sheet No:	A 2.1
Drawing Title:	East Section View - Strata Rd Phase 3
Scale:	

Project:

(2) (A2.1)


Site Plan

Scale 1:200

Drawn by:

3494 Wishard Road Colwood BC

Strata Road Phase 2/3 Transition- East Section View



1 Strata Rd Phase 2/3 Transition A2.2 Scale 1:100






PROFESSIONAL SEALS

	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R1

Drawn by:



Sheet No:	A 2.2
Drawing Title:	East Section View - Phase 2/3 Strata Rd Transition
Scale:	


Project:

Site Plan


A2.2 Scale 1:200

3494 Wishard Road Colwood BC

Phase 2/3 Building Transition - North Section View



Phase 2/3 Building Transition
Scale 1:100




Site Plan
A2.3 Scale 1:200



PROFESSIONAL SEALS

1 08/07/2023 Rezoning 2 09/19/2023 Rezoning R1 3 08/09/2024 Development Permit 4 10/25/2024 Development Permit R		Date	Description
3 08/09/2024 Development Permit	1	08/07/2023	Rezoning
•	2	09/19/2023	Rezoning R1
4 10/25/2024 Development Permit R	3	08/09/2024	Development Permit
	4	10/25/2024	Development Permit R1




Sheet No:	A 2.3
Drawing Title:	North Section View - Phase 2/3 Building Transition
Scale:	

Project:


3494 Wishard Road Colwood BC

Strata Road Phase 2 - North Section View



Site Plan
Scale 1:200

Strata Rd Phase 2 A2.4 Scale 1:100






PROFESSIONAL SEALS

Issued/	Revised	
	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R

Drawn by:





A 2.4
North Section View - Strata Rd Phase 2
The same of the sa

Project:

3494 Wishard Road Colwood BC

Strata Road Entrance - East Section View










PROFESSIONAL SEALS

Issued/	Revised	
5	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R

Drawn by:




Sheet No:	A 2.5
Drawing Title:	East Section View - Strata Road Entrance
Scale:	


Project:


3494 Wishard Road Colwood BC

Building 1 (Plan 1) - Floor Plan

Legend Unfinished Area 438 Sq ft / 40.7 Sq M Level 1 Finished Area 860 Sq Ft / 79.9 Sq M Level 2 Finished Area 1298 Sq Ft / 120.6 Sq M Level 3 Flnished Area 1296 Sq Ft / 120.4 Sq M Total Finished Area 3454 Sq Ft / 320.9 Sq M (116.25+116.8+118.3+118.7)/4 = 117.51 m 8" Concrete Foundation Wall Average Existing Grade Roof Midpoint Elevation 126.90 m **Building Height** 9.39 M










PROFESSIONAL SEALS

	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R1



Sheet No:	A3.01
Drawing Title:	Building 1 Floor Plan 1
Scale:	1/5" = 1'0"

Project:


3494 Wishard Road Colwood BC

Building 2 (Plan 2) - Floor Plan

Legend 876 Sq ft / 81.4 Sq M Unfinished Area Level 1 Finished Area 1720 Sq Ft / 159.8 Sq M 2596 Sq Ft / 241.2 Sq M Level 2 Finished Area Level 3 Flnished Area 2592 Sq Ft / 240.8 Sq M 6908 Sq Ft / 641.8 Sq M Total Finished Area (117.1+119.25+119.4+120.2)/4 =118.99 m 8" Concrete Foundation Wall Average Existing Grade Roof Midpoint Elevation 128.40 m

9.41 M


Building Height





PROFESSIONAL SEALS

	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R1



Sheet No:	A3.02
Drawing Title:	Building 2 Floor Plan 2 - Lvl 1
Scale:	1/5" = 1'0"

Project:

3494 Wishard Road Colwood BC





Issued/I	Revised	
	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R
9		



No:	A3.03
Drawing Title:	Building 2 Floor Plan 2 - Lvl 2 & 3
Scale:	1/5" = 1'0"

3494 Wishard Road Colwood BC

Building 3 (Plan 3) - Floor Plan

Unfinished Area 660 Sq ft / 61.3 Sq M Legend

Level 1 Finished Area 1299 Sq Ft / 120.7 Sq M 226 stud at 18° o/c exterior wall (plan width 5.5°)

Level 2 Finished Area 1958 Sq Ft / 181.9 Sq M 2x4 stud at 24° o/c U.N.O interior wall (plan width 3.5°)

Level 3 Finished Area 1953 Sq Ft / 181.4 Sq M Double 2x4 stud at 24° o/c Unideng wall. 1° et gap Sound Absorptive Material 2 Side BCBC W13C STC 54, FR 1 HR

Average Existing Grade (119.7+120.15+120.8+121.3)/4 8° Concrete Foundation Well

Roof Midpoint Elevation 130.0 m

Roof Midpoint Elevation 130.0 m

Building Height 9.51M








PROFESSIONAL SEALS


1 08/07/2023 Rezoning 2 09/19/2023 Rezoning R1	
2 09/19/2023 Rezoning R1	
3 08/09/2024 Development Perr	nit
4 10/25/2024 Development Perm	it R



Sheet No:	A3.04	
Drawing Title:	Building 3 Floor Plan 3	
Scale:	1/5" = 1'0"	

Project:

3494 Wishard Road Colwood BC





Building 4 (Plan 4) - Floor Plan


Legend 410 Sq ft / 38.1 Sq M Unfinished Area 2x6 stud at 16" o/c exterior wall (plan width 5.5") 926 Sq Ft / 86.0 Sq M Level 1 Finished Area Level 2 Finished Area 1073 Sq Ft / 99.7 Sq M Level 3 Finished Area 1287 Sq Ft / 119.6 Sq M Double 2x4 stud at 24" o/c Dividing wall, 1" air gap Sound Absorptive Material 1 Side BCBC W13C STC 54, FR 1 HR Total Finished Area 3286 Sq Ft / 305.4 Sq M 8" Concrete Foundation Wall (90.1+90.4+92.2+92.4)/4 Average Existing Grade 101.90 m Roof Midpoint Elevation


10.62 m


Building Height














PROFESSIONAL SEALS

	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R

Drawn by:



Sheet No:	A3.05	
Drawing Title:	Building 4 Floor Plan 4	
Scale:	1/5" = 1'0"	

Project:

3494 Wishard Road Colwood BC

Building 5 (Plan 5) - Floor Plan

Legend Unfinished Area 872 Sq ft / 81.0 Sq M 2x6 stud at 16" o/c exterior wall (plan width 5.5") Level 1 Finished Area 1708 Sq Ft / 158.6 Sq M Level 2 Finished Area 2578 Sq Ft / 239.4 Sq M 2x4 stud at 24" o/c U.N.O interior wall (plan width 3.5") Level 3 Finished Area 2558 Sq Ft / 237.6 Sq M Double 2x4 stud at 24" o/c Dividing wall, 1" air gap Sound Absorptive Material 1 Side BCBC W13C STC 54, FR 1 HR Total Finished Area 6844 Sq Ft / 635.8 Sq M Average Existing Grade (95.8+98.0+98.2+99.6)/4 =97.90 m Roof Midpoint Elevation 105.80 m

Building 7 (Plan 5*) - Composed of Units C & D from Building 5

7.90 m

10.06 m

Building Height

Building Height

Building Height

Building 9 (Plan 5*) - Composed of Units B, C & D from Building 5

Unfinished Area 654 Sq ft / 60.8 Sq M

Level 1 Finished Area 1281 Sq Ft / 119.0 Sq M

Level 2 Finished Area 1934 Sq Ft / 179.6 Sq M


Level 3 Finished Area 1918 Sq Ft / 178.2 Sq M


Total Finished Area 5133 Sq Ft / 476.9 Sq M

Average Existing Grade (95.85+96.9+98.1+99.8)/4 = 97.66 m

Roof Midpoint Elevation 107.80 m

10.14 m








PROFESSIONAL SEALS


	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R



Sheet No:	A3.06
Drawing Title:	Building 5, 7 & 9, Lvl 1 Floor Plan 5 & 5*
Scale:	1/5" = 1'0"

Project:

3494 Wishard Road Colwood BC



Building 8 (Plan 6) - Floor Plan

Unfinished Area 410 Sq ft / 38.1 Sq M Level 1 Finished Area 926 Sq Ft / 86.0 Sq M Level 2 Finished Area 1255 Sq Ft / 116.6 Sq M 1500 Sq Ft / 139.4 Sq M Level 3 Flnished Area Total Finished Area 3681 Sq Ft / 342.0 Sq M (92.0+92.2+94.0+94.2)/4 =93.10 m Average Existing Grade

103.80 m Roof Midpoint Elevation **Building Height** 10.70 m

Building 6 (Plan 6*) - Composed of Units A, B, A, B (4 total) from Building 6

Unfinished Area 820 Sq ft / 76.2 Sq M Level 1 Finished Area

1852 Sq Ft / 172.0 Sq M

Level 2 Finished Area 2510 Sq Ft / 233.2 Sq M Level 3 Flnished Area 3000 Sq Ft / 278.8 Sq M

Total Finished Area 7362 Sq Ft / 684.0 Sq M

Average Existing Grade

(89.6+89.7+93.4+94.2)/4 =91.73 m


Legend


Double 2x4 stud at 24" o/c Dividing wall, 1" air gap Sound Absorptive Material 1 Side BCBC W13C STC 54, FR 1 HR


8" Concrete Foundation Wall

Roof Midpoint Elevation 102.36 m

10.63 m **Building Height**










PROFESSIONAL SEALS

	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R1



Sheet No:	A3.08
Drawing Title:	Building 6 & 8, Floor Plan 6 & 6*
Scale:	1/5" = 1'0"

Project:

3494 Wishard Road Colwood BC

Building 12 (Plan 7) - Floor Plan

Unfinished Area 820 Sq ft / 76.2 Sq M

Level 1 Finished Area 1852 Sq Ft / 172.0 Sq M

Level 2 Finished Area 2510 Sq Ft / 233.2 Sq M Level 3 Flnished Area 3000 Sq Ft / 278.8 Sq M

Total Finished Area 7362 Sq Ft / 684.0 Sq M

(101.3+102.5+103.4+103.8)/4 Average Existing Grade

=102.75 m

Roof Midpoint Elevation 112.31 m

Building Height 9.56 m



Building 10 & 11 (Plan 7*) - Composed of Units C & D from Building 12

Unfinished Area 410 Sq ft / 38.1 Sq M 926 Sq Ft / 86.0 Sq M Level 1 Finished Area 1255 Sq Ft / 116.6 Sq M Level 2 Finished Area 1500 Sq Ft / 139.4 Sq M Level 3 Flnished Area 3681 Sq Ft / 342.0 Sq M Total Finished Area

Building 10

(100.8+102.1+103.4+104.5)/4 Average Existing Grade

Roof Midpoint Elevation 112.01 m 9.31 m

Building Height


Building 11

(100.7+101.0+103.2+103.4)/4 Average Existing Grade

112.31 m Roof Midpoint Elevation

10.23 m **Building Height**








PROFESSIONAL SEALS

	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R*



Sheet No:	A3.09
Drawing Title:	Building 10, 11 & 12 Lvl 1, Floor Plan 7 & 7*
Scale:	1/5" = 1'0"

Project:

3494 Wishard Road Colwood BC



Unit B

Unit C

Unit A



	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R1



No:	A3.10
Drawing Title:	Building 10, 11 & 12 Lvl 2 &3, Floor Plan 7 & 7
Scale:	1/5" = 1'0"

Colwood BC

50 Townhouse Unit Development

LIVING AREA 749 SQ FT Unit D

Building 14, 15 & 16 (Plan 8) - Floor Plan

Unfinished Area 880 Sq ft / 81.8 Sq M

Level 1 Finished Area 1694 Sq Ft / 157.4 Sq M

Level 2 Finished Area 2574 Sq Ft / 239.2 Sq M

Level 3 Finished Area 2556 Sq Ft / 237.4 Sq M

Total Finished Area 6824 Sq Ft / 634.0 Sq M

Building 14 Height Calculations

Average Existing Grade (105.7+106.3+109.6+110.3)/4

=107.98 m

Roof Midpoint Elevation 117.30 m

Building Height 9.32 m

Building 15 Height Calculations

Average Existing Grade (106.8+107.0+109.5+110.2)/4

=108.38 n

Roof Midpoint Elevation 118.80 m

Building Height 10.42 m

Building 16 Height Calculations


Average Existing Grade (110.1+110.7+114.7+115.9)/4

=112.85 m

Roof Midpoint Elevation 121.70 m

Building Height 8.85 m

Legend 2x6 stud at 16" orc exterior wall (plan width 5.5") 2x4 stud at 24" orc U.N.O inferior wall (plan width 3.5") Double 2x4 stud at 24" orc Dividing wal, 1" air gap Sound Absorptive Material 1 Side BCBC W13C STC 54, FR 1 HR



Level One 1/5" = 1' 0"

Building 13 & 17 (Plan 8*) - Composed of Units A & B from Building 14

440 Sq ft / 40.9 Sq M

 Level 1 Finished Area
 847 Sq Ft / 78.7 Sq M

 Level 2 Finished Area
 1287 Sq Ft / 119.6 Sq M

 Level 3 Finished Area
 1278 Sq Ft / 118.7 Sq M

Total Finished Area 3412 Sq Ft / 317.0 Sq M

Building 13 Height Calculations

Unfinished Area

Average Existing Grade (105.2+105.3+106.5+106.7)/4

=105.93 m

Roof Midpoint Elevation 116.22 m

Building Height 10.29 m

Building 17 Height Calculations

Average Existing Grade (109.4+111.0+112.2+113.3)/4

=111.48 m


Roof Midpoint Elevation 121.22 m

Building Height 9.74 m



PROFESSIONAL SEALS

	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R




Sheet No:	A3.11
Drawing Title:	Building 13-17 Lvl 1, Floor Plan 8 & 8*
Scale:	1/5" = 1'0"

Project:


3494 Wishard Road Colwood BC


Building 14 (Plan 8) - Floor Plan














PROFESSIONAL SEALS

	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R

Drawn by:



Sheet No:	A3.12
Drawing Title:	Building 13-17 Lvl 2 Lvl 3, Floor Plan 8 & 8*
Scale:	1/5" = 1'0"

Project:

3494 Wishard Road Colwood BC

Building Exterior Colour Scheme Layout



Colour Scheme #1

1	Trim	BM OC-65 Chantilly Lace
2	Unit A & C Hardi Plank	BM 1608 Ashland Slate
3	Unit A & C Hardi Shingles	BM 1608 Ashland Slate
4	Unit A & C Hardi Board and Batten	BM 1608 Ashland Slate
5	Unit B & D Hardi Plank	BM HC-169 Coventry Gray
6	Unit B & D Hardi Shingles	BM HC-169 Coventry Gray
7	Unit B & D Hardi Board and Batten	BM HC-169 Coventry Gra
8	Asphalt Shingles	Midnight Black
9	Fir Timbers & Front Door	Teak Stain/BM 1232 Fresh Brew
10	Hardi Shingles - Gable	BM 1232 Fesh Brew
10	Vinyl Windows	White

Colour Scheme #2

1	Trim	BM OC-65 Chantilly Lace
2	Unit A & C Hardi Plank	BM HC-178 Charcoal Slate
3	Unit B & D Hardi Plank	BM OC-52 Gray Owl
4	Unit A & C Hardi Shingles	BM HC-178 Charcoal Slate
5	Unit B & D Hardi Shingles	BM OC-52 Gray Owl
6	Unit A & C Hardi Board and Batten	BM HC-178 Charcoal Slate
7	Unit B & D Hardi Board and Batten	BM OC-52 Gray Owl
8	Asphalt Shingles	Midnight Black
9	Fir Timbers & Front Door	Teak Stain/BM 1232 Fresh Brew
10	Hardi Shingles - Gable	BM 1232 Fesh Brew
11	Vinyl Windows	White

Colour Scheme #3

7:	Inm	BM OC-65 Chantilly Lace
2	Unit A & C Hardi Plank	BM HC-168 Chelsea Grey
3	Unit B & D Hardi Plank	SW 7069 Iron Ore
4	Unit A & C Hardi Shingles	BM HC-168 Chelsea Grey
5	Unit B & D Hardi Shingles	SW 7069 Iron Ore
6	Unit A & C Hardi Board and Batten	BM HC-168 Chelsea Grey
7	Unit B & D Hardi Board and Batten	SW 7069 Iron Ore
8	Asphalt Shingles	Midnight Black
9	Fir Timbers & Front Door	Teak Stain/BM 1232 Fresh Brew
10	Hardi Shingles - Gable/Sideyard	BM 1232 Fresh Brew
11	Vinyl Windows	White

Colour Scheme #4

Trim BM OC-65 Chantilly Lace
Unit A & C Hardi
Plank
Unit B & D Hardi
Plank
Unit B & C Hardi
Plank
Unit A & C Hardi
CD 8434 Silver Spree
Unit A & C Hardi
Shingles
CD 8432 Garden Bench

Shingles
Unit B & D Hardi
CD 8434 Silver Spree

9 Front Door 10 Hardi Shakes - BM 1232 Fresh Brew

10 Gable BM 123 11 Vinyl Windows White

Unit B & D hardi Shingles
Unit A & C Hardi Board and Batten
Unit B & D Hardi Board and Batten
CD 8434 Silver Spree
Unit B & D Hardi Board and Batten
CD 8432 Garden Bench
Asphalt Shingles
Midnight Black
Fir Timbers &
Front Door
Teak Stain/BM 1232 Fresh Brew


10	1 nm	BM OC-65 Chantilly Lace
2	Unit A & C Hardi Plank	BM HC-168 Chelsea Grey
3	Unit B & D Hardi Plank	SW 7069 Iron Ore
1	Unit A & C Hardi Shingles	BM HC-168 Chelsea Grey
5	Unit B & D Hardi Shingles	SW 7069 Iron Ore
3	Unit A & C Hardi Board and Batten	BM HC-168 Cheisea Grey
,	Unit B & D Hardi Board and Batten	SW 7069 Iron Ore
3	Asphalt Shingles	Midnight Black
,	Fir Timbers & Front Door	Teak Stain/BM 1232 Fresh Brew
0	Hardi Shingles - Gable/Sideyard	BM 1232 Fresh Brew
11	Vinyl Windows	White

See exterior elevations A4.02-A4.09 for additional detail on building exteriors colours



PROFESSIONAL SEALS

	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R




Sheet No:	A4.01
Drawing Title:	Building Exterior Colour Schemes
Scale:	1:300


Project:

3494 Wishard Road Colwood BC

Building 1 (Plan 1) - Elevations



Building Height: 9.39 M





1	Asphalt Shingles
2	2x8 Comb Face Fascia
3	Vinyl Window
4	Prefinished Aluminum Gutter
5	Hardi Shakes
6	Window Flashing
7	Hardi Board and Batten
8	2x10 Comb Face Belly Band
9	1x4 Window Trim
10	Insulated Fiberglass Door
11	4x6 Doulgas Fir Timbers
12	Wood T&G Soffit
13	Combface Corner Boards
14	Hardi Lap Siding, 7" Reveal
15	8" Concrete Foundation Wall
16	Insulated Steel Garage Door
17	French Door
18	Vented Aluminum Soffit


Colour Scheme #1

1	Trim	BM OC-65 Chantilly Lace
2	Unit A Hardi Plank	BM 1608 Ashland Slate
3	Unit A Hardi Shingles	BM 1608 Ashland Slate
4	Unit A Hardi Board and Batten	BM 1608 Ashland Slate
5	Unit B Hardi Plank	BM HC-169 Coventry Gray
6	Unit B Hardi Shingles	BM HC-169 Coventry Gray
7	Unit B Hardi Board and Batten	BM HC-169 Coventry Gra
8	Asphalt Shingles	Midnight Black
9	Fir Timbers & Front Door	Teak Stain/BM 1232 Fresh Brew
10	Hardi Shingles - Gable	BM 1232 Fesh Brew
10	Vinyl Windows	White



PROFESSIONAL SEALS

	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R1
Drawn by:		



Sheet No:	A4.02
Drawing Title:	Building 1 Exterior Elevations
Scale:	1/5" = 1'0"

Project:

3494 Wishard Road Colwood BC





Building 4 (Plan 4) - Elevations







PROFESSIONAL SEALS


1	Asphalt Shingles	Ī
2	2x8 Comb Face Fascia	-
3	Vinyl Window	
4	Prefinished Aluminum Gutter	
5	Hardi Shakes	
6	Window Flashing	
7	Hardi Board and Batten	7
3	2x10 Comb Face Belly Band	
9	1x4 Window Trim	
10	Insulated Fiberglass Door	
11	6x6 Douglas Fir Timbers	1
12	Wood T&G Soffit	
13	Combface Corner Boards	
14	Hardi Lap Siding, 7" Reveal	
15	8" Concrete Foundation Wall	
16	Insulated Steel Garage Door	
17	French Door	
18	Vented Aluminum Soffit	
19	Aluminum & Glass Railing	

Material Legend

Colour Scheme #2

1	Trim	BM OC-65 Chantilly Lace
2	Hardi Plank Unit A	BM HC-178 Charcoal Slate
3	Hardi Plank Unit B	BM OC-52 Gray Owl
4	Hardi Shingles Unit A & B	BM HC-169 Coventry Gray
5	Hardi Board and Batten Unit A	BM HC-178 Charcoal Slate
6	Hardi Board and Batten Unit B	BM OC-52 Gray Owl
7	Asphalt Shingles	Midnight Black
8	Fir Timbers & Front Door	Teak Stain
9	Vinyl Windows	White

1	08/07/2023	Rezoning
	Water Comment	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R1




Sheet No:	A4.05
Drawing Title:	Building 4 Exterior Elevations
Scale:	1/5" = 1'0"

Project:


3494 Wishard Road Colwood BC



Building 8 (Plan 6) - Elevations



Building Height: 10.70 M





PROFESSIONAL SEALS

1	Asphalt Shingles
2	2x8 Comb Face Fascia
3	Vinyl Window
4	Prefinished Aluminum Gutter
5	Hardi Shakes
6	Window Flashing
7	Hardi Board and Batten
8	2x10 Comb Face Belly Band
9	1x4 Window Trim
10	Insulated Fiberglass Door
11	6x4 Douglas Fir Rafters
12	Wood T&G Soffit
13	Combface Corner Boards
14	Hardi Lap Siding, 7" Reveal
15	8" Concrete Foundation Wall
16	Insulated Steel Garage Door
17	French Door
18	Vented Aluminum Soffit
19	8x8 Douglas Fir Post
20	Aluminum & Glass Railing


Material Legend

Colour Scheme #4

1	Trim	BM OC-65 Chantilly Lace
2	Unit A & B Hardi Plank	CD 8432 Garden Bench
3	Unit A Hardi Shingles	CD 8432 Garden Bench
4	Unit B Hardi Shingles	CD 8434 Silver Spree
5	Unit A Hardi Board and Batten	CD 8434 Silver Spree
6	Unit B Hardi Board and Batten	CD 8432 Garden Bench
7	Asphalt Shingles	Midnight Black
8	Fir Timbers & Front Door	Teak Stain/BM 1232 Fresh Brew
9	Vinyl Windows	White
10	Unit A & B Hardi Shingles - Gable	BM 1232 Fresh Brew

	Date	Description
1	08/07/2023	Rezoning
2	09/19/2023	Rezoning R1
3	08/09/2024	Development Permit
4	10/25/2024	Development Permit R1

Drawn by:



Sheet No:	A4.07
Drawing	Building 8
Title:	Exterior Elevations
Scale:	1/5" = 1'0"

Project:

3494 Wishard Road Colwood BC

50 Townhouse Unit Development












Tree Preservation Plan - 3494 Wishart Road











Prepared by LADR Landscape Architects

#3-864 QUEENS AVE VICTORIA, BC V8T 1M5 P. 250.598.0105 ADMIN@LADRLA.CA WWW.LADRLA.CA

Exclusive of GST

02-Jan-25

3494 Wishart Road Landscape Bondi	ng Budget		
A. SOFT LANDSCAPE	Quantity Units	Price	Extension
1. PLANTS			
Trees (4cm caliper)	141 each	\$455.00	\$64,155.00
Shrubs (#10 pot)	10 each	\$142.50	\$1,425.00
Shrubs (#7 pot)	30 each	\$100.00	\$3,000.0
Shrubs (#5 pot)	282 each	\$70.00	\$19,740.0
Shrubs (#3 pot)	32 each	\$55.00	\$1,760.0
Shrubs, Groundcovers and Perennials (#1 pot)	695 each	\$16.50	\$11,467.5
Shrubs, Groundcovers and Perennials (#SP4 pot)	216 each	\$8.00	\$1,728.0
SUB-TOTAL PLANTS			\$103,275.5
3. GRASS			
Restoration Area Meadow Seed Mix	1164 m.sq.	\$4.00	
Hydroseed	3839 m.sq.	\$4.00	
SUB-TOTAL GRASS			\$20,012.0
2. SOIL	400	#20.00	#45 550 0
Soil (Trees & Planting Beds) 450-600mm depth	486 m.cu.	\$32.00	
Soil (Lawn) 150mm depth	575 m.cu	\$32.00	
Mulch (All Beds) 100mm depth	81 m.cu.	\$40.00	
SUB-TOTAL SOIL			\$37,192.0
SUBTOTAL SOFT LANDSCAPE			\$160,479.5
B. HARD LANDSCAPE			
1. IRRIGATION ALLOWANCE			\$20,000.00
2. WOOD FIBER			
Wood Chip Surface (300mm depth)	53 m.cu.	\$60.00	
SUB-TOTAL WOOD FIBER			\$3,180.0
3. AGGREGATE AND SURFACING			
River Rock (155mm depth)	36 m.cu.	\$98.00	\$3,528.0
1/4" Granite Fines (155m depth)	38 m.cu.	\$65.40	
SUB-TOTAL AGGREGATE & SURFACING	oo 111.0a.	\$00.10	\$6,013.2
4. SITE FURNISHINGS AND AMENITIES			
Playground Allowance			\$5,000.0
Community Garden Allowance			\$2,000.0
Restoration Area Sign (By Others)			\$2,000.0
SUB-TOTAL SITE FURNISHINGS			\$9,000.0
SUB-TOTAL SITE FURNISHINGS			φ9,000.0
SUBTOTAL HARD LANDSCAPE			\$38,193.20
TOTAL LANDSCAPE BUDGET ESTIMATE			\$198,672.70
		1989	Ţ.55,0, 2. 11,

Prices include labour and materials. For bonding purposes only; this is not a construction estimate.

Schedule 4







ENVIRONMENTAL ASSESSMENT

FOR 3494 WISHART ROAD, COLWOOD BC

PREPARED FOR: DAVID LUNN WALKING STICK DEVELOPMENTS INC. 7401 VEYANESS ROAD SAANICHTON, BC, V8M 1V9

AND

CITY OF COLWOOD 3300 WISHART ROAD COLWOOD, BC, V9C 1R1

CORVIDAE PROJECT #2023-038 MAY 2023



SOLUTION ORIENTED. PROTECTION OF THE ENVIRONMENT. ABSOLUTE INTEGRITY. OPEN COMMUNICATION. RESPECT.

TABLE OF CONTENTS

1 IN	ITRODUCTION	1
1.1	OBJECTIVES	
1.2	REGULATORY FRAMEWORK	
1.3	DEVELOPMENT PERMIT AREAS	
	COPE OF WORK	
	ETHODS	
3.1	DESKTOP REVIEW	senanang
	NVIRONMENTAL SITE ASSESSMENT	
4 Er	LAND USE	
4.2	CLIMATE AND BIOGEOCLIMATIC ZONE	
4.3	TERRAIN AND SOILS	
4.4	SURFACE WATER	
4.5	VEGETATION	
4.6 4.7	WILDLIFE	
93757	OTENTIAL ENVIRONMENTAL EFFECTS	
	ECOMMENDED ENVIRONMENTAL PROTECTION MEASURES	
	ONCLUSION	
	EFERENCES	
APPE	NDIX A – SITE PHOTOGRAPHS	22
	LIST OF TABLES	
Table	Plant species observed on site during the April 4, 2023 field visit.	10
Table 2	Wildlife species observed on site during the April 4, 2023 field visit	12
	3. Species at risk that may occur in the vicinity of 3494 Wishart Road, Colwood, BC	
	4. Recommended native vegetation to plant in disturbed areas and within green space	
Table :	5. Removal and disposal methods for invasive species	16
	LIST OF FIGURES	
Figure	Site Location and Environmental Features	2
	2. City of Colwood Development Permit Areas and Mapped Potential Sharp-Tailed Snake Hab	
	3. Proposed Development Site Plan	
The grant of the same	4. Species and ecosystems at risk occurrences in the vicinity of the Site	13
		7

LIST OF PHOTOS

Photo 1. View west from driveway off Wishart Road. April 4, 2023.	22
Photo 2. Front of the Site along Wishart Road (view northeast) with rocky outcrop in the fore April 4, 2023.	
Photo 3. Middle of the Site with forested area in background (view northwest). April 4, 2023	23
Photo 4. Middle of the Site (view north). April 4, 2023.	23
Photo 5. Treed area near middle of Site at north boundary (view south). April 4, 2023	24
Photo 6. Western forested area with Scotch broom in understory (view west). April 4, 2023	24
Photo 7. Edge of forested area (view south). April 4, 2023.	25
Photo 8. Open area east of forest (view south). April 4, 2023.	25
Photo 9. Rocky outcrop east of forest (view southwest). April 4, 2023.	26
Photo 10. Rocky outcrop at northwest corner (view north). April 4, 2023	26
Photo 11. Typical view of understory within sharp-tailed snake polygon. April 4, 2023	27
Photo 12. Typical view of understory within sharp-tailed snake polygon. April 4, 2023	27
Photo 13. Small rocky outcrop near Delora Road (view north). April 4, 2023	28
Photo 14. View of ditch from south boundary looking northeast. April 4, 2023	28
Photo 15. View of ditch from north boundary looking southwest. April 4, 2023	29

CAVEAT

This Environmental Assessment (EA) has been prepared with the best information available at the time of writing, including the City of Colwood Official Community Plan, communications with the client, a site visit, review of site plans and design drawings and other documentation relevant to the project. This EA has been developed to assist the project in remaining in compliance with relevant environmental regulations, acts and laws pertaining to the project and to identify and mitigate the expected impacts of the project.



1 INTRODUCTION


Corvidae Environmental Consulting Inc. (Corvidae) is pleased to provide this Environmental Assessment (EA) for a rezoning application and proposed residential development at 3494 Wishart Road in Colwood, BC (the Site) (PID: 005-210-089; LOT 3, PLAN 10219). The Site is currently zoned as Rural 1 (A1). Site boundaries and environmental features are presented in Figure 1.

Currently on the Site is an existing dwelling, several accessory structures, and a horse paddock area. The Site has been cleared of natural vegetation in many areas and has been highly impacted by invasive species. The western extent remains forested, and several rocky outcrops occur throughout the Site. A polygon that represents potential habitat for sharp-tailed snake is mapped in the west (Figure 2). The potential for sharp-tailed snake to occur in this area is considered low based on habitat characteristics (see Section 4.6 of this report for further details). The Site occurs within two Development Permit Areas (DPA), the Hillside Environmental DPA and Natural Hazards DPA (Figure 2).

The landowner is proposing to rezone the Site to allow for a future 49-unit townhouse development. Several areas of green space will be retained as part of the development, particularly at the western boundary where habitat value is greater. An extension of Delora Drive, a public road, is planned in the western extent. The Site plan is presented in Figure 3.

This document addresses the requirements outlined in Part D of the City of Colwood Bylaw No. 1700, provides a detailed assessment on the environmental conditions on the Site, potential impacts of the proposed development, and recommendations for the protection of environmentally sensitive features and methods to minimize impacts of the proposed development.







1.1 OBJECTIVES

The purpose of this EA is to assess the current terrestrial and riparian environments onsite, identifying terrestrial and aquatic habitat, sensitive ecosystems, and wildlife habitat, including wildlife trees, nests, and any other wildlife features. This EA also identifies the presence of threatened or endangered species on or around the Site, which includes a 2-kilometre (km) buffer around the Site boundaries. As part of the EA, Corvidae completed a detailed field assessment to document biophysical features, habitat and verify available ecosystem inventory data.

From this information potential impacts have been determined and mitigations provided to protect the natural environment, its ecosystems and associated biological diversity. This report and planning meet the environmental requirements in the City of Colwood Official Community Plan, zoning by-laws and addresses provincial and federal laws.

1.2 REGULATORY FRAMEWORK

This environmental assessment is designed to comply with the provisions set out in the City of Colwood Official Community Plan (OCP) for development permit areas and for compliance with the provisions for environmental protection contained in the following relevant legislation:

Municipal

City of Colwood OCP, Bylaw No. 1700 (City of Colwood 2018)

Hillside DPA

Objectives

- 19.1.q. Protect wildlife habitat and corridors, and environmentally sensitive areas on hillsides
- 19.1.r. Identify significant features prior to development, and protect hillside character and natural features
- 19.1.s. Conserve unique natural features such as landforms, rock outcrops, mature trees and vegetation, hilltops, and ridge lines.
- 19.1.t. Minimize blasting and re-contouring of hillsides.

Guidelines

- 22.1.a. Open space and corridors between development areas or lots should be retained to provide continuous habitat linkages within the site and surrounding area. Significant features such as rock outcrops, streams, cliffs, and stands of trees should be incorporated into the open space and corridors as much as possible.
- 22.1.b. Windfirm treed buffers must be maintained between the subject parcel and adjacent lots, and should also be applied along major roads fronting the development.
- 22.1.c. Where trees are not present, and soils are suitable, new trees which are native to the Coastal Douglas-Fir Biogeoclimatic Zone must be planted.
- 22.1.g. Post-development, exposed soil on steep slopes subject to erosion shall be re-vegetated with vegetation native to the Coastal Douglas-Fir Biogeoclimatic zone or otherwise protected from run-off erosion.

- 22.1.h. Avoid using fast-growing non-native plants to retain soils. Temporary erosion control measures must be maintained during and post-construction until native vegetation is re-established and capable of protecting slopes from erosion.
- 22.1.i. Avoid tree removal on steep slopes. Trees intercept precipitation and reduce stormwater runoff volumes, protect soils from erosion, and protect the scenic quality of the community.
- 22.1.k. Do not clear more trees and vegetation than is necessary to install services for any given phase of the development.
- 22.1.I. Take advantage of topography and minimize disruption of rock outcroppings, sensitive ecosystems, mature trees and culturally significant features.
- 22.1.m. Design sites to incorporate, protect and enhance remnant riparian zones, watercourses, and urban forests and to optimize opportunities to establish new ecological connections through the site, such as urban forest corridors and watercourses.

Natural Hazards DPA

Objectives

- 19.1.u. Protect lives and property from hazardous conditions such as landslides and erosion by avoiding development on unstable or hazardous areas.
- 19.1.v. Protect people and development from flooding and erosional processes associated with extreme weather events and potential sea level rise in ways that do not lead to hardening of shorelines and loss of environmental and recreational values.
- 19.1.w. Protect lives and property from interface wildfire.

Guidelines

- 23.1.a. Development on lands with slopes greater than 30% must be avoided. Development may be considered on slopes greater than 30% only where it can be demonstrated that the proposed development will not create geotechnical, ecological, or visual impacts, can be sensitively integrated with terrain, and presents no hazards to people or property.
- 1.b. Grading or alteration of key topographic features such as knolls, ridgelines, rocky outcrops, cliffs, and ravines must be avoided.

The guiding principle for the use of Development Permits is found within the Local Government Act. Development Permit Areas can be designated for purposes such as, but not limited to: protecting, enhancing and restoring the biodiversity and ecological values and functions of environmentally sensitive areas; fostering compatibility between development, existing land uses and environmentally sensitive areas; maintaining connectivity between sensitive ecosystems; and protecting water quality and quantity.

Provincial

- Wildlife Act (1996)
- Invasive Species Council of BC
- . Weed Control Act (1996, current as of October 2016)



Federal

- Migratory Birds Convention Act (1994)
- Species at Risk Act (SARA) (2002)

1.3 DEVELOPMENT PERMIT AREAS

As per Figure 18 and 19 of the City of Colwood OCP, the Site occurs within the Hillside Environmental DPA, and Natural Hazards DPA. Development Permit Area boundaries on the Site are presented in Figure 2.

The objectives of the Natural Hazards DPA include the protection of lives and property from hazardous conditions, potential erosion and flooding associated with extreme weather events and sea-level rise, and wildfire. Commentary regarding development requirements to ensure human safety and slope stability within the Natural Hazards DPA on the Site will not be included in this report. As plans progress, a geotechnical evaluation (submitted separately) prepared by a registered geotechnical professional is required to certify that the site is safe for its intended use.

2 SCOPE OF WORK

Corvidae completed an environmental assessment for the Site and documented the ecological features. Background information was reviewed, including applicable databases. The following features were documented and provided in this report:

- Areas of sensitivity, including mapped potential sharp-tailed snake habitat.
- · Areas of habitat and biodiversity values, including rocky outcrops.
- · Plant communities and plant species on site.
- Potential wildlife presence and wildlife habitat.
- Soil types and terrain.
- Surface water flow patterns.

Following the field assessment, the biophysical features were mapped, and buffer areas have been identified. Mitigations to minimize the impacts of the proposed residential development on the environment have been provided in Section 6.

3 METHODS

3.1 DESKTOP REVIEW

Baseline biophysical conditions were compiled by reviewing the best available data and information including existing reports for the area and conducting searches of online provincial and federal databases:

- BC Conservation Data Centre (BC CDC 2023a and 2023b).
- BC HabitatWizard (Province of BC 2023).
- · Aerial photographs of the Site (Google Earth 2023).
- CRD mapping system and database (CRD 2023).
- City of Colwood GIS Mapping (City of Colwood n.d.)
- Colwood Official Community Plan Bylaw No. 1700 (City of Colwood 2018).

3.2 FIELD ASSESSMENT

A field assessment of the Site was completed by a Qualified Environmental Professional (QEP) from Corvidae. The assessment included characterization of vegetation and habitat types, wildlife sign and species observations, wildlife habitat, surface water flow patterns, and assessed the current conditions of the Site.



4 ENVIRONMENTAL SITE ASSESSMENT

Corvidae completed a site visit on April 4, 2023. Site photographs are included as Appendix A.

4.1 LAND USE

A primary residence and various accessory structures are present within the Site. Open areas (grass lawn), and a horse paddock area are located in the eastern portion, closest to Wishart Road. Surrounding land use is primarily rural residential and higher density residential. The Site is bound by residential properties to the north, and by Wishart Road to the east. To the south is a residential development undergoing construction, and to the west is a large rural property that borders Havenwood Park.

4.2 CLIMATE AND BIOGEOCLIMATIC ZONE

The project is located within the Coastal Douglas-fir (CDF) biogeoclimatic zone, specifically in the Moist Maritime Coastal Douglas-fir Subzone (CDFmm) (BC CDC 2023b). The CDFmm occurs at low elevations (<150 m) along southeast Vancouver Island, the southern Gulf Islands, and part of the Sunshine Coast. The CDFmm has the mildest climate in Canada. This subzone has a long growing season with warm, dry summers and mild, wet winters.

4.3 TERRAIN AND SOILS

Soils in the CDF biogeoclimatic zone are generally derived from morainal, colluvial, and marine deposits, and are typically Brunisols, grading with increased precipitation to Humo-Ferric Podzols (Nuszdorfer et. al. 1991). Soils on the Site are described as rapidly drained, Orthic Dystric Brunisols (60%) underlain by undifferentiated bedrock (20%) and well-drained Duric Dystric Brunisols (20%) (BC SIFT 2018). The terrain slopes upward from Wishart Road to the west. The slope of the Site is approximately 15% on average, with some areas approximately 30% in grade. Areas of exposed bedrock (rocky outcrops) are identified in Figure 1. A geotechnical evaluation prepared by a registered geotechnical professional will be completed during ongoing development planning.

4.4 SURFACE WATER

Natural surface water features (e.g., watercourses, wetlands, etc.) were not observed during the field assessment. A shallow grassy ditch is located along the eastern property boundary. The ditch flows into the municipal stormwater management system and does not connect to fish-bearing waters. Therefore, it does not require protections under the *Riparian Areas Protection Regulation*, B.C. Reg. 178/2019.

4.5 VEGETATION

Dry forests in the CDFmm zone are typically dominated by Douglas-fir (*Pseudotsuga menziesii*), arbutus (*Arbutus menziesii*), and western redcedar (*Thuja plicata*). Grand fir (*Abies grandis*) and shore pine (*Pinus contorta* var. *contorta*) may also be present. Salal (*Gaultheria shallon*), dull Oregon-grape (*Mahonia nervosa*), ocean spray (*Holodiscus discolor*), baldhip rose (*Rosa gymnocarpa*), and red huckleberry (*Vaccinium parvifolium*) are common in the shrub layer. Bracken fern (*Pteridium aquilinum*), snowberry (*Symphoricarpos albus*), grasses, and pacific sanicle (*Sanicula crassicaulina are common in the herb layer*. Oregon beaked-moss (*Eurhynchium oreganum*), step moss

Page 9 of 29

(Hylocomium splendens), and electrified cat's-tail moss (Rhytidiadelphus triquetrus) dominate the well-developed moss layer (Nuszdorfer et. al. 1991).

Most of the Site has been cleared of most natural vegetation and has been modified through landscaping and the spread of invasive species. However, in the western extent, a young second-growth forest remains (Figure 1). During the field assessment this area was identified as having the highest habitat value of the areas on the Site, as it is adjacent to undeveloped land and has been less impacted than other areas. However, there is still a high concentration of invasive species in the forested area. The forest canopy layer is dominated by arbutus and Douglas-fir. The understory is composed of native species such as oceanspray, dull Oregon-grape, tall Oregon-grape, baldhip rose, and sword fern. Numerous invasive species were observed in the understory including spurge-laurel, Himalayan blackberry, Scotch broom, and English holly.

Throughout the rest of the Site, treed patches occur, however these areas have been disturbed and lack native understory vegetation. Rock outcrops occur throughout the property. Plant diversity within the rock outcrop areas is low due to impacts from invasive species. Grass fields dominate the eastern portion of the Site, and remaining trees include red alder, arbutus, and bigleaf maple. Some mature trees (>80 years) occur on the Site and are identified in Figure 1.

Five invasive plant species were observed on the Site: Cherry-laurel, English holly, Himalayan blackberry, Scotch broom, and spurge-laurel. These are listed as "Control" species as per the Coastal Invasive Species Committee (2023). It is recommended that efforts to control these species are focused within high value conservation areas and that the use of Biological Control, if available, is utilized on a landscape scale. Measures to remove and prevent invasive species are discussed in Section 6 of this report. All vegetation species noted during the April 4, 2023 field visit are included below in Table 1.

Table 1. Plant species observed on site during the April 4, 2023 field visit.

Common Name	Scientific Name	BC Provincial Status¹	SARA Schedule 1 Status ²	
Arbutus	Arbutus menziesii	Yellow	-	
Baldhip rose	Rosa gymnocarpa	Yellow		
Bigleaf maple	Acer macrophyllum	Yellow	322	
Broad-leaved stonecrop	Sedum spathulifolium	Yellow		
Cherry-laurel	Prunus laurocerasus	Invasive; Exotic		
Common dandelion	Taraxacum officinale	Exotic	**	
Daffodil	Narcissus pseudonarcissus	Exotic	Take 1	
Douglas-fir	Pseudotsuga menziesii	Yellow		
Dull Oregon-grape	Mahonia nervosa	Yellow	***	
Electrified cat's-tail moss	Rhytidiadelphus triquetrus	Yellow		
English holly	llex aquifolium	Invasive; Exotic		
Garry oak	Quercus garryana	Yellow	**	
Grass sp.	Poa sp.	-	-	
Grassland saxifrage	Micranthes integrifolia	Yellow	in the second	
Hairy honeysuckle	Lonicera hispidula	Yellow		
Himalayan blackberry	Rubus armeniacus	Invasive; Exotic	**	
Licorice fern	Polypodium glycyrrhiza	Yellow		
Nootka rose	Rosa nutkana	Yellow	/	

Common Name	Scientific Name	BC Provincial Status¹	SARA Schedule 1 Status ²
Oceanspray	Holodiscus discolor var. discolor	Yellow	(99)
Orchard grass	Dactylis glomerata	Exotic	in the second
Reed canarygrass	Phalaris arundinacea	Exotic	
Red alder	Alnus rubra	Yellow	575
Rock cotoneaster	Cotoneaster horizontalis	Exotic	300
Scotch broom	Cytisus scoparius	Invasive; Exotic	
Smooth hawksbeard	Crepis capillaris	Exotic	-
Snowberry	Symphoricarpos sp.	-	
Spurge-laurel	Daphne laureola	Invasive; Exotic	
Sword fern	Polystichum munitum	Yellow	
Tall Oregon-grape	Mahonia aquifolium	Yellow	-
Thistle sp.	Cirsium sp.	-	
Wild carrot	Daucus carota	Exotic	**
Yarrow sp.	Achillea sp.	-	-

¹BC CDC 2023a

4.6 WILDLIFE

Trees on the Site may provide nesting and roosting habitat for birds, including migratory songbirds, year-round resident species, raptors, and owls. No nests were observed during the assessment. The Site is likely also to be utilized as a movement corridor and refuge for large mammals, including black bears, cougars, and deer. Two black-tailed deer were observed foraging in the forested area to the west.

The northwestern extent of the Site is overlapped by an area of mapped potential sharp-tailed snake habitat (CRD 2021) (Figure 2). Sharp-tailed snake is a red-listed species in BC and is designated as Endangered under Schedule 1 of SARA. Suitable habitat for Sharp-tailed Snake must provide sites for thermoregulation, egg laying, incubation, and inactive phases (overwintering/hibernation and summer inactivity/aestivation) as well as foraging opportunities. Sharp-tailed Snakes are generally found within open canopy forest, dominated by Douglas-fir, arbutus, and/or Garry oak, which provides the mosaic of shaded/cool/moist and open/warm patches required for the snakes to carry out their lifecycle. Critical habitat is identified whenever sparsely forested or treeless rocky openings (~10 m diameter and greater) with warm (southerly) aspects are found. Open habitats must be surrounded by open canopy forest habitat that support prey populations (slugs) and provide opportunities for thermoregulation. In both open habitats and adjacent forest, 3-dimesional features composed of rock or coarse woody debris that provide microhabitats must be present (Environment and Climate Change Canada [ECCC] 2020). No federally designated critical habitat is mapped in the area (ECCC 2020).

Potential for sharp-tailed snake to occupy this area on the Site is considered low. While some optimal biophysical features were observed, including rocky outcrops with southern exposure and an adjacent canopy comprised of the appropriate tree species (e.g., Douglas-fir and arbutus), the area is heavily impacted by invasive vegetation and the site overall lacks 3-dimensional features composed of rock (e.g., talus slopes or patches, or fissures in rock outcrops) and coarse woody debris (including large

² Government of Canada 2023

decaying logs or stumps with sloughing bark). Habitat quality in this area can be improved through restoration of retained green space discussed below in Section 6.

The rocky outcrops that occur on the Site may provide suitable habitat for other reptiles, including garter snakes, as well other vertebrate (e.g., mammals and birds) and invertebrate species and are designated in the City of Colwood OCP as a key topographic feature (2018). During the site assessment the species in Table 2 were observed on or near the Site.

Table 2. Wildlife species observed on site during the April 4, 2023 field visit.

Common Name	Scientific Name	BC Provincial Status¹	SARA Schedule 1 Status ²
Black-tailed deer	Odocoileus hemionus	Yellow	**
American robin	Turdus migratorius	Yellow	445
Northern flicker	Colaptes auratus	Yellow	-
Ruby-crowned kinglet	Corthylio calendula	Yellow	2 2
Spotted towhee	Pipilo maculatus	Yellow	110 0
Turkey vulture	Cathartes aura	Yellow	20
White-crowned Sparrow	Zonotrichia leucophrys	Yellow	
Yellow-rumped warbler	Setophaga coronata	Yellow	#1

¹BC CDC 2023a

4.7 SPECIES AT RISK

A query of the BC CDC iMap tool yielded occurrences of 2 species and 3 ecosystems at risk within a two-kilometer radius of the Site, as well as one masked occurrence (BC CDC 2023b) (Table 3). No atrisk species or ecosystem occurrences are mapped on the Site. The locations of these occurrences in relation to the Site are provided in Figure 4. None of the species or ecosystems listed in Table 3 were detected during the site assessment, nor was suitable habitat identified on the Site for the species mentioned.

Table 3. Species at risk that may occur in the vicinity of 3494 Wishart Road, Colwood, BC.


Scientific Name	BC Provincial Status ¹	SARA Schedule 1 Status ²
		.
Allium amplectens	Blue	n/a
Rana aurora	Blue	Special Concern
Pseudotsuga menziesii / Mahonia nervosa	Red	n/a
Abies grandis / Tiarella trifoliata	Red	n/a
Abies grandis / Mahonia nervosa	Red	n/a
	Allium amplectens Rana aurora Pseudotsuga menziesii / Mahonia nervosa Abies grandis / Tiarella trifoliata	Scientific Name Status¹ Allium amplectens Blue Rana aurora Blue Pseudotsuga menziesii / Mahonia nervosa Red Abies grandis / Tiarella trifoliata Red

¹BC CDC 2023a



² Government of Canada 2023

² Government of Canada 2023



5 POTENTIAL ENVIRONMENTAL EFFECTS

The potential impacts of the proposed development of the Site on the environment are:

- · Impacts on areas with potential habitat and biodiversity values (e.g., rocky outcrops)
- · Loss of native vegetation and spread of invasive plant species.
- · Change in wildlife habitat availability and wildlife mortality risk.
- Sediment movement in the project area.

The residual environmental impacts of the activities on the Site will be reduced by the implementation of the mitigation and restoration measures recommended in Section 6 of this report.

AREAS WITH POTENTIAL HABITAT & BIODIVERSITY VALUES (ROCKY OUTCROPS)

Intact, undisturbed rocky outcrops provide habitat for many at-risk species, and thus have high biodiversity value. The habitat and biodiversity value of the rocky outcrops on the Site has been significantly reduced by previous disturbance and the spread of invasive vegetation. However, if restored, these topographic features still have the potential to provide habitat and increased biodiversity.

VEGETATION

The effects of trees and vegetation removal may include loss of biodiversity of plant species and increased susceptibility to invasive plants not only in the cleared area but also in adjacent plant communities. Vegetation and plant communities immediately adjacent to cleared areas may experience changes due to windthrow and changes in microclimate (increased light and moisture penetration).

INVASIVE SPECIES

Invasive plants are particularly adept at colonizing degraded plant communities and disturbed soils. Invasive plants establish readily in disturbed areas as they have a wide ecological tolerance and grow and propagate quickly. The effects of invasive plant establishment may be the reduction or displacement of native species by capturing resources and occupying habitats.

WILDLIFE AND WILDLIFE HABITAT

Loss and alteration of terrestrial habitat can result in the loss of habitat for wildlife species. Tree and shrub clearing can directly alter or remove wildlife habitat. Noise from site preparation and construction may temporarily disturb and displace remaining wildlife.

EROSION AND SEDIMENT

Removal of vegetation during construction exposes soils to erosion and can result in the movement of sediment on the Site. Damage or degradation of soil surfaces during construction can include loss of soil structure, increased erosion, and soil compaction.



6 RECOMMENDED ENVIRONMENTAL PROTECTION MEASURES

The mitigation measures provided in this report are designed to protect sensitive ecosystems and were developed in accordance with:

- . The City of Colwood OCP (City of Colwood 2018),
- Procedures for Mitigating Impacts on Environmental Values (Environmental Mitigation Procedures) (BC Ministry of Environment [MOE] 2014a),
- Develop with Care 2014: Environmental Guidelines for Urban and Rural Land Development in British Columbia (Government of BC 2014), and
- Environmental Best Management Practices for Urban and Rural Land Development in British Columbia (BC Ministry of Water, Land and Air Protection 2004).

AREAS WITH POTENTIAL HABITAT & BIODIVERSITY VALUES (ROCKY OUTCROPS)

The rocky outcrops on the Site have been highly impacted by disturbance. Where possible, it is recommended that rocky outcrops be retained and restored through the removal of invasive species and seeded with a native seed blend. The following are recommended species to include in a native seed mix blend for application on rocky outcrops: Western fescue (Festuca occidentalis), Alaska oniongrass (Melica subulate), blue wildrye (Elymus glaucus), California brome (Bromus carinatus), Columbia brome (Bromus vulgaris), western fescue (Festuca occidentalis) and Pacific sanicle (Sanicula crassicaulis).

VEGETATION

The forested area (Figure 1) provides the highest habitat value of the areas on the Site, as it is adjacent to undeveloped land and has been less impacted than other areas. It is recommended that the proposed development retain a portion of this forested area as green space. Tree protection fencing will be required around retained trees within the development to protect retained green space and the drip and root zones of trees near active construction areas. Enhancement of green space is also recommended through the removal of invasive species and subsequent installation of native plants. Table 4 details native plant species that are suitable for the area. Recommended plant density following invasive removal is 1 to 2 m² for shrubs and 3 m² for trees.

It is recommended that areas disturbed by project construction or activities that are not part of the permanent footprint also be replanted with native vegetation. Overall plant density should be approximately one plant per 1 to 2 m² of disturbed space. The purpose of using native species is to reduce irrigation maintenance in the future. The optimal time for revegetation is in the fall, prior to the wet winter season. However, planting at any time of the year (with irrigation as needed) is acceptable to prevent invasive species. A replacement ratio of 2:1 is recommended for all trees greater than 50 cm DBH (diameter breast height) on the Site that will need to be removed as part of the development proposal.



Table 4. Recommended native vegetation to plant in disturbed areas and within green space

Common Name	Species	
TREES		
Arbutus	Arbutus menziesii	
Douglas-fir	Pseudotsuga menziesii	
SHRUBS AND FERNS		
Common snowberry	Symphoricarpos albus	
Dull Oregon-grape	Mahonia nervosa	
Oceanspray	Holodiscus discolor	
Rose species	Rosa nutkana / gymnocarpa	
Salal	Gaultheria shallon	
Sword fern	Polystichum munitum	

INVASIVE SPECIES

Any invasive species encountered on the Site will require removal. Invasive species should be removed using the most appropriate methods, at the correct time of year, and plant material must be disposed of correctly to avoid re-establishment or spread. Following removal, re-seed, or re-plant bare soil with desirable, competing vegetation. Details of removal methods for the invasive species onsite are provided below in Table 5.

There is a high concentration of invasive vegetation on the Site, particularly in the western extent. If needed, Corvidae recommends that a company specializing in invasive species removal to aid in weed removal. Corvidae recommends SHR Solutions (info@shrsolutions.ca) as they have helped with large scale invasive species management in the past.

Table 5. Removal and disposal methods for invasive species

Species	Removal Method	Removal Timing	Plant Disposal
Cherry laurel	Dig up or pull small plants. Cut large plants as close to the ground as possible and dig up stumps.	Remove in early spring before plants flower.	Bag all parts and dispose of properly in a landfill. Do not compost
Himalayan blackberry	Can be removed by pulling or cutting the canes from the ground. If possible, dig out the roots, paying careful attention not to damage nearby vegetation.	Removal should occur in the spring and early summer before they produce berries as canes that are cut as the plant is producing flowers are least likely to re-sprout.	Burned or bagged and disposed of properly in a landfill. Do not compost.
English holly	English holly can be removed by hand pulling small seedlings or cutting mature trees at ground level removing all plant material.	Removal is best done before flowering to eliminate seed production.	Holly does not root again once removed, so it can also be piled to desiccate on site. Can be bagged and disposed of properly in a landfill. Do not compost.



Species	Removal Method	Removal Timing	Plant Disposal
Scotch broom	Avoid disturbing the soil which can stimulate dormant broom seeds to sprout. Small broom plants can be pulled easily from the ground by hand without disturbing the soil. Larger plants should be cut below the root crown using loppers or a pruning saw.	Scotch broom removal should occur mid-April through early June, when in flower and before its seed pods begin to open.	Bagged and disposed of properly in a landfill or burning. Do not 'recycle' garden debris or compost.
Spurge- laurel	Spurge-laurel can be removed by pulling small plants or cutting larger plants just below the soil. Spurge laurel stems may re-sprout after cutting and numerous seedlings may germinate so repeated site visits are necessary. Always wear gloves when handling spurge laurel because it produces a noxious substance which can cause severe eye and skin irritation. Avoid spreading berries during removal.	Can be removed year-round.	Removed plants should be bagged and disposed of properly in a landfill. Do no transport inside an enclosed vehicle as the plants can cause respiratory irritation.

Mitigation measures to control and minimize the spread of invasive weeds on the site include:

- Clean all machinery before arrival onto the site to ensure that more weed seeds and other propagules (e.g., pieces of root) are not brought into the project area.
- If fill or topsoil is imported from external areas, ensure that it is from a weed-free source.

Any soil should not be left exposed until landscaping. Disturbed areas should be seeded with fast growing vegetation such as a mix with a native clover or seed mix to compete with weed species, fix nitrogen and provide soil stabilization right after clearing.

WILDLIFE AND WILDLIFE HABITAT

Page 17 of 29

Mitigation measures to minimize impacts on wildlife and wildlife habitat include:

- Vegetation clearing should be completed outside of the migratory bird window (prior to March 15th or after August 31st; Government of Canada 2018). If vegetation clearing is scheduled within the sensitive time period for breeding birds, a QEP should conduct nest search surveys a maximum of 2-3 days prior to the start of activities. If an active nest is discovered during nest search or clearing activities, the nest will be subject to site-specific mitigation measures (e.g., protective buffer around the nest or unobtrusive monitoring) until the young have naturally fledged/left the area. Multiple nest sweeps may be required, particularly on large sites or in complex habitats such as mature trees. Nest search areas include both vegetation and onsite, man-made structures that are scheduled for removal.
- If clearing is scheduled between January 1 and August 15, a raptor nest survey should be completed by a QEP prior to clearing. Occupied or active nests would be subject to the actions described above. In addition, permits are required to remove eagle or osprey nests regardless of occupancy.

 Avoid additional removal of established trees or shrubs, where practical (outside of the project footprint), except for identified danger trees that cannot be avoided.

Restoration of the green space within the forested area is recommended to improve habitat value for sharp-tailed snake and other wildlife. Important restoration measures include the removal of invasive vegetation as described in Table 5, and replanting with native vegetation as described in Table 4. Further restoration measures include retaining natural cover like leaf litter, fallen logs, bark, and rocks. Placement of additional rocks or logs in sunny areas of the green space area is also recommended for resident reptiles, and to add habitat complexity.

EROSION AND SEDIMENT CONTROL

The primary focus of erosion and sediment control planning is erosion control; if there is no erosion then there is no sediment. Erosion control is far more cost effective to implement and manage than sediment control.

Mitigation options to minimize the potential effects of the project on the natural environment include:

- No soil should be left exposed for more than one growing season. Disturbed areas should
 be seeded with fast growing vegetation such as a mix with a native clover or seed mix to
 compete with weed species, fix nitrogen and provide soil stabilization right after
 vegetation removal.
- Heed weather advisories and scheduling initial clearing work to avoid excessively rainy periods (>10 cm in 24 hours) that may result in high flow volumes and/ or increase erosion and sedimentation.
- If movement of sediment or sediment laden water is detected during construction, particularly into the ditch along Wishart Road, flow should be captured, and sediment allowed to settle prior to entering the ditch and stormwater system. Possible mechanisms for prevention of sediment laden water entering the ditch directly include installation of sediment fencing or straw wattles, and/or use of a tiger floc system.
- Regularly inspect and maintain Erosion and Sediment Control measures for the duration of the project.

Measures must also be taken to prevent the risk of hazardous materials and contaminant spills, including oil, gas, and hydraulic fluid during construction. It is recommended that a large, labeled, mobile spill kit is kept onsite during construction works and that all construction equipment is kept in good working order without leaks.



7 CONCLUSION

The potential environmental impacts of the proposed development at 3494 Wishart Road have been presented in this report. The environmental impacts of the proposed development are reduced by concentrating the development plans in areas which have been historically disturbed and maintaining as much forest as possible in the west. As development plans progress, implementation of the mitigation and restoration measures recommended in this report, including invasive species removal, and native plant restoration within retained green space, will further minimize the residual impacts of the development on the environment resulting in relatively low overall environmental impact.

Report Prepared By:

Nicole da Silva, BIT, B.Sc., Junior Biologist Corvidae Environmental Consulting Inc.

Nuor da Dili

Jessica O Horvey O BP. Bo 2556

Jessica Harvey, M.Sc, R.P.Bio., Principal/Senior Biologist, Riparian QEP Asio Environmental Consulting Inc.

8 REFERENCES

- BC Soils Information Finder Tool (BC SIFT). 2018. Provincial Soils Working Group. BC Ministry of Environment and Climate Change Strategy and Ministry of Agriculture. Available at: https://governmentofbc.maps.arcgis.com/apps/MapSeries/index.html?appid=cc25e43525c5471 ca7b13d639bbcd7aa. Accessed: April 2023.
- British Columbia Conservation Data Centre (CDC). 2023a. BC Species and Ecosystems Explorer. B.C. Ministry of Environment. Victoria, B.C. Available at: http://a100.gov.bc.ca/pub/eswp/. Accessed: April 2023.
- British Columbia Conservation Data Centre (CDC). 2023b. CDC iMap [web application]. Available at: http://maps.gov.bc.ca/ess/hm/cdc/. Accessed: April 2023.
- British Columbia Ministry of Environment (MOE). 2014a. Procedures for Mitigating Impacts on Environmental Values (Environmental Mitigation Procedures) Version 1.0. Available at: https://www2.gov.bc.ca/assets/gov/environment/natural-resource-policy-legislation/environmental-mitigation-policy/em_procedures_may27_2014.pdf. Accessed: April 2023.
- British Columbia Ministry of Environment (MOE). 2014b. Develop with Care 2014: Environmental Guidelines for Urban and Rural Land Development in British Columbia. Available at: https://www2.gov.bc.ca/gov/content/environment/natural-resource-stewardship/laws-policies-standards-guidance/best-management-practices/develop-with-care. Accessed: April 2023.
- British Columbia Ministry of Environment (MOE). 2004. Environmental Best Management Practices for Urban and Rural Land Development. Available at: https://www.env.gov.bc.ca/wld/documents/bmp/urban_ebmp/urban_ebmp.html. Accessed: April 2023.
- City of Colwood. 2018. Official Community Plan Bylaw 1700. Available at: <u>https://colwood.civicweb.net/document/131567/</u>. Accessed: April 2023.
- City of Colwood. n.d. Web Mapping Application. Available at: https://colwood.maps.arcgis.com/apps/webappviewer/index.html?id=84a08451d8c94076adde5 e21d2cbc84e. Accessed: April 2023.
- Coastal Invasive Species Committee (Coastal ISC). 2022. Coastal ISC Priority Invasive Plants. Available at: https://www.coastalisc.com/priority-invasive-plants/. Accessed April 2023.
- Capital Regional District. 2021. CRD Regional Map. Available at: https://maps.crd.bc.ca/Html5Viewer/?viewer=public. Accessed: April 2023.
- Environment and Climate Change Canada. 2020. Recovery Strategy for the Sharp-tailed Snake (Contia tenuis) in Canada. Species at Risk Act Recovery Strategy Series. Environment and Climate Change Canada, Ottawa. 2 parts, 17 pp. + 42 pp
- Government of Canada. 2023a. Species at Risk Public Registry. Available at: https://www.canada.ca/en/environment-climate-change/services/species-risk-publicregistry.html. Accessed: April 2023.
- Government of Canada. 2018. General nesting periods of migratory birds. Available at: https://www.canada.ca/en/environment-climate-change/services/avoiding-harm-migratory-birds/general-nesting-periods/nesting-periods.html. Accessed: April 2023.



Nuszdorfer., F.C., K. Klinka, and D.A. Demarachi. 1991. Coastal Douglas-fir Zone. In Ecosystems of British Columbia. D. Meidinger and J. Available at:

https://www.for.gov.bc.ca/hfd/pubs/docs/srs/Srs06/chap5.pdf. B.C. Ministry of Forestry, Victoria, BC. Special Report Series 6. Pp 82 - 93. Accessed: April 2023.

Province of British Columbia. 2023. HabitatWizard. Available at: http://maps.gov.bc.ca/ess/hm/habwiz/. Accessed: April 2023.



APPENDIX A - SITE PHOTOGRAPHS

Photo 1. View west from driveway off Wishart Road. April 4, 2023.



Photo 2. Front of the Site along Wishart Road (view northeast) with rocky outcrop in the foreground. April 4, 2023.



Photo 3. Middle of the Site with forested area in background (view northwest). April 4, 2023.



Photo 4. Middle of the Site (view north). April 4, 2023.



Photo 5. Treed area near middle of Site at north boundary (view south). April 4, 2023



Photo 6. Western forested area with Scotch broom in understory (view west). April 4, 2023.



Photo 7. Edge of forested area (view south). April 4, 2023.



Photo 8. Open area east of forest (view south). April 4, 2023.



Photo 9. Rocky outcrop east of forest (view southwest). April 4, 2023.



Photo 10. Rocky outcrop at northwest corner (view north). April 4, 2023.



Photo 11. Typical view of understory within sharp-tailed snake polygon. April 4, 2023.



Photo 12. Typical view of understory within sharp-tailed snake polygon. April 4, 2023.



Photo 13. Small rocky outcrop near Delora Road (view north). April 4, 2023.



Photo 14. View of ditch from south boundary looking northeast. April 4, 2023.



Photo 15. View of ditch from north boundary looking southwest. April 4, 2023.



Schedule 5



HABITAT RESTORATION AND ENHANCEMENT PLAN FOR 3494 WISHART ROAD

PREPARED FOR:

DAVID LUNN WALKING STICK DEVELOPMENTS INC. 7401 VEYANESS ROAD SAANICHTON, BC, V8M 1V9

AND

CITY OF COLWOOD 3300 WISHART RD VICTORIA, BC V9C 1R1

CORVIDAE PROJECT #2023-038 AUGUST 19, 2024



6526 WATER STREET, SOOKE, BC

SOLUTION ORIENTED. PROTECTION OF THE ENVIRONMENT. ABSOLUTE INTEGRITY. OPEN COMMUNICATION. RESPECT.

TABLE OF CONTENTS

1	INTRODUCTION1
	1.1 SCOPE OF WORK
	1.2 REGULATORY FRAMEWORK
2	RESTORATION AND ENHANCEMENT
3	CONCLUSION5
4	REFERENCES6
5	APPENDIX A - SITE PHOTOGRAPHS7
	LIST OF TABLES
Ta	ble 1. Plant List and Cost Estimate
	LIST OF FIGURES
Fi	gure 1. Site Plan2

1 INTRODUCTION

Corvidae Environmental Consulting Inc. (Corvidae) is pleased to provide this Habitat Restoration and Enhancement Plan for 3494 Wishart Road (the Site; PID 005-210-089; LOT 3 SECTION 62 ESQUIMALT PLAN VIP10219) (Figure 1). Walking Stick Developments Inc. is proposing a multi-unit development on the Site. As part of the proposed development, a 0.1-hectare section of natural greenspace along the western edge of the Site will be retained and restored (see "Environmental Conservation Area" on Site Plan).

The Environmental Conservation Area is currently young second-growth forest with a high concentration of invasive species. The proposed restoration consists of invasive species removal and native species planting as recommended in the Environmental Assessment (EA) by Corvidae dated May 2023 ("the EA Report"). The restoration will improve the biodiversity and habitat value of the Environmental Conservation Area. This Habitat Restoration and Enhancement Plan has been requested by the City of Colwood and will be submitted as part of the development permit application for the Site.

1.1 SCOPE OF WORK


A Qualified Environmental Professional (QEP) from Corvidae completed an environmental assessment of the Site. The environmental assessment documented ecological features onsite and within adjacent areas where applicable, including forested areas, and disturbed areas. Following the field assessment, the proposed Environmental Conservation Area was selected because it has the highest habitat value on the Site. The following restoration plan was developed to further improve the area.

1.2 REGULATORY FRAMEWORK

The proposed works occur within the City of Colwood Hillside Environmental Development Permit Area (DPA). All works will be completed in accordance with the DPA guidelines and in accordance with relevant provincial and federal legislation.

¹ Please see the Environmental Assessment Report completed by Corvidae for further details.





2 RESTORATION AND ENHANCEMENT

This plan is designed to protect sensitive ecosystems and was developed in accordance with:

- The City of Colwood OCP (City of Colwood 2022),
- Procedures for Mitigating Impacts on Environmental Values (Environmental Mitigation Procedures)
 (BC Ministry of Environment [MOE] 2014a),
- Develop with Care 2014: Environmental Guidelines for Urban and Rural Land Development in British Columbia (Government of BC 2014), and
- Environmental Best Management Practices for Urban and Rural Land Development in British Columbia (BC Ministry of Water, Land and Air Protection 2004).

INVASIVE SPECIES REMOVAL

The following invasive species were identified onsite during the assessment:

- Cherry-laurel (Prunus laurocerasus)
- English holly (llex aquifolium)
- Himalayan blackberry (Rubus armeniacus)
- · Scotch broom (Cytisus scoparius)
- Spurge-laurel (Daphne laureola)
- · Thistle (Cirsium sp.)

Other exotic weed species identified include reed canarygrass and orchard grass. Invasive species will be removed and disposed of appropriately, as directed by a QEP or another qualified professional. Bare areas that result will be re-vegetated with native species provided in Table 1.

NATIVE PLANT INSTALLATION

Corvidae recommends replanting the Environmental Conservation Area with native species typical of the Coastal Douglas-fir Moist Maritime (CDFmm) biogeoclimatic zone. Table 1 provides a list of recommended species that typically grow in this ecological community; and provides the estimated restoration cost. Information contained in Table 1 is subject to change based on plant availability and site conditions following invasive removal. Upon completion of invasive removal, the qualified professional will assess the quantity of plants required to revegetate bare areas. Installed plants will be spaced according to existing vegetation on site, with 1 to 2 m spacing and clustered planting to mimic natural habitats. The plant quantities in Table 1 were selected based on an assumption of 50% existing native vegetation for the 0.1-hectare area.



Area (m2)	Species Common Name	Scientific Name	Pot Size	Plant Quantity	Price per plant	Total
1000	Arbutus	Arbutus menziesii	2 gal	10	\$45.00	\$450.00
	Garry oak	Quercus garryana	2 gal	10	\$45.00	\$450.0
	Bigleaf maple	Acer macrophyllum	2 gal	5	\$12.50	\$62.5
	Oull Oregon grape	Mahonia nervosa	Nahonia nervosa 10 cm 40			\$460.00
	Tall Oregon-grape	Mahonia aquifolium	raquifolium 1 gal 20		\$11.50	\$230.00
	Oceanspray	Holodiscus discolor 1 gal 20		20	\$11.50	\$230.00
	Nootka rose	Rosa nutkana	1 gal	20	\$11.50	5230.00
	Indian plum	Oelmeria cerasiformis	1 gal	20	\$11.50	\$230.00
	Saskatoon	Amelanchier alnifolia	1 gal	20	\$11.50	\$230.0
	Salal	Gaultheria shallon	10 cm	50	\$8.00	\$400.00
	Sword fern	Polystichum munitum	10 cm	50	\$8.00	\$400.00
	Installation Costs					\$5,000.0
	Irrigation system					\$3,000.00
	Monitoring	2 site visits to oversee restora		\$700.00		
					Subtotal	\$12,073
					GST	\$604
					Total	\$12,676

MITIGATION MEASURES

WILDLIFE

Invasive plant removal should be completed outside of the migratory bird window (prior to March 15th or after August 31st; Government of Canada 2018). If invasive removal is scheduled within the migratory bird window, a QEP should conduct nest search surveys a maximum of 2-3 days prior to the start of activities. If an active nest is discovered during nest search or clearing activities, the nest will be subject to site-specific mitigation measures until the young have naturally fledged/left the area. Multiple nest sweeps may be required.

Retain natural cover such as leaf litter, fallen logs, bark, and rocks. Placement of additional rocks or logs in sunny areas is also recommended to add habitat features for reptiles.

INVASIVE REMOVAL

All invasive vegetation removal will be done by hand and using hand-held equipment, or a mini-excavator with a skilled operator, to avoid disturbance to native vegetation. For the start and completion of clearing a QEP should be on site to direct the invasive removal. Additional mitigation measures for invasive species are provided in the EA report.

IRRIGATION

Following the native plant installation, the new plants should be irrigated for a two to three year period, until established. This involves weekly irrigation during dry periods.

EROSION AND SEDIMENT CONTROL

To reduce risk of erosion and sedimentation during restoration activities, schedule work to avoid periods of heavy rainfall (>20 mm in 24 hrs) and re-plant bare areas promptly after invasive removal.

3 CONCLUSION

Significant negative environmental impacts are not anticipated as a result of the invasive species removal within the Environmental Conservation Area at 3494 Wishart Road. Works will be overseen by a QEP. Enhancement of the area through invasive species removal and planting of native species characteristic of the area will improve biodiversity and increase wildlife and habitat value over time.

Report Prepared By:



Nicole da Silva, R.P. Bio., B.Sc., Intermediate Biologist



Julie Budgen, R.P.Bio., P.Ag., B.Sc., Senior Environmental Planner

Corvidae Environmental Consulting Inc.



4 REFERENCES

- British Columbia Ministry of Environment (MOE). 2014a. Procedures for Mitigating Impacts on Environmental Values (Environmental Mitigation Procedures) Version 1.0. Available at: https://www2.gov.bc.ca/assets/gov/environment/natural-resource-policy-legislation/environmental-mitigation-policy/em-procedures-may27-2014.pdf.
- British Columbia Ministry of Environment (MOE). 2014b. Develop with Care 2014: Environmental Guidelines for Urban and Rural Land Development in British Columbia. Available at: https://www2.gov.bc.ca/gov/content/environment/natural-resource-stewardship/laws-policies-standards-guidance/best-management-practices/develop-with-care.
- British Columbia Ministry of Environment (MOE). 2004. Environmental Best Management Practices for Urban and Rural Land Development. Available at: https://www.env.gov.bc.ca/wld/documents/bmp/urban_ebmp/urban_ebmp.html.
- Capital Regional District. 2023. CRD Regional Map [web application]. Available at: https://maps.crd.bc.ca/Html5Viewer/?viewer=public.
- City of Colwood. 2022. Official Community Plan Bylaw 1700. Available at: https://colwood.civicweb.net/document/131567/.
- City of Colwood. 2023. City of Colwood GIS Map. Available at: http://colwood.maps.arcgis.com/apps/webappviewer/index.html?id=84a08451d8c94076adde5e21d 2cbc84e.
- Google Earth. 2023. Available at: https://earth.google.com/web.
- Government of Canada. 2023. General nesting periods of migratory birds. Available at: https://www.canada.ca/en/environment-climate-change/services/avoiding-harm-migratory-birds/general-nesting-periods/nesting-periods.html.
- Nuszdorfer., F.C., K. Klinka, and D.A. Demarachi. 1991. Coastal Douglas-fir Zone. In Ecosystems of British Columbia. D. Meidinger and J. Available at: https://www.for.gov.bc.ca/hfd/pubs/docs/srs/Srs06/chap5.pdf. B.C. Ministry of Forestry, Victoria, BC. Special Report Series 6. Pp 82 - 93.
- Province of British Columbia. 2023. HabitatWizard. Available at: http://maps.gov.bc.ca/ess/hm/habwiz/.



5 APPENDIX A - SITE PHOTOGRAPHS

Photo 1. Invasive species within Environmental Conservation Area. April 4th, 2023.



Photo 2. Invasive species within Environmental Conservation Area. April 4th, 2023.



Photo 3. Invasive species within Environmental Conservation Area. April 4th, 2023.



Photo 4. Invasive species within Environmental Conservation Area. April 4th, 2023.



Photo 5. Invasive species within Environmental Conservation Area. April 4th, 2023.



Photo 6. Invasive species within Environmental Conservation Area. April 4th, 2023.





Victoria, BC, V8Z 7H6 TEL: 250-479-8733 EMAIL: trees@talmack.ca www.treehelp.ca

3494 Wishart Road, Colwood

Construction Impact Assessment &

Tree Management Plan

PREPARED FOR: David Lunn

Lunn Projects

7401 Veyaness Road, Victoria, BC V8M 1V9

PREPARED BY: Talmack Urban Forestry Consultants Limited

Garrett Whelan

ISA Certified #ON-2772A

Tree Risk Assessment Qualified

DATE OF ISSUANCE: October 25th, 2024 (Original May 16, 2023)

CONTENTS

1.	INTR	ODUCTION	2
2.	TREE	INVENTORY METHODOLOGY	2
3.	EXE	CUTIVE SUMMARY	2
4.	TREE	INVENTORY DEFINITIONS	3
5.	SITE	INFORMATION & PROJECT UNDERSTANDING	5
6.	FIEL	D OBSERVATIONS	5
7.	TREE	RISK ASSESSMENT	6
8.	CON	STRUCTION IMPACT ASSESSMENT	6
	8.1.	Retention and Removal of Onsite Trees	6
	8.1.1.	Additional Information and Mitigation Measures for Onsite Trees	7
	8.2.	Retention and Removal of Private Offsite Trees.	8
	8.2.1.	Additional Information and Mitigation Measures for Offsite Trees	8
9.	IMPA	CT MITIGATION	8
10.	DISC	LOSURE STATEMENT	11
11.	IN CI	OSING	12
12.	REFE	ERENCES	12
13.	COM	PANY INFORMATION	12

APPENDICES

Appendix A Tree Inventory Table

Appendix B Tree Management Plan

Appendix C Paved Surfaces Over Tree Root Diagram

REVISION RECORD

REVISION	DESCRIPTION	DATE (YYYY-MM-DD)	ISSUED BY
F0	Original TPP report	2023-05-11	GW
F1	Updated TPP report	2023-05-16	GW
F2	Updated TPP report to reflect changed development plan	2023-09-19	GW
F3	Updated TPP report to address use of greenspace areas for construction staging	2024-08-12	TT
F4	Updated TPP for Maple #35 removal for retaining wall construction	2024-08-15	TT
F5	Update TPP to reflect City Comments	2024-10-25	TT + CC

1. INTRODUCTION

David Lunn (Client) retained Talmack Urban Forestry Consultants Limited (Talmack) to complete a tree inventory, construction impact assessment and tree management plan for the following proposed project:

Site: 3494 Wishart Road, Victoria BC

Municipality: City of Colwood

Client Name: Lunn Projects

Dates of Site Visit(s): April 5, 2023, & August 14th, 2024

Site Conditions: Pre-Construction

The purpose of this report is to address requirements of the City of Colwood arborist report terms of reference, and Urban Forest Bylaw No. 1735. The findings of this report are based solely on the survey (Powell & Associates March 2023), civil plans by OnPoint Project Engineers LTD. (August 9th, 2024), architectural plan/site plan by Walking Stick Drafting (August 9th, 2024), Landscape plans by LADR Landscape Architects (October 17th, 2024), and civil grading plans by OnPoint Project Engineers LTD. (October 10th, 2024).

2. TREE INVENTORY METHODOLOGY

For this report, the size, health, and structural condition of trees and hedges within influencing distance of the proposed development were documented (*Appendix A*). Onsite, bylaw protected trees and hedges were labeled with metal numerated tags. Trees located on neighbouring properties were not tagged but identified as OS# in the inventory table. Trees located on municipal properties were not tagged but identified as M# in the inventory table. One tree in the inventory was changed from OS11 to a NT1 as the tree was thought to be on a neighbouring property at the time of the inventory (before survey was completed). Each onsite tree was visually examined on a limited visual assessment basis (level 1), in accordance with Tree Risk Assessment Qualification (TRAQ) methods (Dunster et al. 2017) and ISA Best Management Practices.

3. EXECUTIVE SUMMARY

The client has proposed the construction of fifty (50) dwellings, greenspace, and an access road at 3494 Wishart Road, Colwood BC. As part of the development process, Talmack was retained to complete a tree inventory, construction impact assessment and tree management plan. A total of one hundred and fourteen (114) trees were included in the inventory. Of these one hundred and fourteen (114) trees there were one hundred and ten (110) that were considered bylaw-protected by size/species. The tree inventory identified one hundred and three (103) onsite trees, and eleven (11) off-site trees within influencing distance of the proposed project.

Of the inventoried trees, seventy-nine (79) trees are proposed for removal, all of which are onsite trees. Sixteen (16) onsite trees and ten (10) offsite trees are to be retained. Eight (8) onsite trees and one (1) offsite tree have been given the status of "to be determined" (TBD).

As per City of Colwood requirements outlined in Bylaw No. 1735 one hundred and fifty-two (152) replacement trees will be required for the removal of seventy-six (76) bylaw protected trees. An additional eighteen (18) replacement trees may be required depending on the final retention status of the eight (8) onsite bylaw protected "TBD" trees, and the one (1) offsite bylaw protected "TBD" tree. The Landscape plan provided by LADR Landscape Architects (October

10th, 2024) indicates the planting of exactly one-hundred and fifty-two (152) trees. This meets the required 152 required replacement trees for the removal of seventy-six (76) on-site bylaw protected trees. Due to limited spacing and soil volume, the removal of any trees listed as "TBD" (if necessary) will likely be proposed as a cash in lieu payment to the city of Colwood. Any replacement planting shortfall will require a cash-in-lieu payment to the City of Colwood at a rate of \$1000/tree.

4. TREE INVENTORY DEFINITIONS

Tag: Tree identification number on a metal tag attached to tree with nail or wire, generally at eye level. Trees on municipal or neighboring properties are not tagged.

NT: No tag due to inaccessibility or ownership by municipality or neighbor.

DBH: Diameter at breast height – diameter of trunk, measured in centimeters at 1.4m above ground level. For multi-stemmed trees, the DBH is equal to the summation of the DBH of the three largest stems. For trees on a slope, it is taken at the average point between the high and low side of the slope. * Measured over ivy, ~ Approximate due to inaccessibility or on neighbouring property

Dripline: Indicates the radius of the crown spread measured in meters to the dripline of the longest limbs.

Relative Tolerance Rating: Relative tolerance of the tree species to construction related impacts such as root pruning, crown pruning, soil compaction, hydrology changes, grade changes, and other soil disturbance. This rating does not consider individual tree characteristics, such as health and vigor. Three ratings are assigned based on our knowledge and experience with the tree species: Poor (P), Moderate (M) or Good (G).

Critical Root Zone: A calculated radial measurement in meters from the trunk of the tree. It is the optimal size of tree protection zone and is calculated by multiplying the DBH of the tree by 10, 12 or 15 depending on the tree's Relative Tolerance Rating. This methodology is based on the methodology used by Nelda Matheny and James R. Clark in their book "Trees and Development: A Technical Guide to Preservation of Trees During Land Development."

- 15 x DBH = Poor Tolerance of Construction
- 12 x DBH = Moderate
- 10 x DBH = Good

To calculate the critical root zone, the DBH of multiple stems is considered the sum of 100% of the diameter of the largest stem and 60% of the diameter of the next two largest stems. It should be noted that these measures are solely mathematical calculations that do not consider factors such as restricted root growth, limited soil volumes, age, crown spread, health, or structure (such as a lean).

Health Condition:

Poor – significant signs of visible stress and/or decline that threaten the long-term survival

of the specimen

- Fair signs of stress
- Good no visible signs of significant stress and/or only minor aesthetic issues

Structural Condition:

- Poor Structural defects that have been in place for a long period of time to the point that mitigation measures are limited
- Fair Structural concerns that are possible to mitigate through pruning
- Good No visible or only minor structural flaws that require no to very little pruning

Suitability ratings are described as follows:

Rating: Suitable.

 A tree with no visible or minor health or structural defects, is tolerant to changes to the growing environment and is a possible candidate for retention provided that the critical root zone can be adequately protected.

Rating: Conditional.

A tree with good health but is a species with a poor tolerance to changes to its growing environment or has
a structural defect(s) that would require that certain measures be implemented, in order to consider it suitable
for retention (i.e., retain with other codominant tree(s), structural pruning, mulching, supplementary watering,
etc.)

Rating: Unsuitable.

 A tree with poor health, a major structural defect (that cannot be mitigated using ANSI A300 standards), or a species with a poor tolerance to construction impacts, and unlikely to survive long term (in the context of the proposed land use changes).

Retention Status:

- Remove Not possible to retain given proposed construction plans
- Retain It is possible to retain this tree in the long-term given the proposed plans and information available. This is assuming our recommended mitigation measures are followed
- TBD (To Be Determined) The impacts on the tree could be significant. However, in the absence of
 exploratory excavations and in an effort to retain as many trees as possible, we recommend that the final
 determination be made by the supervising project arborist at the time of excavation. The tree might be
 possible to retain depending on the location of roots and the resulting impacts, but concerned parties should
 be aware that the tree may require removal.

5. SITE INFORMATION & PROJECT UNDERSTANDING

The project is proposed within the existing lot at 3494 Wishart Road, Colwood BC. It is understood that the following items will be completed under the proposal:

- Removal of selected onsite trees
- Demolition of existing onsite buildings
- Excavation for building foundations
- Grading of site
- Construction of road and new buildings
- Installation of new landscape features

6. FIELD OBSERVATIONS

The site contains an existing buildings, horse paddock, trees, and hardscaping. The tree resources within influencing distance of the project are predominantly in the forested area at the western side of the property.



Figure 1: Site context aerial photo. The approximate boundary of the proposed project at 3494 Wishart Road, Victoria BC is outlined in yellow.

TREE RISK ASSESSMENT

During our April 5, 2023 and August 14th, 2024, site visits and in conjunction with the tree inventory, onsite trees were assessed for risk, on a limited visual assessment basis (level 1), and in the context of the existing land uses. The time frame used for the purpose of our assessment is one year (from the date of the tree inventory). Unless otherwise noted herein, we did not conduct a detailed (level 2) or advanced (level 3) risk assessment, such as resistograph testing, increment core sampling, aerial examinations, or subsurface root/root collar examinations.

Existing Land Uses

We did not observe any trees that were deemed to be moderate, high, or extreme risk in the context of the existing land uses, that would require hazard abatement to eliminate present and/or future risks (within a 1-year timeframe). Targets considered during this TRAQ assessment included: existing structures (constant use), occupants of existing structures (constant use), vehicles within the onsite parking areas (frequent use), occupants of vehicles travelling on Wishart Road (frequent use), and pedestrians travelling along existing roadways/sidewalks (frequent use).

4.4	1 11 141	
Matrix I	Likelihood	matrix.

Likelihood		Likelih	ood of Impact	
of Failure	Very low	Low	Medium	High
Imminent	Unlikely	Somewhat likely	Likely	Very likely
Probable	Unlikely	Unlikely	Somewhat likely	Likely
Possible	Unlikely	Unlikely	Unlikely	Somewhat likely
Improbable	Unlikely	Unlikely	Unlikely	Unlikely

Matrix 2. Risk rating matrix.

Likelihood of	Consequences of Failure										
Failure & Impact	Negligible	Minor	Significant	Severe							
Very likely	Low	Moderate	High	Extreme							
Likely	Low	Moderate	High	High							
Somewhat likely	Low	Low	Moderate	Moderate							
Unlikely	Low	Low	Low	Low							

Figure 2: Likelihood and Risk Rating Matrices used to evaluate tree risk in the ISA Tree Risk Assessment Manual, Second Edition (Dunster et al. 2017).

8. CONSTRUCTION IMPACT ASSESSMENT

8.1. RETENTION AND REMOVAL OF ONSITE TREES

The following <u>bylaw protected</u> onsite trees (indicated by tag #) are located where they may be possible to retain, provided the mitigation measures outline in this report are followed.

Retain and Protect sixteen (16) bylaw protected onsite trees

576, 577-583, 619-621, 627, 629, 630, 648, 649

The following <u>bylaw protected</u> onsite trees (indicated by tag #) are located where they may be possible to retain depending on the impacts during construction and their final retention status will be determined during excavation by the project arborist. The tree's owner should be notified prior to the day of excavation that their tree may not be able to be retained.

Retention status of eight (8) bylaw protected onsite trees "to be determined"

585, 618, 622, 625, 626, 628, 641, 647

The following <u>bylaw protected</u> size onsite trees (indicated by tag/ID #) are located where they are likely to be impacted by proposed onsite construction and are proposed for removal (shown on the tree management plan in <u>Appendix B</u>):

Remove seventy-six (76) bylaw protected onsite trees

24-35, 563-575, 584, 586-617, 623, 624, 631-640, 642-646, NT1

The following non-bylaw protected size onsite trees (indicated by tag #) are located where they are likely to be impacted by proposed onsite construction and are proposed for removal (shown on the tree management plan in Appendix B):

Remove three (3) non-bylaw protected onsite trees

36, 37, 562

8.1.1. Additional Information and Mitigation Measures for Onsite Trees

Several mitigation techniques will be employed to retain the onsite trees identified in the Tree Management Plan (*Appendix B*). Every effort will be made to preserve the trees marked as "to be determined"; however, the final retention status of these trees will be determined onsite by the project arborist during excavation and blasting activities.

Tree protection fencing, as indicated in *Appendix B*, will be installed to safeguard the trees and their CRZs from mechanical damage and compaction. The fencing will also prevent materials or fill from being piled within the CRZs of trees to be retained. Additionally, three areas of the property have been designated for greenspace where replacement trees are to be planted. Where possible tree protection zones should encapsulate desired green space areas to preserve these areas for future replanting. However, on this site where locations for site and construction staging is limited, it is likely that these future greenspace areas will be required for this use. Therefore, following construction it will be necessary to aerate and amend the soils where required within these zones prior to commencing the landscape and replanting phase.

When walking equipment through the CRZs of trees to be retained, plywood (2 layers of 19mm) or another soil compaction mitigation technique (see Section 9) should be used.

All excavation within the CRZs or blasting activities onsite must be supervised by the project arborist. Line drilling and pre-shearing should be used as blasting operations approach retained trees or trees that are "TBD" to prevent back breaking of the rock and impacting the trees.

During our August 14th, 2024, site visit, we re-examined the health and structure of on-site bylaw protected tree #35 along with the potential impacts from the proposed construction. We observed numerous structural defects within the canopy that would be difficult to mitigate the risk to new targets that will be introduced from the proposed construction. Plans provided to date indicate significant grade changes within the CRZ of this tree that would be detrimental to the health and structure of the tree. Given its current condition (noted in the tree inventory), and impacts from the proposed construction, we believe retention is unlikely long term, even if certain mitigation measures are followed. This tree is selected for removal.

On-site bylaw protected tree **#618** is located where it may be impacted by the proposed construction and has been given the retention status "to be determined". Based on plans provided to date indicate grade changes ~5-6m from the trunk of this tree for the building foundation. Excavation for the building foundation is far enough away that retention should be possible, however critical rooting structures may be encountered during excavation that may influence the retention of this tree. Following excavation, supplemental irrigation is recommended during the hot summer months, along with mulch applications within the root zone will aid the tree in adapting to any root loss caused by construction.

On-site bylaw protected trees **585**, **576**, **577**, **581**, **582**, **579**, **580**, **583**, & **584** are located where they may be impacted by the grade changes for the proposed re-landscaping. Project arborist is to review the possible grade changes at the time of landscape installation within the CRZ of these trees.

8.2. RETENTION AND REMOVAL OF PRIVATE OFFSITE TREES

The following <u>bylaw-protected</u> offsite trees (indicated by ID#) are located where they may be possible to retain, provided the mitigation measures outline in this report are followed.

Retain and Protect nine (9) bylaw protected off-site trees

OS2-OS10

The following non-bylaw protected offsite tree (indicated by ID#) is located where it may be possible to retain, provided the mitigation measures outline in this report are followed.

Retain and Protect one (1) bylaw protected off-site tree

OS1

The following <u>bylaw protected</u> offsite tree (indicated by ID #) is located where it may be possible to retain depending on the impacts during construction and the final retention status will be determined during excavation by the project arborist. The tree's owner should be notified prior to the day of excavation that their tree may not be able to be retained.

Retention status of one (1) bylaw protected off-site tree "to be determined"

OS12

8.2.1. Additional Information and Mitigation Measures for Offsite Trees

Similar mitigation techniques will be employed to retain the offsite trees identified in the Tree Management Plan (*Appendix B*). Every effort will be made to preserve the trees marked as "to be determined"; however, the final retention status of these trees will be determined onsite by the project arborist during excavation and blasting activities.

Tree protection fencing around OS1-OS4, as indicated in *Appendix B*, will be installed to safeguard the trees and their CRZs from mechanical damage and compaction. The fencing will also prevent materials or fill from being piled within the CRZs of trees to be retained.

When walking equipment through the CRZs of trees to be retained, plywood (2 layers of 19mm) or another soil compaction mitigation technique (see Section 9) should be used.

All excavation within the CRZs or blasting activities onsite must be supervised by the project arborist. Line drilling and pre-shearing should be used as blasting operations approach retained trees or trees that are "TBD" to prevent back breaking of the rock and impacting the trees.

IMPACT MITIGATION

Tree Protection Barrier: The areas surrounding the trees to be retained should be isolated from the construction activity by erecting protective barrier fencing (see *Appendix B* for municipal barrier specifications). Where possible, fencing should be erected at the perimeter of the critical root zone. The barrier fencing to be erected must be a minimum of 4 feet in height, of solid frame construction that is attached to wooden or metal posts. A solid board or rail must run between the posts at the top and the bottom of the fencing. This solid frame can then be covered with flexible snow fencing. The fencing must be erected prior to the start of any construction activity on site (i.e., demolition, excavation, construction), and remain in place through completion of the project. Signs should be posted around the

protection zone to declare it off limits to all construction related activity. The project arborist must be consulted before this fencing is removed or moved for any purpose.

Arborist Supervision: All excavation occurring within the critical root zones of protected trees should be completed under supervision by the project arborist. Any severed or severely damaged roots must be pruned back to sound tissue to reduce wound surface area and encourage rapid compartmentalization of the wound. In particular, the following activities should be completed under the direction of the project arborist:

- All excavation with the critical root zones of retained bylaw protected trees
- Any pruning efforts of retained tree for access of equipment should be completed under the direction of the project arborist and fulfilled by an ISA certified arborist
- · All blasting operations on the property

Methods to Avoid Soil Compaction: In areas where construction traffic must encroach into the critical root zones of trees to be retained, efforts must be made to reduce soil compaction where possible by displacing the weight of machinery and foot traffic. This can be achieved by one of the following methods:

- Installing a layer of hog fuel or coarse wood chips at least 20 cm in depth and maintaining it in good condition until construction is complete.
- Placing medium weight geotextile cloth over the area to be used and installing a layer of crushed rock to a depth of 15 cm over top.
- Placing two layers of 19mm plywood.
- Placing steel plates.

Demolition of the Existing Buildings: The demolition of the existing houses, driveways, and any services that must be removed or abandoned, must take the critical root zone of the trees to be retained into account. If any excavation or machine access is required within the critical root zones of trees to be retained, it must be completed under the supervision and direction of the project arborist. If temporarily removed for demolition, barrier fencing must be erected immediately after the supervised demolition.

Paved Surfaces Above Tree Roots:

If the new paved surfaces within the critical root zones of trees to be retained require excavation down to bearing soil and roots are encountered in this area, this could impact their health and structural stability. If tree retention is desired, a raised and permeable paved surface should be constructed in the areas within the critical root zone of the trees.

The objective is to avoid root loss and to instead raise the paved surface and its base layer above the roots. This may result in the grade of the paved surface being raised above the existing grade (the amount depending on how close roots are to the surface and the depth of the paving material and base layers). Final grading plans should take this potential change into account. This may also result in soils which are high in organic content being left intact below the paved area.

To allow water to drain into the root systems below, we also recommend that the surface be made of a permeable material (instead of conventional asphalt or concrete) such as permeable asphalt, paving stones, or other porous paving materials and designs such as those utilized by Grasspave, Gravelpave, Grasscrete and open-grid systems.

Mulching: Mulching can be an important proactive step in maintaining the health of trees and mitigating construction related impacts and overall stress. Mulch should be made from a natural material such as wood chips or bark pieces

and be 5-8cm deep. No mulch should be touching the trunk of the tree. See "methods to avoid soil compaction" if the area is to have heavy traffic.

Blasting: Care must be taken to ensure that the area of blasting does not extend beyond the necessary footprints and into the critical root zones of surrounding trees. The use of small low-concussion charges and multiple small charges designed to pre-shear the rock face will reduce fracturing, ground vibration, and overall impact on the surrounding environment. Only explosives of low phytotoxicity and techniques that minimize tree damage should be used. Provisions must be made to ensure that blasted rock and debris are stored away from the critical root zones of trees.

Scaffolding: This assessment has not included impacts from potential scaffolding including canopy clearance pruning requirements. If scaffolding is necessary and this will require clearance pruning of retained trees, the project arborist should be consulted. Depending on the extent of pruning required, the project arborist may recommend that alternatives to full scaffolding be considered such as hydraulic lifts, ladders, or platforms. Methods to avoid soil compaction may also be recommended (see "Minimizing Soil Compaction" section).

Landscaping and Irrigation Systems: The planting of new trees and shrubs should not damage the roots of retained trees. The installation of any in-ground irrigation system must take into account the critical root zones of the trees to be retained. Prior to installation, we recommend the irrigation technician consult with the project arborist about the most suitable locations for the irrigation lines and how best to mitigate the impacts on the trees to be retained. This may require the project arborist supervise the excavations associated with installing the irrigation system. Excessive frequent irrigation and irrigation which wets the trunks of trees can have a detrimental impact on tree health and can lead to root and trunk decay.

Arborist Role: It is the responsibility of the client or his/her representative to contact the project arborist for the purpose of:

- · Locating the barrier fencing
- · Reviewing the report with the project foreman or site supervisor
- · Locating work zones, where required
- Supervising any excavation within the critical root zones of trees to be retained
- Reviewing and advising of any pruning requirements for machine clearances

Review and site meeting: Once the project receives approval, it is important that the project arborist meet with the principals involved in the project to review the information contained herein. It is also important that the arborist meet with the site foreman or supervisor before any site clearing, tree removal, demolition, or other construction activity occurs and to confirm the locations of the tree protection barrier fencing.

10. DISCLOSURE STATEMENT

This arboricultural field review report was prepared by Talmack Urban Forestry Consultants Ltd. for the exclusive use of the Client and may not be reproduced, used, or relied upon, in whole or in part, by a party other than the Client without the prior written consent of Talmack Urban Forestry Consultants Ltd. Any unauthorized use of this report, or any part hereof, by a third party, or any reliance on or decisions to be made based on it, are at the sole risk of such third parties. Talmack Urban Forestry Consultants Ltd. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report, in whole or in part.

Arborists are professionals who examine trees and use their training, knowledge, and experience to recommend techniques and procedures that will improve a tree's health and structure or to mitigate associated risks. Trees are living organisms whose health and structure change and are influenced by age, continued growth, climate, weather conditions, and insect and disease pathogens. Indicators of structural weakness and disease are often hidden within the tree structure or beneath the ground. The arborist's review is limited to a visual examination of tree health and structural condition, without excavation, probing, resistance drilling, increment coring, or aerial examination. There are inherent limitations to this type of investigation, including, without limitation, that some tree conditions will inadvertently go undetected. The arborist's review followed the standard of care expected of arborists undertaking similar work in British Columbia under similar conditions. No warranties, either express or implied, are made as to the services provided and included in this report.

The findings and opinions expressed in this report are based on the conditions that were observed on the noted date of the field review only. The Client recognizes that passage of time, natural occurrences, and direct or indirect human intervention at or near the trees may substantially alter discovered conditions and that Talmack Urban Forestry Consultants Ltd. cannot report on, or accurately predict, events that may change the condition of trees after the described investigation was completed.

It is not possible for an Arborist to identify every flaw or condition that could result in failure, nor can he/she guarantee that the tree will remain healthy and free of risk. The only way to eliminate tree risk entirely is to remove the entire tree. All trees retained should be monitored on a regular basis. Remedial care and mitigation measures recommended are based on the visible and detectable indicators present at the time of the examination and cannot be guaranteed to alleviate all symptoms or to mitigate all risk posed.

Immediately following land clearing, grade changes or severe weather events, all trees retained should be reviewed for any evidence of soil heaving, cracking, lifting or other indicators of root plate instability. If new information is discovered in the future during such events or other activities, Talmack Urban Forestry Consultants Ltd. should be requested to re-evaluate the conclusions of this report and to provide amendments as required prior to any reliance upon the information presented herein.

11. IN CLOSING

We trust that this report meets your current needs. The civil, servicing, grading, landscape, and architectural plans have been reviewed and adjustments to the report have been made accordingly. Should there be any questions regarding the information within this report, please do not hesitate to contact the undersigned.

Yours truly,

Talmack Urban Forestry Consultants Ltd.

Box 48153 RPO Uptown Victoria, BC V8Z 7H6 Ph: (250) 479-8733 ~ Fax; (250) 479-7050 Email: trees@talmack.ca

Prepared by:

Garrett Whelan

ISA Certified Arborist: ON-2772A

TRA Qualified Trees@talmack.ca

Tom Talbot

ISA Certified Arborist - PN0211A

TRA - Qualified

Craig Charlton

ISA Certified Arborist - PN9812A

TRA - Qualified

REFERENCES

Capital Regional District (CRD). 2022. CRD Regional Map. Retrieved data from

https://maps.crd.bc.ca/Html5Viewer/?viewer=public&

Dunster, J.A., E.T. Smiley, N. Matheny, and S. Lily. 2017. Tree Risk Assessment Manual, International Society of Arboriculture (ISA).

The City of Colwood Urban Forest Bylaw No. 1735.

13. COMPANY INFORMATION

General Liability: Intact Insurance, Policy No. 5V2147122: \$5,000,000

Table 2: Tree Inventory Table

Tag		Location	Bylaw	N	ame	Tolly Control	Name and the second	Dripline	Critical	Herrina	Cond	dition	Retention		Tree retention /	
or ID #	Surveyed? (Yes/No)	(On, Off, Shared, City)	protected? (Yes/No)	Common	Botanical	dbh (cm)	Calculated DBH	diameter (m)	root zone radius (m)	Relative Tolerance	Health	Structural	Suitability (on-site trees)	General field observations/remarks	location comments	Retention status
562	Yes	Shared	No	Red alder	Alnus rubra	58		12	8.7	Poor	Poor	Poor	Unsuitable	Measured below union, decay in trunk, multiple large failures, surface rooting	Currently outside of striking distance of targets	Remove
037	Yes	On	No	English walnut	Juglans regia	30, 29, 25, 27	55.6	12	8.3	Poor	Good/fair	Fair	Unsuitable	Historical topping, sap sucker injury, active inclusions between scaffold limbs weakly attached epicormics		Remove
36	Yes	On	No	English walnut	Juglans regia	45		10	6.8	Poor	Good/fair	Fair	Unsuitable	Historically topped sapsucker damage, weakly attached epicormics		Remove
033	Yes	On	Yes	Arbutus	Arbutus menziesii	38		8	5.7	Poor	Fair	Fair	Unsuitable	Measured below union, asymmetrical crown, leans heavily to the east, twig dieback, rooted against stump		Remove
34	Yes	On	Yes	Bigleaf maple	Acer macrophyllum	34, 34, 29, 21	60.0	10	7.2	Moderate	Good	Fair	Unsuitable	Lower trunk is enveloping metal, some deadwood, quadra dominance from base, included bark		Remove
035	Yes	On	Yes	Bigleaf maple	Acer macrophyllum	126		17	15.1	Moderate	Fair	Fair/poor	Conditional	Decay on south side (former failed stem) response growth around it, codominant at ~2.5m, failed second stem with large end weighted lateral, large epicormics, large deadwood in primary leader	See section 8.1.1	Remove
563	Yes	On	Yes	Bigleaf maple	Acer macrophyllum	150		13	18.0	Moderate	Fair	Poor	Unsuitable	Multiple stems, old stump with water sprout growth		Remove
564	Yes	On	Yes	Western red cedar	Thuja plicata	44		8	6.6	Poor	Good	Good/fair	Unsuitable	Suppressed by grand fir, growing 1.5m north of neighbouring fence line, slightly asymmetrical		Remove

Tag		Location	Bylaw	N	ame			Dripline	Critical		Cond	dition	Retention		Tree retention /	
or ID #	Surveyed? (Yes/No)	(On, Off, Shared, City)	protected? (Yes/No)	Common	Botanical	dbh (cm)	Calculated DBH	diameter (m)	root zone radius (m)	Relative Tolerance	Health	Structural	Suitability (on-site trees)	General field observations/remarks	location comments	Retention status
565	Yes	On	Yes	Grand fir	Abies grandis	45		7	6.8	Poor	Good	Good/fair	Unsuitable	Asymmetrical crown from alder, growing right beside neighbours fence (northside)		Remove
OS1	Yes	Off	No	Red alder	Alnus rubra	~22, ~9	23.8	10	3.6	Poor	Fair	Fair	Suitable	Previous stem failure, included bark in union, high crown, overhangs property by ~6m		Retain
OS2	Yes	Off	Yes	Douglas fir	Pseudotsuga menziesii	~55		10	8.3	Poor	Good	Good/fair	Suitable	Corrected lean,		Retain
OS3	Yes	Off	Yes	Western red cedar	Thuja plicata	~45		9	6.8	Poor	Good/fair	Good/fair	Suitable	Asymmetrical crown		Retain
OS4	Yes	Off	Yes	Western red cedar	Thuja plicata	~55		9	8.3	Poor	Good/fair	Good/fair	Suitable	Asymmetrical crown due to competition,		Retain
566	Yes	On	Yes	Bigleaf maple	Acer macrophyllum	114		13	13.7	Moderate	Poor	Poor	Unsuitable	Main stem failure, extensive decay, large poorly attached epicormics, hollow trunk, severely end weighted scaffold limbs	Currently outside of striking distance of targets	Remove
567	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	53		9	8.0	Poor	Good/fair	Fair/poor	Unsuitable	Historically topped, shear planes and cracked limbs, deflections in upper trunk		Remove
568	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	41		7	6.2	Poor	Fair/poor	Fair/poor	Unsuitable	Deflection in upper trunk, suppressed, dead top,		Remove
569	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	65, 67	93.3	13	14.0	Poor	Good	Fair/poor	Unsuitable	Stems fused at base, multiple deflections, secondary leaders, very end weighted limbs, asymmetrical crowns		Remove
570	Yes	On	Yes	Arbutus	Arbutus menziesii	11		2	1.7	Poor	Poor	Poor	Unsuitable	Functionally dead	Currently outside of striking distance of targets, small size limits damage that could occur	Remove

Tag		Location	Bylaw	N	ame			Dripline	Critical		Cond	dition	Retention		Tree retention /	
or ID #	Surveyed? (Yes/No)	(On, Off, Shared, City)	protected? (Yes/No)	Common	Botanical	dbh (cm)	Calculated DBH	diameter (m)	root zone radius (m)	Relative Tolerance	Health	Structural	Suitability (on-site trees)	General field observations/remarks	location comments	Retention status
571	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	70		11	10.5	Poor	Good/fair	Good/fair	Unsuitable	Asymmetrical crown, surface root to the south, irregular bark pattern on lower trunk		Remove
572	Yes	On	Yes	Arbutus	Arbutus menziesii	60		10	9.0	Poor	Fair/poor	Fair/poor	Unsuitable	Substantial cavity on lower trunk, signs of canker infection, canopy weighted to the north, fused with Douglas fir until around 2.5m		Remove
573	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	45		7	6.8	Poor	Fair	Fair/poor	Unsuitable	Suppressed, fused with arbutus, mechanical injury on trunk at ~9m, sparse canopy		Remove
574	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	45		5	6.8	Poor	Fair	Fair	Unsuitable	Narrow crown, epicormic on trunk, irregular bark pattern on lower trunk		Remove
575	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	51		5	7.7	Poor	Fair/poor	Fair/poor	Unsuitable	Irregular bark pattern in lower trunk, stressed, epicormics on trunk, missing top, lower deadwood		Remove
576	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	37		5	5.6	Poor	Fair/poor	Fair	Suitable	Sparse, stressed, narrow, epicormics on trunk, irregular bark pattern on lower trunk	Monitor health, assess prior to installation of playground	Retain
577	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	61		12	9.2	Poor	Fair	Fair	Suitable	Asymmetrical crown, quite stressed, deadwood,	Monitor health, assess prior to installation of playground	Retain
578	Yes	On	Yes	Bigleaf maple	Acer macrophyllum	3x38, 25	70.4	16	8.4	Moderate	Good	Fair	Suitable	Seam in western most leader, included bark, hangers,		Retain
579	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	70		12	10.5	Poor	Good/fair	Fair	Suitable	Asymmetrical crown, lots of deadwood	Crown clean/deadwood if retaining	Retain
580	Yes	On	Yes	Western red cedar	Thuja plicata	46		9	6.9	Poor	Fair	Fair	Suitable	Asymmetrical crown, suppressed by fir		Retain

Tag		Location	Bylaw	N	ame			Dripline	Critical		Cond	dition	Retention		Tree retention /	
or ID #	Surveyed? (Yes/No)	(On, Off, Shared, City)	protected? (Yes/No)	Common	Botanical	dbh (cm)	Calculated DBH	diameter (m)	root zone radius (m)	Relative Tolerance	Health	Structural	Suitability (on-site trees)	General field observations/remarks	location comments	Retention status
581	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	52		7	7.8	Poor	Fair	Fair	Suitable	Corrected lean, deadwood, sparse asymmetrical crown	Monitor health, assess prior to installation of playground, deadwood, and crown clean	Retain
582	Yes	On	Yes	Western red cedar	Thuja plicata	47		7	7.1	Poor	Fair	Fair	Suitable	Suppressed, asymmetrical crown,	Monitor health, assess prior to installation of playground	Retain
583	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	34		6	5.1	Poor	Good	Good/fair	Suitable	Asymmetrical crown, highly vigorous, surface rooting,		Retain
584	Yes	On	Yes	Arbutus	Arbutus menziesii	40		11	6.0	Poor	Good/fair	Fair	Suitable	Measured at roughly 1.4m from germination point, heavy lean east		Retain
585	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	72		13	10.8	Poor	Good/fair	Good/fair	Conditional	Asymmetrical crown weighted to the west,	Arborist supervision while excavating within CRZ	TBD
586	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	36		6	5.4	Poor	Fair/poor	Fair	Unsuitable	Narrow asymmetrical crown, corrected leans, bends in trunk, health stress, epicormics on trunks		Remove
587	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	61		11	9.2	Poor	Good/fair	Good/fair	Unsuitable	Asymmetrical crown, irregular bark pattern on lower trunk		Remove
588	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	30		6	4.5	Poor	Good/fair	Good/fair	Unsuitable	Rooted on edge of bank (fill), vigorous upper canopy		Remove
589	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	30		5	4.5	Poor	Good/fair	Good/fair	Unsuitable	Asymmetrical crown, vigorous upper canopy, rooted on edge of bank (fill)		Remove
590	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	33		5	5.0	Poor	Good/fair	Good/fair	Unsuitable	Asymmetrical crown, rooted on edge of bank (fill)		Remove

Tag		Location	Bylaw	N	ame			Dripline	Critical		Cond	dition	Retention		Tree retention /	
or ID #	Surveyed? (Yes/No)	(On, Off, Shared, City)	protected? (Yes/No)	Common	Botanical	dbh (cm)	Calculated DBH	diameter (m)	root zone radius (m)	Relative Tolerance	Health	Structural	Suitability (on-site trees)	General field observations/remarks	location comments	Retention status
591	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	38		7	5.7	Poor	Good/fair	Good/fair	Unsuitable	Asymmetrical crown, rooted on edge of bank (fill)		Remove
592	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	38		8	5.7	Poor	Good/fair	Good/fair	Unsuitable	Asymmetrical crown, rooted on edge of bank (fill)		Remove
593	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	31		7	4.7	Poor	Good/fair	Good/fair	Unsuitable	Corrected lean, quite vigorous,		Remove
594	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	31		8	4.7	Poor	Good/fair	Good/fair	Unsuitable	Quite vigorous, surface rooting		Remove
032	Yes	On	Yes	Arbutus	Arbutus menziesii	39, 18	43.0	8	6.4	Poor	Fair	Far/poor	Unsuitable	Hanger, cavity at base,		Remove
30	Yes	On	Yes	Western red cedar	Thuja plicata	93		12	14.0	Poor	Good/fair	Fair/poor	Unsuitable	Big surface roots, codom @~1.5m, recent top failure, stump beside tree		Remove
031	Yes	On	Yes	Arbutus	Arbutus menziesii	49, 36	60.8	14	9.1	Poor	Fair	Fair	Unsuitable	Codom @ 0.5m attachment okay, balsam cavity on eastern side, twig dieback, some deadwood		Remove
595	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	43, 20, 12	48.9	12	7.3	Poor	Good/fair	Poor	Unsuitable	Growing on old stump, surface rooting,		Remove
596	Yes	On	Yes	Arbutus	Arbutus menziesii	20		4	3.0	Poor	Fair/poor	Poor	Unsuitable	Remnants of larger tree, substantial decay at base		Remove
597	Yes	On	Yes	Arbutus	Arbutus menziesii	30		7	4.5	Poor	Good/fair	Fair/poor	Unsuitable	Canopy weighted to the east, cavity at base		Remove
025	Yes	On	Yes	Arbutus	Arbutus menziesii	41, 34		11	8.0	Poor	Fair/poor	Fair	Unsuitable	Canopy weighted to the north, third stem removed, sparse brown foliage		Remove

Tag		Location (On, Off, Shared, City)	Bylaw protected? (Yes/No)	Name					Critical		Condi		Retention	0. 1511	Tree retention /	
or ID #	Surveyed? (Yes/No)			Common	Botanical	dbh (cm)	Calculated DBH	diameter (m)	meter radius	Relative Tolerance	Health	Structural	Suitability (on-site trees)	opservations/remarks	location comments	Retention status
598	Yes	On	Yes	Arbutus	Arbutus menziesii	22		5	3.3	Poor	Fair/poor	Fair/poor	Unsuitable	Leans south, crown mostly epicormics		Remove
599	Yes	On	Yes	Arbutus	Arbutus menziesii	25		11	3.8	Poor	Fair/poor	Fair	Unsuitable	stressed, brown leaves, lots of epicormics		Remove
600	Yes	On	Yes	Arbutus	Arbutus menziesii	40		12	6.0	Poor	Fair/poor	Fair	Unsuitable	Stressed, brown leaves, lots of epicormics		Remove
27	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	70		14	10.5	Poor	Good	Fair/poor	Unsuitable	Corrected lean, codominant		Remove
601	Yes	On	Yes	Arbutus	Arbutus menziesii	38		4	5.7	Poor	Fair/poor	Poor	Unsuitable	Measured below union, sharp deflection with decay/cavity on underside, dead codom, large deadwood, twig dieback, small browning foliage		Remove
602	Yes	On	Yes	Arbutus	Arbutus menziesii	24		8	3.6	Poor	Fair	Good/fair	Unsuitable	Twig dieback, stunted		Remove
26	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	67		14	10.1	Poor	Good	Fair	Unsuitable	Asymmetrical due to historic tree to the east, end weighted limbs		Remove
603	Yes	On	Yes	Arbutus	Arbutus menziesii	27		7	4.1	Poor	Fair	Fair/poor	Unsuitable	Deflected leader, canopy weighted to the south		Remove
604	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	31		8	4.7	Poor	Good/fair	Good/fair	Unsuitable	Asymmetrical crown, surface roots, small deadwood in crown		Remove
605	Yes	On	Yes	Arbutus	Arbutus menziesii	9, 5, 4	11.0	6	1.7	Poor	Poor	Poor	Unsuitable	Water sprouts from removed tree		Remove

Tag		Location (On, Off, Shared, City)	Bylaw protected? (Yes/No)	Name			Dripline	Critical	Deletion	Condition		Retention	0 1511	Tree retention /	Retention	
or ID #	Surveyed? (Yes/No)			Common	Botanical	dbh (cm)	Calculated DBH	diameter (m)		Relative Tolerance	Health	Structural	Suitability (on-site trees)	General field observations/remarks	location comments	status
606	Yes	On	Yes	Arbutus	Arbutus menziesii	14		3	2.1	Poor	Fair	Fair/poor	Unsuitable	Growing over slab of rock,		Remove
24	Yes	On	Yes	Arbutus	Arbutus menziesii	36, 32, 28, 15, 11, 5	58.9	13	8.8	Poor	Fair/poor	Fair/poor	Unsuitable	Couple of large stems that have failed/removed decay from these old wounds, twig dieback		Remove
607	Yes	On	Yes	Arbutus	Arbutus menziesii	~30		3	4.5	Poor	Poor	Poor	Unsuitable			Remove
608	Yes	On	Yes	Western red cedar	Thuja plicata	27, 32	41.9	7	6.3	Poor	Fair	Fair	Unsuitable	Codom from 0.4m, tops are dead, branches trying to establish apical dominance, suppressed by arbutus		Remove
609	Yes	On	Yes	Arbutus	Arbutus menziesii	27		6	4.1	Poor	Fair	Fair/poor	Unsuitable	Lean to the northwest, canopy weighted to northwest, dead lateral, rooted next to large decaying stump,		Remove
610	Yes	On	Yes	Arbutus	Arbutus menziesii	12, 9, 3	15.3	5	2.3	Poor	Poor	Poor	Unsuitable	Growing from stump, leans heavily to south		Remove
611	Yes	On	Yes	Arbutus	Arbutus menziesii	31		7	4.7	Poor	Fair	Fair/poor	Unsuitable	Pronounced cavity, twig dieback,		Remove
612	Yes	On	Yes	Arbutus	Arbutus menziesii	12		4	1.8	Poor	Fair/poor	Fair/poor	Unsuitable	Cavity at base, lots of dieback		Remove
613	Yes	On	Yes	Arbutus	Arbutus menziesii	~20		4	3.0	Poor	Fair	Fair/poor	Unsuitable	Cavity at base, twig dieback,		Remove
615	Yes	On	Yes	Arbutus	Arbutus menziesii	26, 18	31.6	7	4.7	Poor	Fair	Fair	Unsuitable	Codom at 0.4m, twig dieback,		Remove
614	Yes	On	Yes	Arbutus	Arbutus menziesii	6, 3, 1	6.8	2	1.0	Poor	Poor	Poor	Unsuitable	Sprouts from decaying stump		Remove

Tag		Location (On, Off, Shared, City)	Bylaw protected? (Yes/No)	Name				Dripline	oline Critical	All Control of the Co	Con	dition	Retention		Tree retention /	
or ID #	Surveyed? (Yes/No)			Common	Botanical	dbh (cm)	Calculated DBH	diameter (m)	root zone radius (m)	Relative Tolerance	Health	Structural	Suitability (on-site trees)	General field observations/remarks	location comments	Retention status
616	Yes	On	Yes	Arbutus	Arbutus menziesii	10		1	1.5	Poor	Poor	Poor	Unsuitable	Measured 1.4m from germination point, mostly dead, previously topped		Remove
617	Yes	On	Yes	Arbutus	Arbutus menziesii	21		4	3.2	Poor	Fair	Poor	Unsuitable	Cavity at base, measured at ~1m, lower trunk nearly fused with small maple, some twig dieback, branch failure		Remove
028	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	75		13	11.3	Poor	Good	Fair	Unsuitable	Asymmetrical crown, small deadwood south side (canopy competition), very large exposed and damaged surface root to the east, newly exposed on south side		Remove
029	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	81		13	12.2	Poor	Good	Fair	Unsuitable	Pronounced root flare, asymmetrical crown, surface roots to the east, some deadwood, end weighted lower limbs, newly exposed south side		Remove
618	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	44		5	6.6	Poor	Fair	Fair	Conditional	Irregular bark pattern, very asymmetrical crown, some epicormics on trunk, newly exposed on south side	Arborist supervision while excavating within CRZ	TBD
619	Yes	On	Yes	Western red cedar	Thuja plicata	31		9	4.7	Poor	Good	Good/fair	Suitable	Some chlorosis on south side (newly exposed), girdling roots,		Retain
OS5	Yes	Off	Yes	Arbutus	Arbutus menziesii	~15		8	2.3	Poor	Fair	Fair	Suitable	2.5m south of pl, most of crown on property, leaning, lower live crown ratio, newly exposed on south side		Retain
OS6	Yes	Off	Yes	Western red cedar	Thuja plicata	44		9	6.6	Poor	Good	Fair	Suitable	Newly exposed on south side, asymmetrical crown, multiple leaders		Retain
OS7	Yes	Off	Yes	Western red cedar	Thuja plicata	~20		5	1.7	Poor	Fair	Fair	Suitable	Asymmetrical crown, competing (suppressed), newly exposed on south side		Retain


Tag		Location (On, Off, Shared, City)	Bylaw protected? (Yes/No)	Name			Dripline	Critical		Condition		Retention	0 15.11	Tree retention /	Retention	
or ID #	Surveyed? (Yes/No)			Common	Botanical	dbh (cm)	Calculated DBH	diameter (m)	root zone radius (m)	Relative Tolerance	Health	Structural	Suitability (on-site trees)	General field observations/remarks	location comments	status
OS8	Yes	Off	Yes	Arbutus	Arbutus menziesii	~32		8	4.8	Poor	Fair/poor	Fair/poor	Suitable	Weighted to east, newly exposed to south, 3.5m south of pl, high crown, branch failure, low live crown ratio		Retain
OS9	Yes	Off	Yes	Douglas fir	Pseudotsuga menziesii	40		6	6.0	Poor	Fair	Fair	Suitable	0.5m south of pl, asymmetrical crown, high narrow crown		Retain
OS10	Yes	Off	Yes	Douglas fir	Pseudotsuga menziesii	85		13	12.8	Poor	Good/fair	Fair	Suitable	~2.5m south of pl, large surface roots, deadwood, extended limbs		Retain
620	Yes	On	Yes	Bigleaf maple	Acer macrophyllum	23, 19, 1	29.8	8	3.6	Moderate	Fair	Fair/poor	Suitable	Growing from stump		Retain
621	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	47		5	7.1	Poor	Fair	Poor	Suitable	Historical failure, asymmetrical narrow crown		Retain
622	Yes	On	Yes	Arbutus	Arbutus menziesii	10		3	1.5	Poor	Fair/poor	Fair/poor	Conditional	Cavity at base, twig dieback	Arborist supervision while excavating within CRZ	TBD
623	Yes	On	Yes	Arbutus	Arbutus menziesii	13		3	2.0	Poor	Fair	Poor	Unsuitable	Sprouting from old stump		Remove
624	Yes	On	Yes	Arbutus	Arbutus menziesii	25, 16	29.7	7	4.5	Poor	Fair/poor	Fair/poor	Unsuitable	Codom from base, cavity at base, twig dieback, branch failures		Remove
625	Yes	On	Yes	Arbutus	Arbutus menziesii	21, 4	21.4	5	3.2	Poor	Fair	Poor	Conditional	Large cavity, tearout injury,	Monitor health	TBD
626	Yes	On	Yes	Arbutus	Arbutus menziesii	20, 8	21.5	6	3.2	Poor	Fair	Fair/poor	Conditional	Third stem (decayed),		TBD
627	Yes	On	Yes	Arbutus	Arbutus menziesii	8		1	1.2	Poor	Fair/poor	Fair/poor	Suitable	Substantial decay at base (has holding wood good for size), stressed, low live crown ratio		Retain

Tag	Location Surveyed? (On, Off,	Bylaw	N	ame			Dripline	Critical		Con	dition	Retention		Tree retention /		
or ID #	(Yes/No) Shared, City)		protected? (Yes/No)	Common	Botanical	dbh (cm)	Calculated DBH	diameter (m)	root zone radius (m)	Relative Tolerance	Health	Structural	Suitability (on-site trees)	General field observations/remarks	location comments	Retention status
628	Yes	On	Yes	Arbutus	Arbutus menziesii	20		5	3.0	Poor	Fair	Fair/poor	Conditional	Some twig dies back, basal decay		TBD
629	Yes	On	Yes	Arbutus	Arbutus menziesii	15		6	2.3	Poor	Fair	Fair/poor	Suitable	Browning, twig dieback, cavity at base		Retain
630	Yes	On	Yes	Arbutus	Arbutus menziesii	18		4	2.7	Poor	Fair	Fair	Suitable	Twig dieback, codom, rooted beside stump, little bit of decay at base		Retain
631	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	38		8	5.7	Poor	Fair	Fair	Unsuitable	High narrow asymmetrical crown (due to presence of large trees historically), epicormics in trunk (stressed),		Remove
632	Yes	On	Yes	Arbutus	Arbutus menziesii	25, 22, 14, 12	38.1	7	5.7	Poor	Fair	Fair/poor	Unsuitable	Some decay at base, twig dieback		Remove
633	Yes	On	Yes	Arbutus	Arbutus menziesii	12		3	1.8	Poor	Fair/poor	Fair/poor	Unsuitable	Cavity at base, twig dieback		Remove
634	Yes	On	Yes	Arbutus	Arbutus menziesii	21, 18	27.7	6	4.1	Poor	Fair	Fair/poor	Unsuitable	Codom at base, small foliage, twig dieback, leaning to the east, cavity at base		Remove
635	Yes	On	Yes	Arbutus	Arbutus menziesii	23		4	3.5	Poor	Fair	Fair	Unsuitable	Small cavity at base, twig dieback, deflected leader (past leader failure), small lower trunk wound (compartmentalizing)		Remove
636	Yes	On	Yes	Arbutus	Arbutus menziesii	27		7	4.1	Poor	Fair	Fair/poor	Unsuitable	~3m long wound with decay in lower trunk (starting to seal), twig dieback in lower canopy		Remove
637	Yes	On	Yes	Western red cedar	Thuja plicata	100		11	15.0	Poor	Fair	Poor	Unsuitable	Measured below unions, multiple leaders emerging from ~2m, cavity with decay near base, active inclusions in most unions, west side stem failure (35cm),		Remove

Tag	Tag Location			N	ame			Dripline	Critical		Cond	dition	Retention		Tree retention /	
or ID #	Surveyed? (Yes/No)	(On, Off, Shared, City)	protected? (Yes/No)	Common	Botanical	dbh (cm)	Calculated DBH	diameter (m)	root zone radius (m)	Relative Tolerance	Health	Structural	Suitability (on-site trees)	General field observations/remarks	location comments	Retention status
638	Yes	On	Yes	Western red cedar	Thuja plicata	44		8	6.6	Poor	Good	Good/fair	Unsuitable	Codom tops (small),		Remove
639	Yes	On	Yes	Bigleaf maple	Acer macrophyllum	55		13	6.6	Moderate	Good/fair	Fair/poor	Unsuitable	Past stem failure (now cavity at base extensive decay no fruiting bodies), tri dominant leaders active seam, some deadwood, exposed roots on top side of slope		Remove
640	Yes	On	Yes	Grand fir	Abies grandis	42			6.3	Poor	Dead	Dead	Unsuitable	Fine twigs remaining	Unlikely to hit targets	Remove
641	Yes	On	Yes	Arbutus	Arbutus menziesii	17, 4	17.5	6	2.6	Poor	Fair	Fair/poor	Conditional	Decay at base larger stem historically removed, rooted on mound		TBD
642	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	63		12	9.5	Poor	Good	Good/fair	Unsuitable	Asymmetrical crown,		Remove
643	Yes	On	Yes	Grand fir	Abies grandis	33		5	5.0	Poor	Fair	Poor	Unsuitable	Highly irregular taper, lower trunk wounds, codom, deflected leader		Remove
644	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	70		10	10.5	Poor	Good/fair	Good/fair	Unsuitable	Asymmetrical high crown, some deadwood, epicormic growth on trunk		Remove
645	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	55, 60, 24	84.9	8	12.7	Poor	Good	Good/fair	Unsuitable	Larger stem has some deadwood		Remove
646	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	60, 24	64.6	8	9.7	Poor	Good	Good/fair	Unsuitable			Remove
647	Yes	On	Yes	Arbutus	Arbutus menziesii	9		2	1.4	Poor	Poor	Poor	Conditional	Growing on decayed stump		TBD

		Location	Bylaw protected? (Yes/No)	Name						Cond	Condition			Tree retention /	Retention	
	Surveyed? (Yes/No)	(On, Off, Shared, City)		Common	Botanical	dbh (cm)	Calculated DBH	diameter (m)	root zone radius (m)	Relative Tolerance	Health	Structural	Suitability (on-site trees)	General field observations/remarks	location comments	status
648	Yes	On	Yes	Arbutus	Arbutus menziesii	47		10	7.1	Poor	Fair	Fair/poor	Suitable	Surface roots, growing on rock, twig dieback, hangers, deadwood,		Retain
649	Yes	On	Yes	Douglas fir	Pseudotsuga menziesii	45		8	6.8	Poor	Good/fair	Good/fair	Suitable	Slight lean corrected,		Retain
NT1	Yes	On	Yes	Arbutus	Arbutus menziesii	~39		7	5.9	Poor	Fair/poor	Fair/poor	Unsuitable	Large tearouts on western stem, epicormic growth, browning, formerly OS11		Remove
OS12	No	Off	Yes	Bigleaf maple	Acer macrophyllum	~35, ~25, ~22, ~14	50.3	11	6.0	Moderate	Fair/poor	Fair/poor	Conditional	Surface roots, large failures, deadwood, epicormic growth, ~2.5m north of fence		TBD

APPENDIX B - TREE MANAGEMENT PLAN



TREE PROTECTION NOTES

should be isolated from the construction activity by erecting protective barrier fencing. Where possible, the fencing should be erected at the perimeter of the critical root zone. The barrier fencing to be erected must machine access is required within the critical root zones of trees to be be a minimum of 1200mm in height, of solid frame construction that is attached to wooden or metal posts. A solid board or rail must run between arborist. If temporarily removed for demolition, barrier fencing must be the posts at the top and the bottom of the fencing. This solid frame can then be covered with flexible snow fencing. The fencing must be erected prior to the start of any construction activity on site (i.e. demolition off limits to all construction related activity. The project arborist must be methods: consulted before this fencing is removed or moved for any purpose. Arborist supervision: All excavation occurring within the critical root zones of protected trees must be completed under the supervision of the project arborist. Any severed or severely damaged roots must be pruned back to . sound tissue to reduce wound surface area and encourage rapid compartmentalization of the wound

Demolition: The demolition of the existing houses, driveways, and any services that must be removed or abandoned must take the critical root zone of the trees to be retained into account. If any excavation or retained, it must be completed under the supervision of the project erected immediately after the supervised demolition.

Methods to avoid soil compation: In areas where construction traffic must performed to ANSI A300 standards and Best Management Practices. encroach into the critical root zones of trees to be retained, efforts must be Paved surfaces above tree roots. Where paved areas cannot avoid excavation, construction), and remain in place through completion of the made to reduce soil compaction where possible by displacing the weight encroachment within critical root zones of trees to be retained, project. Signs should be posted around the protection zone to declare it. of machinery and foot traffic. This can be achieved by one of the following construction techniques, such as floating permeable paving, may be

- Installing a layer of hog fuel or coarse wood chips at least 20cm in depth and maintaining it in good condition until construction is
- installing a layer of crushed rock to a depth of 15cm over top. Placing two layers of 19mm plywood.
- Placing steel plates.

Mulching: Mulching can be an important proactive step in maintaining the be made of a permeable material (instead of conventional asphalt or health or trees and mitigating construction related impacts and overall stress. Mulch should be made from a natural material such as wood chipspaving materials and designs such as those utilitzed by Grasspave, or bark pieces and be 5-8cm deep. No mulch should be touching the trunk of the tree. See "methods to avoid soil compaction" if the area is to have heavy traffic.

Pruning: We recommend that any pruning of bylaw-protected trees be

required. The "paved surfaces above tree roots" detail above offers a npromise to full depth excavation (which could impact the health or structural stability of the tree). The objective is to avoid root loss and to instead raise the paved surface above the existing grade (the amount Placing medium weight geotextile cloth over the area to be used and depending on how close roots are to the surface and the depth of the paving material and base layers). Final grading plans should take this potential change into account. This may also result in soils which are high of pruning required, the project arborist may recommend that alternatives * in organic content being left intact below the paved area. To allow water to full scaffolding be considered such as hydraulic lifts, ladders or

to drain into the root systems below, we also recommend that the surface

concrete) such as permeable asphalt, paving stones, or other porous Gravelpave. Grasscrete and open-grid systems. Blasting and rock removal: Care must be taken to ensure that the area of

ng does not extend beyond the necessary footprints and into the critical root zones of surrounding trees. The use of small low-concussi charges and multiple small charges designed to pre-shear the rock face will reduce fracturing, ground vibrations and overall impact to the urrounding environment. Only explosives of low phytotoxicity and critical root zones of trees.

Scaffolding: This assessment has not included impacts from potential scaffolding including canopy clearance pruning requirements. If scaffolding is necessary and this will require clearance pruning of retained . trees, the project arborist should be consulted. Depending on the extent .

platforms. Methods to avoid soil compaction may also be recommended (see "Minimizing Soil Compaction" section).

Landscaping and irrigation systems: The planting of new trees and shrubs should not damage the roots of retained trees. The installation of any in-ground irrigation system must take into account the critical root zones the trees to be retained. Prior to installation, we recommend the irrigation technical consult with the project arborist about the most suitable location for the irrigation lines and how best to mitigate the impacts on the trees to be retained. This may require the project arborist supervise the excavations associated with installing the irrigation system. Excessive techniques that minimize tree damage should be used. Provisions must frequent irrigation and irrigation which wets the trunks of trees can have a be made to ensure that blasted rock and debris are stored away from the detrimental impact on the tree health and can lead to root and trunk decay Arborists role: It is the responsibility of the client or his/her representative

- to contact the project arborist for the purpose of Locating the barrier fencing.
- Reviewing the report with the project foreman or site supervisor.
- Locating work zones and machine access corridors where required. Supervising excavation for any areas within the critical root zones of trees to be retained including any proposed retaining wall footings. and review any proposed fill areas near trees to be retained.

CRITICAL ROOT ZONE OF TREE TO BE RETAINED DRIPLINE OF TREE TREE TO BE REMOVED TREE TO BE RETAINED TREE RETENTION STATUS TO BE DETERMINED TREE PROTECTION FENCING TREE PROTECTION THAT MAY NEED TO BE ADJUSTED TO ALLOW STORAGE OF **MATERIALS** *ĞAĞAĞ*XXXXİ*ĞAĞAĞA*İX ANANAN. TREE PROTECTION FENCING PENCE WILL BE CONSTRUCTED I POSTS * USE ORANGE SNOW-FEI TIES OR GALWANIZED STAPLES. ATTACH A SOOMIN X SOOMIN SIGN WITH THE FOLLOWING WORDING: PROTECTED DOOT ZONE - NO ENTRY. THIS SIGN MUST BE AFFIXED ON EVERY FENCE OR AT LEAST EVERY TO LINEAR METERS. IN ROCKY AREAS, METAL POSTS (T-BAR OR REBAR) DRILLED INTO ROCK WILL BE ACCEPTED. TREE MANAGEMENT PLAN 3494 Wishart Road

LEGEND

CRITICAL ROOT ZONE OF TREE TO BE REMOVED

Colwood, BC

August 15, 2024

Prepared for: Lunn Projects

Scale: 1:700 @ 11" X 17"


ngs: Concept Plan (Walking Stick Drafting, August



Victoria, BC, V8Z 7H6 TEL: 250-479-8733 EMAIL: trees@talmack.ca www.treehelp.ca

APPENDIX C - PAVED SURFACES ABOVE TREE ROOTS DIAGRAM

HARD SURFACE ABOVE TREE ROOTS DETAIL



HARD SURFACE ABOVE TREE ROOTS NOTES

- 1. Maintain as large a setback between the fill encroachment and the root collar of the tree as possible.
- Review any canopy clearance pruning requirements to accommodate vehicle or pedestrian clearances (Pruning to be performed to ANSI A300 standards).
- Excavate the new footprint of the driveway or sidewalk under the supervision of the project arborist. Excavation will be limited to the removal of the existing sod layer. Excavation around root structures must be performed by hand, airspade, or hydroexcavation.
- Install a two-dimensional (such as Combigrid ³⁰/₅₀) or Three-dimensional geogrid reinforcement.
- Install a 150mm depth layer of clear crushed gravel (no fines) using 20mm and/or 75mm diameter material or approved equivalent. *Note - the depth may be less than 150mm in some situations (dependant on grading constraints).
- 6. Install 4 oz non woven geotextile over the clear crushed gravel layer to prevent fine particles of sand from infiltrating this layer.
- 7. The bedding or base layer and new driveway or sidewalk surface can be installed directly on top of the felted filter fabric.
- Fill slopes where possible install loose stacked boulders to reduce the footprint of the fill slopes that encroach within the critical
 root zone. Fill slope materials must be permeable to air and water. Do not pile fill material directly against the trunk of a tree.







RYZUK GEOTECHNICAL

Engineering & Materials Testing

6-40 Cadillac Ave, Victoria, BC, V8Z 1T2 Tel: 250-475-3131 E-mail: mail@ryzuk.com www.ryzuk.com

October 1, 2024 File No: 11653-3

Walking Stick Developments Inc. 7401 Veyaness Road Saanichton, BC V8M 1V9

Attn: David Lunn (david@lunnprojects.ca)

Re: Geotechnical Assessment - Proposed Townhouse Development

3494 Wishart Road - Colwood, BC

As requested, we attended the referenced site on September 4th, 2024, to assess the existing geotechnical conditions pertaining to the proposed construction of a townhouse development. We understand the site is designated as being within the Natural Hazards Development Permit Area – Steep Slopes, as per the City of Colwood Official Community Plan, Bylaw 1700, amended September 26th, 2022, and requires a geotechnical evaluation prepared by a geotechnical professional. Our comments and recommendations pertaining to the proposed development are summarized herein. Our work has been completed in accordance with, and is subject to, the previously accepted Terms of Engagement.

The development site is rectangular shaped parcel approximately 1.36 Ha in area and bounded by Wishart Road to the east, and similar lots on all other sides. Based on the attached Site Survey, completed on March 13, 2023, the site slopes down from the west to Wishart Road on the east, with approximately 30 m of relief across the site. Terrain fluctuates between gentle and moderately sloped areas throughout the property with steeper sections occurring locally within bedrock outcrops. Level areas are present along the property frontage on Wishart Road and within the areas of the existing residence and shop buildings.

We understand the proposed development plans include the construction of 50 townhouse units, extending Delora Dr. through the western portion of the property as well as the construction of a strata road providing access into site from Wishart Road. The property is divided into Area 1 and Area 2 separated by the proposed Delora Drive extension. A retaining wall is proposed along the north property line to facilitate the construction of the strata road. The proposed building locations and associated infrastructure is shown on the attached Site Plan, dated August 9, 2024.

We understand that where terrain is sloping, the proposed buildings will be built into the slope, with the bottom level being a walkout onto the lower lawn or garage. The building is designed such that the existing grade of the slope will be retained once construction is completed.

During our site attendance, we noted that the site conditions generally matched that of the survey. Surface conditions comprised moderate to dense vegetation with sporadic grassy areas. Mature timbers were present further west near the proposed Delora Drive extension. Local bedrock outcrops were observed throughout with zones of soils between such that are anticipated to comprise local fills, and topsoil above dense mineral soils.

Given the shallow nature of the bedrock as well as the moderately sloping terrain, we consider that the slopes would not be subject to shallow or deep-seated instability. Accordingly, we believe that the proposed development can be carried out without negatively impacting slope stability and erosion conditions at the subject property as well as neighbouring properties.

Building pad preparation is anticipated to consist of removal of all vegetation, topsoil, disturbed native mineral soil, and other unsuitable material to expose a subgrade of glacial till or bedrock and excavation into bedrock (blasting) where required. Placement of 450 mm minus blast rock engineered fill may be carried out to establish grades where fills are required. This material is being placed in maximum 450 mm thick lifts and compacted with a 10-ton vibratory roller to 95% Standard Proctor Maximum Dry Density (SPMDD) or judged equivalent. For foundations atop bedrock, native mineral soil or engineered fill atop either, a bearing resistance of 150/225 kPa SLS/ULS is considered feasible for the proposed structures. If higher values are considered advantageous, such will be evaluated on a case-by-case basis.

Depending on the actual foundation subgrade conditions encountered during excavation, Site Classification 'C' is considered appropriate for all building locations. Improvement to Site Classification 'B' may be feasible where foundations are constructed atop bedrock or a thin veneer of engineered fill atop such. This would need to be assessed at the time of construction.

Based on the above and in accordance with Section 56 of the Community Charter, the Professional Practice Guidelines for Landslide Assessments in British Columbia (Appendix D: Landslide Assessment Assurance Statement is attached), and Bylaw 1700 of the City of Colwood Official Community Plan, we consider the site and proposed building locations as well as the driveway may be used safely for the use intended, that being the construction and use of a townhouse development. Our assessment considers a design seismic event with 2% probability of exceedance in 50 years.

We trust the preceding is suitable for your purposes at present, however if you have any questions with respect to the above, please contact us.

Sincerely, Ryzuk Geotechnical

PTPN: 1002996

Cam Schellenberg, P.Eng. Lead Geotechnical Engineer

Attachments Site Survey


Overall Development Site Plan

C.P. A. SCHELLENBERG

2024-10-01

EGBC Landslide Hazard Assurance Statement

Ryzuk Geotechnical Page 2





APPENDIX D: LANDSLIDE ASSESSMENT ASSURANCE STATEMENT

Note: This Statement is to be read and completed in conjunction with the "APEGBC Guidelines for Legislated Landslide Assessments for Proposed Residential Development in British Columbia", March 2006/Revised September 2008 ("APEGBC Guidelines") and the "2006 BC Building Code (BCBC 2006)" and is to be provided for landslide assessments (not floods or flood controls) for the purposes of the Land Title Act, Community Charter or the Local Government Act. Italicized words are defined in the APEGBC Guidelines.

To: The Approving Authority City of Colwood	Date: October 1, 2024
3300 Wishart Rd, Victoria, BC V9C 1R	11
Jurisdiction and address	- :
and Safety Policy Branch Information E	and 920) – Development Permit ding Permit Flood Plain Bylaw Variance
Legal description and civic address of the Proper	rty
The undersigned hereby gives assurance that I Engineer or Professional Geoscientist.	he/she is a Qualified Professional and is a Professional
	ertified, the attached landslide assessment report on the lelines. That report must be read in conjunction with this
Check to the left of applicable items	
1. Collected and reviewed appropriate ba	ckground information
2. Reviewed the proposed residential dev	relopment on the Property
2. Reviewed the proposed residential dev3. Conducted field work on and, if require	d, beyond the Property
	k on and, if required, beyond the Property
5. Considered any changed conditions on	
For a landslide hazard analysis or land	
	ropriate, any landslide that may affect the Property
6.2 estimated the landslide hazard	, , , , , , , , , , , , , , , , , , , ,
	uture elements at risk on and, if required, beyond the
✓ 6.4 estimated the potential consequent	ces to those elements at risk
7. Where the Approving Authority has add	
	fety adopted by the Approving Authority with the findings of
	slide safety on the Property based on the comparison
	landslide hazards and/or landslide risks
8. Where the Approving Authority has not	t adopted a level of landslide safety I have:

✓ 8.1	described the method of landslide hazar	d analysis or landslide risk analysis used
8.2	referred to an appropriate and identified of landslide safety	provincial, national or international guideline for level
₹ 8.3	compared this guideline with the findings	of my investigation
₹ 8.4	made a finding on the level of landslide s	safety on the Property based on the comparison
☑ 8.5	made recommendations to reduce lands	lide hazards and/or landslide risks
	orted on the requirements for future inspe uct those inspections.	ctions of the Property and recommended who should
Based on m	ny comparison between	
Check or	ne	
		ne adopted level of landslide safety (item 7.2 above) national or international guideline for level of
I hereby g assessmen		conditions ^[1] contained in the attached landslide
Check or		
	for <u>subdivision approval</u> , as required by used safely for the use intended"	he Land Title Act (Section 86), "that the land may be
	Check one ☐ with one or more recommended reg ☐ without any registered covenant.	istered covenants.
~		the Local Government Act (Sections 919.1 and ernment in determining what conditions or ction (7.1) it will impose in the permit".
	for a <u>building permit</u> , as required by the oused safely for the use intended"	Community Charter (Section 56), "the land may be
	Check one with one or more recommended reg without any registered covenant.	istered covenants.
		d by the "Flood Hazard Area Land Use Management overnment Act (Section 910), "the development may
	for flood plain bylaw exemption, as requi	red by the Local Government Act (Section 910), "the nded".
Cam :	Schellenberg	2024-10-01
Name (print)	land	Date
	[/WW/	
Signature		

When seismic slope stability assessments are involved, *level of landslide safety* is considered to be a "life safety" criteria as described in the National Building Code of Canada (NBCC 2005), Commentary on Design for Seismic Effects in the User's Guide, Structural Commentaries, Part 4 of Division B. This states:

ctural Commentaries, Part 4 of Division B. This states:

"The primary objective of seismic design is to provide an acceptable level of safety for building occupants and the general public as the building responds to strong ground motion; in other words, to minimize loss of life. This implies that, although there will likely be extensive structural and non-structural damage, during the DGM (design ground motion), there is a reasonable degree of confidence that the building will not collapse nor will its attachments break off and fall on people near the building. This performance level is termed 'extensive damage' because, although the structure may be heavily damaged and may have lost a substantial amount of its initial strength and stiffness, it retains some margin of resistance against collapse".

771 Vernon Avenue #100, Victoria, BC V8X 5A7 250-475-3131 (Affix Professional seal here) Telephone If the Qualified Professional is a member of a firm, complete the following. I am a member of the firm Ryzuk Geotechnical and I sign this letter on behalf of the firm. (Print name of firm)

WALKING STICK DEVELOPMENT LTD. 3494 WISHART ROAD COLWOOD, BC ISSUED FOR DEVELOPMENT PERMIT

2025.01.03 CITY OF COLWOOD PERMIT No: ISLAND HEALTH PERMIT No.:


Schedule 8

	Sheet List Table	
Sheet Number	SHEET TITLE	Drawing #
1	TITLE PAGE	C000
2	GENERAL NOTES	C100
3	PRIVATE ROAD - EARTHWORKS	C200
4	DELORA DRIVE - EARTHWORKS	C201
5	ROAD SECTIONS	C202
6	DELORA DRIVE UTILITIES	C300
7	ROAD A UTILTIES	C301
8	ROAD B UTILITIES	C302
9	WISHART FRONTAGE IMPROVEMENTS	C303



LOCATION PL 3494 WISHART ROAD









	na conditions at also and report any dispreparates to engineer palor to precoupling with work
ľ	DO NOT SCALE THE DRAWING

No.	ISSUED DESCRIPTION	OATE	8/ON	No	REVISIONS pescilentos	DATE	SIGN
1.	ISSUED FOR TON APPROVAL	509468409	900				
2	ISSUED FOR DEVELOPMENT PERMIT	2024-10-25	JEH				
1	ISSUED FOR OFF-SITE APPROVAL	2025-01-03	STR				
114.		1 2 3 3 5 5 5 5	=:				
_						_	



WALKING STICK DEVELOPMENTS LTD.

3494 WISHART ROAD
WALKING STICK DEVELOPMENTS LTD
COVER PAGE

ON POINT PROJECT No.
369-2

OVERNING AUTHORITY FILE No.
TBD.
SHEET 1 or 9
REEY
ON POINT DRAWING No.

- A PERMIT TO CONSTRUCT WORKS WITHIN RIGHTS OF WAY, STREETS, LANES AND CITY PROPERTY AREAS ADJACENT TO THE DEVELOPMENT SITE WILL BE RECURRED WHERE CONSTRUCTION IS TO BE UNDERTAINED MITH-SIZE AREAS.
- PERMITS REQUIRED FOR WORKS WITHIN ANY PUBLIC AREA OR RIGHT OF WAY SHAUL BE OBTAINED BY THE CONTRACTOR PRIOR TO ANY WORKS. COMMERCING WITHIN TROSS AREAS. ALL WORK AND NATIONAL TO BE IN ACCORDANCE WITH CURRENT CITY OF COLUMDOD BYLAWS; LATEST EDITION OF THE WINCO SPECIFICATIONS.
 AND DRAWNINGS PROJECT SPECIFICATIONS. AND CONSTRUCTION DOCUMENTS.
- SPECIFICATIONS TAXE PROCEDURES OF CONSTRUCTION GOLDWINTS.
 SPECIFICATIONS TAXE PROCEDURES OF CONSTRUCTION GOLDWINTS.
 ANY AND ALL DECREPANCES BETWEEN BRANCHES AND SPECIFICATIONS ARE TO BE BROOKET TO THE IMMEDIATE ATTENTION OF THE ENGREEP BROOT TO EXCELED NO. THE TRATALLATION.
 CONTROL TO REPOVED TO THE CONTROL TO THE CON

- D. TO COMMANDED AT DE CONSTRUCTION WITH CITY OF ONE WOOD COVEY, ENGINEER, AND CONTRACTO
- CONTRACTOR TO MAINTAIN IN THE SITE OFFICE AT ALL THESE FOR USE BY THE ENGINEER, CITY AND TRADES, A COUNT OF THE LATEST APPROVED DRAWNER, ON SONG REJLINE PREVAINES, MICH SPECIATIONS, CITY OF COLWOOD SPECIAL SINGER OF ALL SITE INSTRUCTIONS, CLAREFICATIONS, CONTRIBUTION OF CHARGE AND APPROVED CHARGE OFFICE THOSE SOND SPECIAL SINGER OF ALL SITE INSTRUCTIONS.
- ENGINEER TO HAVE REPRESENTATIVE ON SITE DURING THE ROAD CONSTRUCTION AND INSTALLATION OF UTILITIES. INSPECTOR TO PREPARE DALLY REPORTS AND SUBMIT WEEKLY TO CITY OF COLWOOD.
- RED ON METRIC GEODETIC DATUM LINCERS OTHERWISE NOTED.
- ALL EXISTING CONNECTION POINTS TO BE EXPOSED PRIOR TO CONSTRUCTION AND INVERTS CONFIRMED, NOTIFY ENGINEER IN WRITING OF ANY DISCREPANCES IMMEDIATELY AND BEFORE PROCEEDING WITH CONSTRUCTION, ALLOW MINALIAN 45 HOURS FOR REVIEW
- 10. CONTRACTOR TO VERBY LOCATIONS OF SERVICES EXISTING THE POINTS CROSSINGS AND OTHER FEATURES AND APPLICTEMANCES ANY DISCREPANCIES TO BE BROUGHT TO THE ATTENTION OF THE PROJECT ENVINEER ALLOW MINIMAM AS HOURS FOR REVIEW NO CHANGE TO THE DESIGN IS PERMITTED WITHOUT A PORMAL INSTRUCTION FROM THE ENGINEER. REQUESTS FOR INFORMATION FROM THE CONTRACT OR ARE TO BE IN WRITING, RESPONSES TO AFIS OR OTHER CONTRACT OR FIELD INSTRUCTIONS ARE TO BE ISSUED BY THE ENGINEER PLANTAGE.
- IN APPLIANCE APPLIETEMENTS EXIST PRIOR TO CONSTRUCTION (BUCH AS MANHOLE CASTINGS, VALVE BOXES, EVORANTS, SERVICE BOXES, HITCE BOXES, ETC.), APPLIETEMENTOS SHALL BE ADJUSTED TO SHIT NEW ORACES BY CONTRACTOR (PALESS NOTED OTHERWISE).

 I CONNECTION TO GRAIT THANKING SHALL BY ADJUSTED TO SHIT THE OF CHARGE WATCHING IN YES PROTECTED SHITLY OF THE PARTY OF THE

- REPRESENTATIVE.

 A LAL WORK AREAS TO BE RESTORED TO GRIGINAL CONDITION OR RETTER AND TO THE SATISFACTION OF THE DIRECTOR OF ENGALEPING.

 ALL ESTENDABLE UTILITIES AND SERVICE CONNECTIONS IN ROCK TREASHES TO HAVE ROCK BLASTED & EXCAVATED MRY 2.5% BEYOND END OF SERVICE OF TO LIGHTANT RESAME. TO SERVICE OF CARRIED AND ASSESSMENT OF THE SERVICE OF THE SE
- CONTRACTOR TO ENSURE ANY EXISTING MONUMENTS AND FROM PINS ARE NOT DISTURBED. ANY MONUMENTS OR FROM PINS DISTURBED DURING CONSTRUCTION SHALL BE REPLACED BY A BOLLS AT THE CONTRACTORS EXPENSE.
- 18. FOR BC HYDRO, TELLE, SHAW AND FORTIS BC WORKS REPER TO DWGS SUPPLIED BY UTILITY COMPANIES, INFORMATION ON UTILITIES SHOWN ON COLD, UNANIMOS, ARE NOT TO BE USED FOR CORSTITUTION SHOWN CO. STO THE BURGES, OF THE PROPERTY OF THE SHOWN OF COLD WAS AN EXPENSE OF THE SHOWN OF COLD WAS AN EXPENSE OF THE SHOWN OF THE
- 20. ALL UTILITY BOXES TO HAVE EDGES PERPENDICULAR TO EDGE OF ROAD AND SIDEWALK.

- HIGHT OF WAY SHOWN REPRESENT GENERAL INTERN. FOR YOU DOWNWAY OFFICE OF BUSINESS FOR INSECTION TO BE BOLLSTO'S TEACH LOCATIONS OF FOR ITLIES YEARS OF YOU WAND THROUGH EXAMENTS AS REQUIRED. RIGHTS OF WAY AND EXEMENTE FOR INTERIES, DIRECTOR SET OF THE ADMINISTRATION FOR CONSTRUCTION DRAWINGS FOR CLARITY. BOLLSTO PROMOTION FOR THE YOUNG AND DEPOLATION FLAMS.

SURVEY

ALL SURVEY LAYOUT AND RECORD INFORMATION TO BE CARRED OUT BY ON POINT PROJECT ENGINEERS LTG. CONTRACTOR TO PROVIDE AS MACHINOTICE AS POSSIBLE, AT LEAST TWO (2) BUSINESS DAYS IS PREFERRING. CONTRACTOR SHALL MAKE ALL AND REASONABLE EFFORTS TO PROVIDE AS THE PROPERTY OF TH

SANITARY AND DRAIN

- MECHANICAL PLUG MUST BE INSTALLED IN MANHOLES PRIOR TO CONNECTING TO EXISTING MAINS TO ENSURE NO DEBRIS OR WATER ENTERS EXISTING SYSTEM DURING CONSTRUCTION CONTRACT ADMINISTRATOR TO APPROVE REMOVAL CONTRACTOR TO MONITOR FOR, AND REMOVE ANY BACKDUP DEBRIS PRIOR TO REMOVANT FLUG.
- ALL 100mm AND 150mm-DIAMETER SANTARY AND DRAIN SEWER SHALL BE SOR 28. ALL SANTARY AND DRAIN SEWER 300mm AND LARGER SHALL BE SOR 39 UNLESS OTHERWISE NOTED, MINIMUM COVER 1.5m UNLESS NOTED, DUCTUE FROM PIPE WHERE SHOWN TO PRESSURE OLD AS 150.
- BANTARY AND DRAIN SERVICES TO BE CONSTRUCTED IN ACCORDANCE WITH CITY OF COLWOOD BY AN 1000 SED 57 AND SED 56 COMPLETE WITH ASPECTION OF WAREN ON CITY SIDE OF PROPERTY LINE. REPRECION CHARGES SHALL BE IN BROOKS JITY CONCRETE BOXES COMPLETE WITH
- ALL SANTIARY AND DHAIN SERVICES TO BE PLACED AT MINIMAN 2'S GRADE FROM OBSERT OF MAIN TO PROPERTY LINEAD AND EXTEND A MINIMA MINIMA OF AN INCORPORATY.
- OF 24 NITO PROPERTY.

 ALL SERVICE STUBS TO PROPERTIES TO BE STAKED WITH DEPTH TO INVERT NOTICE.

 ALL SERVICE STUBS TO PROPERTIES TO BE STAKED WITH DEPTH TO INVERT NOTICE.

 CATCH BASH LEDGE TO BE 2003 SER 35 PVC AT 2 DK. MN UNLESS ON THEIR DEPTH TO INVERT NOTICE.

 COMPACTION TESTING TO BE IN ACCORDANCE WITH OITY OF COLUMNOD BYLAMS.

 ALL SANITARY AND DRAIN MARKS TO BE OCTV INSPECTED IN ACCORDANCE WITH MIMOD. POWER FLUSH & CCTV TO NEAREST GOWNSTREAM MARKS TO BE OCTV INSPECTED IN ACCORDANCE WITH MIMOD. POWER FLUSH & CCTV TO NEAREST GOWNSTREAM MARKS TO.

- 10. CCTV REPORTS ARE TO BE SUBMITTED TO THE ENGINEER AND CITY OF COLWOOD FOR REVIEW/ACCEPT/ANCE PRIOR TO HOT MIX ASPIALT CONCRETE PAYING.

- MANHOLE LIDS TO BE INSTALLED TO MATCHROAD GRACE LID CASTINGS TO BE STAMPED "COLWOOD SANITARY SEWER" OR "COLWOOD STORM CHAIN" HIM ELEVATIONS ARE APPROXIMATE ONLY FOR ESTIMATING QUANTITIES AND ROUGH IN
- CASTING TO BE ENCASED IN CONCRETE WITH APPROPRIATE FALL PIPE CITY OF COUNCOD BY LAW 2000.
 ALL PRECAST OR CAST IN PLACE CONCRETE INCLUDING PRIMES AND GRATES TO BE HEAVY DUTY WITH H 20 LONDING UNLESS OTHERWISE MOTE.

 ADVE.D.
- CONSTRUCTION SHALL NOT PROCEED WITHOUT FIRST OBTAINING A CONSTRUCTION PERMIT FROM ISLAND HEALTH AND CRD WITER SERVICES ACCEPTANCE OF THE DESIGN DRAWINGS
- CONTRACTOR BUSING IMMUNION.

 CONTRACTOR BANK, DE REGISTERE WITH WORKSAFE BC.
 ALL WATERWORKS CONSTRUCTION AND WATERING SHALL BE IN ACCORDANCE WITH CURPRENT CRD WATER SERVICES ENGINEERING
 SECENCIFICATION AND STANDARDS PROVINGES.
- WATER MAINS SHALL BE PIND OR 19 TO AWAYA CROLLING SS OTHERWISE NOTED, PIPES JOURNAUD LARGER TO BE DUCTLE BOOK ICLASS 350 WITH MAIL COMMINIOR ALL JOINTS TO BE RESTRANCED TO PRESSURE CLASS OF PIPE ON 300 MID DUCTLE BOOK OF LARGER, TRILLING THE SET THE PROFERING OFFICIAL PLANTS COMMINIORS TO BE LISTED WHERE COMMINIORS TO SET LISTED WHERE TO PRESCRIBE TO THE TOTAL TO STATE AND ALL SET TO THE THE SET
- MARK WATER MANS BELOW GRADE USING A METALLIC DETECTABLE REPRORCED UNDERSECUND UTLITY MARKING TAPE. THE TAPE SHALL BE MANAGEN TSOM INTO METALC SLUE IN COLCUR AND SHALL BE MARKING CHATTON WATER LINE BURED BELOW! INSTALL TAPE ON TOP OF THE PIPE CUSHION 300000 ABOVE THE TOP OF THE PIPE PROVIDED "HOSPITCH MARKING TAPE OR A PEPSOUND DOLLY."
- MAINTAIN A MINIMUM OF 31 HORIZONTAL CLEAR SEPARATION AND 450161 CLEAR VERTICAL SEPARATION BETWEEN WATER MARS AND ALL SANTARY SEMERS SERVICES AND DIALN SEWDESSERVICES EXCEPT WHERE MOTED AND APPROVED BY CRO WATER SERVICES, SANTARY SEWIER SANTARY SERVICES FALL NOT GOODS COVER WATER MARKS. MAINT AIR A MINROUND DY SHI HORIZONTAL CLEAR BEPARATION AND ARCHITECTURED VERTICAL SEPARATION BETWEEN WATER SERVICES AND SEWER SERVICES SOMMARY ON STORMANDAN IN SPECIAL CROCAMISTANCES, WHICH A EARLY VERTICAL STORM BEHAVED IS COME THAN A NOTED AND APPROVED BY COST WATER SERVICES. WHE HORIZONIAL OFFSET WAS 61 HIGHCARD TO MISS THAN 10 BE RECEIPT WHERE NOTED AND APPROVED BY COST WATER SERVICES.
- MHERE NEW CATCHBASK ICE; LEDGS DO NOT HAVE A 450mm VERTICAL SEPARATION WIRAP WATERWAN AND CE LEAD JOINTS WITH PETROLATUM TAPE WITHIN 5% OF CROSSING.
- TE. MAINTAIN A MINIMUM OF 1.5th HORIZONTAL CENTRE TO CENTRE AND YOUTH CLEAR VERTICAL SEPARATION SETWEEN WATER MAINS AND ELECTRICAL CONDUITS, CAS MAINS, AND TELEPHONE CONDUITS EXCEPT WHERE MOTED AND APPROVED BY CRD WATER SERVICES.
- 11. MAINTAIN A MINIMUM OF 1.5_{TH} HORIZONTAL CENTRE TO CENTRE AND 150 to CLEAR VERTICAL SEPARATION SETWEEN WATER SERVICES AND ELECTRICAL, CAS, AND TELEPHONE SERVICES EXCEPT WHERE NOTED AND APPROVED BY CRD WATER SERVICES.
- 12. CONTRACTOR SHALL CONDUCT A PRESSURE AND LEAK TEST IN ACCORDANCE WITH ORD WATER SERVICES ENGINEERING SPECIFICATIONS AND IN PRESENCE OF ENGINEER.
- PROSERVAC OF PARAMETER

 1. CONTRACTOR SHALL PLUSE MAD DISINEED, WATER MAINS BLACCORDINACE WITH AWAYS STANDARDS AND AS APPROVED BY CRD WATER
 1. SERVICES, WATER SHAME ISS FOR HEALTH TESTS RESULTS TO BE SUBMITTED TO ENGINEED.

 1. SERVICES, WATER SHAME ISS FOR HEALTH TESTS RESULTS TO BE SUBMITTED TO ENGINEED.

 1. SERVICES, COLORNE SCULTUDES ADDOCRATICE WITH HAMBERT OF ENVIRONMENT AND FRHERES AND OCEANS CANADA RESULATIONS

 1. CONTRACTOR TO PROFUZE SHOULD HAVE NOTED TO CORD WATER SERVICES PRIOR TO PROCEEDING WITH ANY WATERWORKS.

- CRD WATER SERVICES SHALL MAKE ALL CONNECTIONS TO EXISTING WATER MAINS AT THE DEVELOPMENTS EXPENSE. CONTRACTOR TO COORDINATE WITH CRD WATER SERVICES FOR WORK REQUIRED BY CRD WATER SERVICES FORCES. TO WHERE FRANCES, ISSENSE THERE AND INTER MORE SHALL BE INTERLED TO THE SERVICES FORDES.

 WHERE FRANCES, ISSENSE THERE AND INTER BOKES SHALL BE INSTALLED TO INSELED CROKE OWNED CAN'T BE AND INTERLED TO INSELED CROKE OWNED CROKE OF THE CORD SHAPE, YET SHALL BE REPORTED OF THE WHEN THE CORD SHAPE, YET SHALL BE REPORTED OF THE WHEN THE CORD SHAPE, YET SHALL BE REPORTED OF THE WHEN THE CORD SHAPE, YET SHALL BE

ONPOINT

PROJECT ENGINEERS LTD TO, 250-478-7875 WWW.OPPCL.CA BUILTE TITL WAY (AMON'D MED PRINTY VICTORIA NO. VIRGINIA

ALL IRRIGATION SLEEVES TO BE 1901th PVC SDR 28 AND ARE TO EXTEND A NIN 1,0th SEYOND ANY HARDSCAPE SURFACE SUCH AS CURBS, TRAILS, SIDEWALKS OR ROADS, UNLESS OTHERWISE NOTED.

Contractor must shack and varily all chromators

DO NOT SCALE THE DRAWING

2 IRRIGATION SLEEVES TO BE STAKED BY CONTRACTOR, CONTRACTOR TO COORDINATE SURVEY FOR RECORD DRAWINGS

- ALL MATERIALS TO BE IN ACCORDANCE WITH CITY OF COLWOOD BY AW 2000, WHERE MATERIALS STANDARDS ARE NOT SPECIFIED MASTER MANAGEM, CONTRACT DOCUMENT STANDARDS SHALL BE USED. IN ALL OTHER CASES MATERIALS STANDARDS SHALL BE IN ACCORDANCE WITH THE EMAILER OF RECORDS SPECIFICATION.
- PERMITS FOR WORKS WITHIN ANY PUBLIC AREA OR ROAD RIGHT OF WAY SHALL BE OBTAINED PRIOR TO ANY WORKS COMMERCING WITHIN THOSE AREAS.
- CONSTRUCTION AND RECTIONS IN ACCORDANCE WITH THE DRAWINGS.

- ALL SIDEWALKS ARE BROOM FINISHED UNLESS NOTED OTHERWISE, 2IF-STRIP TYPE CONTROL JOINTS TO CITY OF COLWOOD SYLAW 2000, CURB LET DOWNS FOR SIDEWALK AT CROSS WALKS ARE TO BE SALOUTH WITH NO RUSED "LIP".
- CONCRETE SIDEWALKS SHALL BE 150mm THICK TO TICK OF CURBLET OTION AT DRIVEWAY CROSSINGS AND WHERE MOUNTABLE CURBS ARE SECURED, TOWN THICK WHERE NOW WOUNTABLE CURBS ARE SECURED AND STIRM THICK AT INJUSTICAL AND COMMERCIAL DRIVEWAY

CONCRETE

- MAND FORWER CLAR AND GUTTER, SIDEMALKS AND STARWAYS SLURP RIVER AND STARWAYS SLURP RIVER AND STARWAYS SLURP RIVER AND STARWAYS SLURP RIVER AND STARWAYS SLURP RIVER AND STARWAYS AND STARWAYS AND STARWAYS SLURP RIVER STARWAYS AND STARWAYS AND AND STARWAYS SARWAYS STARWAYS AND AND STARWAYS SARWAYS STARWAYS SARWAYS ARWAY SARW
- EXTRUDED CURS AND SUTTER EXPOSURE CLASS, 0.2 SUMP-0.25em
 AIR ENTRAINMENT 69-99-FINENESS MODULUS: 21-24
- ADDREDATE SIZE AND AIR CAN WARY PER CSA

- THE CONTRACTOR IS RESPONSIBLE FOR HAVING THE MINING THE MINING REQUIRED MATCHAIL TESTING LINDERTAKEN BY A THIRD PARTY AND ADVISE THE ENGINEERS OF RECORD OF THE THIRD PARTY THAT WILL BE RESPONSIBLE FOR THIS TESTING.
- GEOTECHARD, ENGAGERS TO PROCEED WRITTEN A SEPARABELE FOR USE INSTITUTION OF THE TESTING.

 GEOTECHARD, ENGAGERS TO PROCEED WRITTEN A REPORTANCE OF PLAND COMPACTION METHODOLOGY ANCLIGING CERTIFICATION THAT
 TERRICH BEDDING, BADRING, SABORDE AND FILL INVESTMENT HE MANURAL COMPACTION MEDIUMENTS THIRDSCHOOLT

 FOR SEPARABEL SHEETCHEN REPORTS ARE TO BE SENT ORDIRECTLY FROM THE LAST OF THE ANORMER'S REPRESENTATIVE WITHIN 72 HOURS,
 ANY MATERIAL TO BE FOUND DEFICIENT BY TO BE COMPRESTED AND RETEXTED WITH COMPS OF THE RE-REPECTION REPORTS TO BE SENT
 OFFICE CLYPTHON THE LAST OTHER COMMERCING REPORTS AND TRANSPORT TO BUSINESS.

- 6.1.1 DOCLMENTATION FROM THE ASPHALT PLANT SHALL BE PROVIDED FOR ALL PROJECTS (THIS WILL INCLUDE REFERENCE TO THE MIX DESIGN TYPE FOR THE MATERIAL PROVIDED AND THE MOST RECENT APPLICABLE MIX TEST REPORTIS).
- MIX DESIGN THE FOR THE MINISTRAL PROFIDED WIS THE WORLD RESIDNED TO ASPHALT CONCRETE MIX PLACED EXCERDS

 1.2.1 ONE SMARLE BANK, BE TAXED EXCENDING OF OPERATION. IF THE AURUST OF ASPHALT CONCRETE MIX PLACED EXCERDS

 5.1.2.1 ONE SMARLE BANK, BE DISTRICTED AND RESIDNED OF THE MINISTRAL BE ADMERSOR OF THE MIN

- 5.2.1 DOCLMENTATION FROM THE CONCRETE PLANT SHALL BE PROVIDED FOR ALL PROJECTS (THIS WILL INCLUDE NOX DESIGN INCOMMENTATION AND DAILY BATCH REPORTS FOR THE MATERIAL PROVIDED).
- CONNECTE SAMELING AT PROJECT LOCATION.

 5.2.1 FAR SAMELING STATE SHALL BE TAXABLED MAY OF OFFINATION. IF THE LENGTH OF CARR, CUTTER OR SIDENIAL NETALLED MANN ONE DAY EXCEPTED AND LINEAR, OR 100-1/AND EVER EXCEPTED AND LINEAR OF THE THAT LINEAR SHALL BE COLLECTED SHALL BE COLLECTED OF THE THAT HAVE A SHALL BE COLLECTED AND A THE THAT HAVE AND SHALL BE COLLECTED SHALL BE A THE THAT LINEAR SHALL BE COLLECTED SHALL BE A THE THAT LINEAR SHALL BE COLLECTED SHALL BE A THE THAT HAVE AND SHALL BE REPORTED FOR
- ONCRETE TEST SUMMARY REPORT SHALL BE PROVIDED FOR EACH SAMPLE TAKEN. 8.2.2.3 THESE SAMPLING REQUIREMENTS SHALL BE ADHERED TO UNLESS SPECIFIED AND RECORDED OTHERWISE AT THE PROJECT PINE-CONSTRUCTION MEETING. ADDITIONAL SAMPLING AND TESTING MAY BE REQUIRED AT THE DISCRETION OF THE PROJECTION.
- CTION (SEWER, DRAIN, WATER):
- - MMM, in QUALITY CONTINUE TEST THEOUGNOISES SPECIFIC ARE THE WIMMAIN NUMBER REQUIRED TO DETERMINE SUFFICIENT THENCH COMPACTION. THE CONTINUE OF SHALL PERFORM AS MANY TESTS AS ARE NECESSARY TO ENSURE THAT THE BYOMS AND SERVICES CONTINUE TO THE REQUIREMENTS OF THE CONTINUES REQUIRED.
 - 53.1.1 SENCH BEDDING (MADILINE) ONE TEST FOR EVERY 75HI OF TRENCH. MINIMUM ONE BETWEEN ANY TWO MANHOLES FOR SEVER AND DRUN.
 - 6.3.1.2 TRENCH BADDELL IMMALINE; ONE TEST FOR EVERY 75th OF TRENCH AT EACH 1.0th FILL CEPTH. MINIMUM ONE BETWEEN ANY WOO MANHOL ES FOR SEINER AND DAME.

 - ANY TWO MINERALES FUN SERVER AND DRUK.

 5.1.1.3 TRENCH BEDDING (SERVICE) ONE PER ROAD CROSSING

 5.1.4 TRENCH BACKFUL (SERVICE) ONE PER ROAD CROSSING AT EACH 1 MW FUL DEPTH.

 5.1.5 ROAD BACE ONE PER ROAD CROSSING AT EACH 1 MW FUL DEPTH.
- 5.3.1.5 ROAD BASE. ONE FOR EVERY 75th OF TRENCH, WITH A MINIMUM OF DNE SETWEEN ANY TWO MANHOLES FOR SAMITARY.
 AND DRAIN.

- PAVEMENT MARKINGS SUCH AS CROSSWALKS AND STOPBARS ARE TO BE THERMOPLASTIC WITH NON-BLIP SURFACE, LONG PAINT LINES SUCH AS CENTERLINES AND FOIL INES ARE TO BE PAINT IN ACCOMMANCE WITH MIND SPECIFICATIONS.
- EXEMPLANES ARE FOR LINES ARE TO BE PAINT IN ACCORDANCE WITH MICE SEPECHCIATIONS. IN ASSESSED OF STANDARDS USE MUTCHC. SHEAR LINE PRAVENERS MARKINGS, WHERE APPLICABLE TO GITTY OF COLMINGO STANDARDS. IN ASSESSED OF STANDARDS USE MUTCHC. SHEAR ELECTRONS SHOWN ARE FOR GENERAL INTEST ONLY. ALL SIGNS AND LOCATIONS ARE TO BE IN ACCORDANCE WITH MUTCHC. COMPRACTOR OF POXIDIC 44 HOUR NOTICE TO EMBORE TO CODERNITE WITH CITY OF REVIEW LIKE PAYMENT LAYOUT PRIOR TO

CLEARING AND GRUPPING

- CLEARING CONSISTS OF CUITING OFF TREES AND BRUSH VEGETATIVE GROWTH TO NOT WORE THAN SPECIFIED HEIGHT ABOVE GROUND AND DISPOSING OF FELLED TRIES, PREVIOUSLY UPPOOTED TRIES AND STUAPS, AND SURFACE DEBISS.
- CLOSE CUT CLEARING CONSISTS OF CUTTING OFF STANDING TIRES, BRUSH SCRUB, ROOTS STUMPS AND EMBEDDED LOGS, REMOVING AT OR CLOSE TO EXISTING GRADE AND DISPOSING OF PAULDI TUMBER AND SURFACE DESIGN.
- 3. CLEARING GOLATED TREES CONSISTS OF CUTTING OFF TO NOT MORE THAN SPECIFIED HEIGHT ABOVE GROUND OF DESIGNATED TREES, AND DISPOSING OF FELLED TREES AND DEBIGS.
- UNDERGRISH CLEARING CONSETS OF PRINCIPAL FROM TREED AREAS OF UNDERGROWTH, DEADWOOD, AND TREES SWALLER THAN 59100 TRUNK DIMETER AND DEPOSING OF PALLON TIMERS AND SUPPACE DIBBIES. 5. GRUBBING CONSISTS OF EXCAVATION AND DISPOSAL OF STUMPS AND ROOTS, BOULDERS AND ROCK PRAGMENTS TO NOT LESS THAN SPECIFIED DISPIT BELOW EXISTING CROUND SUBPLICE.
- PROTECTION

 PREVENT DAMAGE TO TREES, HABITAT, NATURAL FEATURES, BENCH MARKS, WATER COURSES, AND ROOT SYSTEMS OF TREES WHICH ARE TO RESOLVE.

- PROTECT TREES DESIGNATED TO REMAIN BY ERECTING HOARDING AROUND THE DRIP LINE. REPAIR DAMAGED LITEMS TO APPROVAL OF ENVIRONMENTAL MONTOR (ENGINEER.

- 3. REPAR DAMAGED ITEMS TO APPROVING OF ENGROMENTAL MONTOR (ENGREER).
 PREPARATION
 1. SURVEYURS TO STANDOUT USING LABELLED COLORS RIBBON AND STANDS (TORS (OUT // FLL), CREDISIDE CODE OF FOOTINGS.)
 2. INSPECT SITE AND VISION WITH BOTH ENGROMENTAL MONTOR I ENGINEER ITEMS DESCRIPTION TO REMAIN AND LIMITS OF DORSTRUCTION.
 3. INSTALL CONSTRUCTION FRANDS AND STRANDS CELLINEAR TIMES OF CONSTRUCTION.
 4.1. FULL ENDORS IN RECORD CONTROL PROCEDURES ARE NOT EXPECTED FOR USINGOW WHEN CLEARING MAY COMMENCE.
 4.1. FULL ENDORS AND SEDIMENT CONTROL PROCEDURES ARE NOT EXPECTED FOR CLEARING ACTIVITIES.
 5. RECEIVE WITHOUT SEDIMENT CONTROL PROCEDURES MET BY RETAILED AND REPRECISED FOR CLEAR ON TOWNING.
 6. RECEIVE WITHOUT SEDIMENT CONTROL PROCEDURES MET BY RETAILED AND REPRECISED FOR CLEAR ON TOWNING.
 6. RECEIVE WITHOUT SEDIMENT CONTROL PROCEDURES MET BY RETAILED AND REPRECISED PROCEDURES AND TOWNING.
 6. LEADING AND SEDIMENT CONTROL PROCEDURES MET BY RETAILED AND REPRECISED PROCEDURES FOR CREATER ON THE PROCEDURES AND THE PROCEDURES.
- LEARING

 CLEARING INCLUDES FELLING, TRIMINING, AND CUTTING OF TIRES INTO SECTIONS AND SATISFACTORY DISPOSAL OF TREES AND OTHER
 STREET AND KESSPANIED FOR REMOVAL, INCLUDING DOWNED TIMBER, SMASS, BRUSH, AND RUSSISH OCCURRING WITHIN CLEARSED AREAS.
- CLEAR AS DIRECTED BY CONSULTANT, BY CUTTING AT HEIGHT OF NOT NORE THAN 300NIN ABOVE GROUND. IN AREAS TO BE SUBSEL GROUND, HEIGHT OF STUMPS LEFT FROM CLEARING OPERATIONS TO BE NOT MORE THAN 1.0Y ABOVE GROUND SURFACE.
- ANY SAFE MINIMUM SEMECTED STREES DESIGNATED TO REMAIN AS DIRECTED BY CONSULTANT
 REMAINED. OF WOODY DERBIS FROM THE CREEK ONLY PERMITTED UNDER THE DIRECT, FULL TIME SUPERVISION OF THE ENVIRONMENTAL
 MOINTON.
- MISHITOR
 CLOSE OUT CLEARING
 1. CLOSE CUT CLEARING TO GROUND LEVEL TO WITHIN 190+W OF GROUND SURFACE.
 2. CUT OF PRANCHES OVERHANDING AREA CLEARED.
 3. CUT OFF URSOUND SPANICHES ON TREES DESIGNATED TO REMAIN.

- CUIT OF FURGULAD SHANDES ON THESE DESIGNATED TO HEADING.

 BOALHED TREES OF TREE AT HIGHET OF NOT MORE THAN 200-MM, ABOVE GROUND SURFACE.

 GRILD OUT DOLATED TREE STAMPS.

 THAN TREES DESIGNATED TO BE LEFT STANDING WITHIN CLEARED AREAS OF DEAD BRANCHES.

 UNDERBRUIGHT GLARMO.
- NDERBRUSH GLEARING CLEAR UNDERBRUSH FROM AREAS AS INDICATED AT GROUND LEVEL
- IRIJEBINO REMICVE AND DISPOSE OF ROOTS LARGER THAN TSHIT IN DIAMETER, MATTED ROOTS, AND DESIGNATED STUMPS FROM INDICATED GRUIBING ABBUSE
- OKEAL SRUB OUT STUMPS AND ROOTS TO NOT LESS THAN 200mm BELOW GROUND SURFACE.
- DRUG OUT YISBLE BOOK FRAGMENTS AND BOLLDERS, GREATER THAN 200YET IN GREATEST DIMENSION, BUT LESS THAN 0, 15H*,
 FILL DEPIMENSIONS MADE BY CRUMBING WITH SURFACE MATERIAL AND TO MAKE NEW SURFACE COMPONE WITH EXISTING ADJACENT SURFACE OF
- CROCORD.

 REMOVAL & DISPOSAL

 1. REMOVE CLEMED AND GRUSSED MATERIALS TO DISPOSAL AREA
 FINISHED SURFACE

 1. LEAVE CROADED SURFACE IN CONDITION SURFABLE FOR INMEDIATE GRADING OPERATIONS TO APPROVAL OF ENGINEER.

EARTHWORKS, BLASTING AND GEOTECHNICAL

- LOCAL AUTHORITY SHALL BE GIVEN NOTICE AS RECARRED PRIOR TO ANY BLASTING TAYING PLACE.
 EARTHWORKS PRODUCTS MATERIALS MAY REQUIRE A PERMIT PRIOR TO ANY REMOVAL OR DEPOSITING. CONTRACTOR TO ENSURE PERMITS ARE
 DITAMED.
- ING WALLS AND EARTHWORK STRUCTURES TO BE APPROVED BY THE GEOTECHNICAL ENGINEER OF RECORD
- ALL FILL TO BE COMPACTED TO MINIMUM RW. STANDARD MODIFIED PROCTOR DENSITY UNLESS OTHERWISE NOTED OR DIRECTED BY DESCRIBED HELD IN LARBOSCHE AREAS TO BE MINIMUM BY. STANDARD MODIFIED PROCTOR DENSITY IN ACCIDENT AND DEPTH OF SOL PRE-LANDSCAPE DENSITY OF CONSULTANT TO PROVIDE WINTER ACCIDENTANCE OF SUSGREDE PRIOR TO PLACING SOL.
- DESTRUCTIONS AND PROVIDE WHITTEN ACCEPTANCE OF SUBGRACE PRIOR TO CONSTITUCTING STRUCTURAL WALLS.

 DEDTECNING A ENGREER TO REVIEW AND APPROVE ALL RETAINING WALLS AND EARTHWORK STRUCTURAL WALLS.

 TO THE CONSERNAG AUTHORITHMS.
- TO THE GOVERNING AUTHORITIES.

 1. CONTECHNICA CHITTMANN IS REQUIRED ON ALL RETAINING WALLS MAD EARTHWORK STRUCTURES AND PROVIDE WRITTEN APPROVAL

 1. CONTECHNICAL ENGINEET TO PROVIDE WRITTEN ACCEPTANCE OF THIS AND COMPACTION RETHODICAGY. REQUIRED CERTIFICATION THAT
 TRESHOL RECORD, BACKFUL SUBGRACE AND FILL HAVE MET MANIAN COMPACTION REQUIREMENTS THROUGHOUT

 CONTRACTOR TO COORDINATE REQUIRED GEOTECHNICAL TESTING, ALL TESTING REPORTS TO BE FORWARDED TO THE ENGINEER WITHIN 72

 HOURS.

ROUGH GRADING

- PROTECT CONSTRUCTION FENCING, TREES, EROSION AND SEDIMENT CONTROL FEATURES, NATURAL FEATURES AND SENCE MARKS WHICH ARE
 TO REMAIN AS DIRECTED BY CONSULTANT, IF DAMAGED RESTORE TO ORIGINAL OR BETTER CONDITION UNLESS DIRECTED OTHERWISE.
- DO NOT HORSELY APPECTED AS DETERMINED BY COMPLETE WELL OF PROZEN CONDITION OR IN ANY MANNER IN WHICH BOIL STRUCTURE IS ADVERSELY AFFECTED AS DETERMINED BY COMPLETAVE.
- COMMENCE TO PSOLESTIRPHING OF AREAS AS INDICATED AFTER AREA HAS BEEN QUEATED OF BRUSH WEEDS AND DRASSES AND RUMOVED FROM 8/TB.
- STRIP TOPSOL TO DEPTHS AS INDICATED.
 STOCKPLE TOPSOL AWAY FROM PROJECT SITE TO PREVENT MICRATION OF FINES TO WATERCOURSE.

ENVIRONMENTAL PROTECTION

VOI. TOTALITIMA.

EXCANTIONED TO BE SPRINKLED LIKTIL DAMP OR TO THE DISCRETION OF THE ENGINEER/BROSION AND SECRMENT CONTROL SUPERVISOR OD NOT DEPENDENCE SO A TO CREATE RUNGER.

1. ROUGH GRADE TO LEVELS, PROFILES AND CONTOURS ALLOWING FOR SURFACE TREATMENT AS MOICATED ON CONSTRUCTION DOCUMENTS

- OFIGINAL LABELS AND MATERIAL SAFETY DATA INFORMATION WILL BE RETAINED. THEY CONTAIN IMPORTANT PROBUCT APPORMATION, IF SURPLUS PROBUCTS MUST BE DISPOSED OF MANUFACTURING OR LOCAL AND PROBUCHS AND TROOD WITHOUT FOR PROPER DISPOSAL WILL BE
- 3. ALL ON-SITE VEHICLES TO BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTATIVE MAINTENANCE TO REDUCE THE CHANCE OF TRANSPORT.

- ALL CONTAINERS ARE TO BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE, EXCESS PAINT IS NOT TO BE DISCHARGED TO THE STORM WATER SYSTEM, BUT PROPERLY DISPOSED OF ACCORDING TO MANUFACTURERS' INSTRUCTIONS OR PROVINCIAL AND LOCAL BEGILLATION.

- DESCRIPTION OF CONTINUE STATES FROM THE STATES WANTED SECRETARY OF CONSTRUCTION PROJECT.

 THE FOLLOWING HOUSENESS FROM PRACTICES ARE TO BE FOLLOWED ORSITE DURING THE CONSTRUCTION PROJECT.

 AN EFFORT IS WANTED TO STORED CAN'T INDUCEN PROGRET TO GO THE CO.

 ALL MATERIALS STORED CASTE ARE TO BE STORED IN A NEAT, ORDERLY MANNER IN THEIR APPROPRIATE CONTAINERS AND, IF POSSIBLE, UNDER A PROOF OR OTHER BILLIOUSIES.

- SPLL CONTROL PRACTICES

 IN ADDITION TO THE GOOD HUSSINGEPPES AND WATERIAL WAVAGEMENT PRACTICES, THE FOLLOWING PRACTICES ARE TO BE FOLLOWED FOR SPLL

 PROJECTION AND CLEARLY.
- MATERIUS AND BOUPHENT NECESSARY FOR SPIL CLEMAP, ARE TO BE REPT IN THE MATERIUS STORAGE AREA CHRISTE EQUIPMENT AND MATERIAS WILL PASTURE AT MOTHER FOR TO BROOKE DIES FANS MOSS, RIVES GLOVES, GOOGLES HITTY (IFTER SWAD EMMOLET, AND RESIDE AND MATERIAL REPORT AREA CHRISTER SPECIFICATION FOR INSPECIATION FOR THE PROPERTY OF THE PROPERTY
- SPILLS OF HAZARDOUS OR TOXIC MATERIAL ARE TO BE REPORTED TO THE APPROPRIATE PROVINCIAL OR LOCAL GOVERNMENT AGENCY. REGARDLESS OF THE 522".
- AFTER A SPILL THE SPILL PREVENTION PLAN IS TO BE ADJUSTED TO INCLIDE MEASURES TO PREVENT ANY TYPE OF SPILL FROM RE-OCCURING. A DESCRIPTION OF THE SPILL WHAT CAUSED IT, AND THE CURANIP MEASURES ARE TO ALSO BE INCLUDED. THE STIT SUPPRINTENDENT IS RESPONSIBLE FOR THE DAY-TO-DAY STIT OF RATIONS AND WILL BE THE SPIL PREVENTION AND CLEARLY EXCHANGE THE STILL PREVENTION AND CLEARLY EXCHANGE THESE THE STILL PREVENTION AND CLEARLY EXCHANGE THESE
- THE CONTRACTOR IS FULLY RESPONSIBLE FOR CONTROLLING EROSION, SEDIMENT, DUST AND ALL POTENTIAL RELEASES FROM THE PROJECT.
- THE EROSION & SEGMENT CONTROL WORKS NOTED ON THIS PLAN ARE TO BE CONSIDERED THE ABSOLUTE MINIMUM CONSTRUCTION ACTIVITIES MAY RECKARE ADDITIONAL MEASURES TO PREVENT SEDMENT FROM ENTERING MUNICIPAL SYSTEMS OF ENVIRONMENTALLY PROTECTED AREAS
- ERGISION AND SEDMENT WORKS ARE TO BE INSTALLED WHERE POTENTIAL PROBLEMS CAN BE PREDICTED OR ARE LIKELY TO HAPPEN, OD NOT WAIT FOR AN ERGISION AND SEDMENT PROBLEM TO ARISE.
- EQUIPMENT AND WINDHAMSHEM TO TO BE OF BSST QUALITY. THE ENGINEER OR ENVIRONMENTAL MONITOR RESERVES THE RIGHT TO DISHRIS ANY EQUIPMENT HOWN THE SITE WHICH IS INSURVABLE (OF ENTRAUDIC LEWIS ETC.)

 THE CONTRACTOR SHALL BE RESPONSIBLE FOR TAKING APPROPRIATE MEASURES TO KEEP SLTS AND OTHER DELETERIOUS MATERIAL FROM LEWING THE STATE OF THE PROPRIES OF
- TO AVOID RECEIVE AND COST, APPLICATION OF SERVING PROCESSES SHOULD THAT CONSTRUCTION ACTIVITIES ARE PRIVATED SO TO AVOID RECEIVE AND COST, APPLICATION OF SERVING PROCESSES AND AVOID AND AVOID AND AVOID AVOID AND AVOID AND AVOID AVOID AND AVOID AV
- FROSION AND SEDIMENT CONTROLS WILL BE INSPECTED DURING AND AFTER ALL MAJOR STORM EVENTS. THE ENVIRONMENTAL MONITOR WILL MEET WITH THE CONTRACTOR PERIODNOM IT AS SEDULIBED TO BEVIEW THE PROJECT SCHOOL & AND RE ATED FROSION CONTROL MEASURES.
- 4. WERRE SECURISED BOLLS TO BE LET FOR A PERIOD OF AT LEST SECURING SHOWS HITCHISSENSENS. TERMINISENS WAS A SECURISED SHOWS HITCHISSENSENS. TERMINISENS WAS A SECURISED SHOWS HITCHISSENSENS. TERMINISENS WAS A SECURISED SHOWS AS A SECUR

- ALL SET FENCES SHALL BE INSPECTED IMMEDIATELY AFTER A RUNOFF EVENT AND AT LEAST DAILY DURING PROLONGED RANFALL. ANY THE SET FENCE SHARRERS SHALL BE MAINTAINED IN PLACE, WITHOUT GAPS, AND WITHOUT UNDERWINNING, SO AS TO PREVENT BEDIMENT PASSAGE THROUGH OR UNDER THE BARRIER. ADDITIONAL THROUGH OF VARIANCHE MANDER.

 ACCUMULATED SEMINATI SHALL BE REMOVED AT THE DIRECTION OF THE PROJECT ENVIRONMENTAL MONITOR OF ENVIRONMENTAL BUT FROM EASING SHALL SE REMOVED WHEN, IN THE OPINION OF THE ENVIRONMENTAL MONITOR OF ENGINEER THE MEASURE IS NO CONCER RECURSION.
- CONGER RECOURSED.

 SELT FENCE BARRIERS SHALL SE REMOVED IN A MANNER THAT:

 * AVOIDS ENTRY OF EQUIPMENT, OTHER THAN HAND HELD EQUIPMENT, TO ANY WATER COURSE, AND PREVENTS RELEASE OF SEDIMENT AND DESRIS TO ANY WATER COURSE.
 REMOVE DROSION AND SEDIMENTATION CONTROLS AND RESTORE AND STABLIZE AREAS DISTURNED DURING RENOVAL

ISSUED FOR OFF-SITE APPROVAL

NOTES

ALL SOIL PILES ARE TO BE SECURELY COVERED MIGHTLY WITH ANCHORED TARRAULINS OR WHEN NOT IN USE FOR EXTENDED PERIODS DURING THE DAY OF WHEN RIGHT PURITS ARE ANTICIPALIED.

A SARRIER FENCE IS TO BE PROVIDED AROUND THE CONSTRUCTION SITE CONSISTING OF A CONSTRUCTION FENCE TO RESTRICT AREAS OF

THE SE PRACTICES ARE USED TO REDUCE THE RISK ASSOCIATED WITH HAZARDOUS MATERIAL PRODUCTS THAT WILL SE KEPT IN ORIGINAL CONTINUES UNLESS THEY ARE NOT RE-SEAL-MALE.

LEAVIGE.

PETROCILIA PRODUCTS

PETROLILIA PRODUCTS

FERTILIZERS ARE TO BE APPLIED DRUY IN THE MINIMUM AMOUNTS RECOMMENDED BY THE MANUFACTURER, ONCE APPLIED FERTILIZERS ARE TO BE WORKED INTO THE SIDE TO LIMIT EXPOSURE TO STORM WATER STORMAGE WILL BE IN A COVERED SHED. THE CONTENTS OF ANY PARTIALLY USED SAILS OF PERTILIZERS ARE TO BE TRANSFERRED TO A SEALABLE PLANTIC BIN TO AND SMILLS.

CONGRETE TRUCKS ARE NOT FERMITTED TO WASH OUT OR DISCHARGE SURPLUS CONCRETE OR DRUM WASH WATER ON THE SITE, UNLESS TO A DESIGNATIO ID DATHON SEPARATE FROM THE STORM WATER SEDWAY. BASIN.

A ROOF DISTORER END. COURSE.

PRODUCTS ARE TO DE REPT IN THEIR ORIGINAL CONTAINERS WITH THE ORIGINAL MANUFACTURER'S LABEL,
SUBSTANCES ARE NOT TO BE MAKED WITH ANOTHER MAY ESPECIAMENDED BY THE MANUFACTURERS.
WHENDERS POSSIBLE ALL OF A PRODUCT ARE TO BE USED OF USE FOR LOOP OR THE MANUFACTURERS.
MANUFACTURERS RECOMMENDATIONS FOR PROPERTURE AND DISTORAL ARE TO BE FOLLOWED.
THE STEE MAY PROPERTURE AND THE MAY REPT COURT OF PROPERTURE AND DISTORAL ARE TO BE FOLLOWED.

- MANUFACTURERS RECOMMENDED METHODS FOR SPLL CLEANLY ARE TO BE CLEANLY POSTED AND SITE PERSONNEL ARE TO BE MADE AWARE OF PROCEDURES AND THE LOCATION OF THE INCOMMENTATION AND CLEANARY SURVEYES.
- ALL SPILLS ARE TO BE CLEARED UP IMMEDIATELY AFTER DISCOVERY.
 THE SPILL AREA IS TO DE KEPT WELL VENTLATED, AND PERSONNEL ARE TO WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT BULIRY FROM CONTACT WITH A MAZARDOL AS I BRETANCE.
- EROSION AND SEDIMENT CONTROL CONTRACTOR TO CONSTRUCT FROSION AND SEDIMENT CONTROL MEASURES TO PREVENT ANY RUNOFF, IN ACCORDANCE WITH CITY OF COLMODE BY JAKE AND DRAWING BOTES.
- THE ENGINEER OR ENVIRONMENTAL MONTOR WAS THE RIGHT TO SHUT DOWN CONSTRUCTION ACTIVITIES IF EROSION AND SEDIMENT CONTROL MEASURES ARE NOT MEETING THEIR PURPOSE OR CAUSING POSSIBLE DETERMENTAL EFFECTS TO PROTECTED RIPARIAN AREAS.
- EROSION AND SEDMENT CONTROL. IS AN ON-GOING PROCESS DETAILS NOTED ON THESE PLANS ARE FOR EARTHWORKS AND GENERAL GUIDANCE ONLY. AS CONSTRUCTION PROCESSOS, VARIOUS EROSION AND SEDMENT CONTROL TECHNIQUES WILL BE REQUIRED TO AUGIO THE TRANSPORT OF SEPAMENT.
- ALL TEMPORATE RESIDENCE IN WAILER.

 ALL TEMPORATE RESIDENCE AND EXPENSES ARE TO BE BRANCES WITHOUT ONLY OF THAT IT IS PARTUATION ON AFTER ARE THE THAT THE T
- EXCAVATION WORKS THAT ARE TO OCCUP CLOSE TO A RIPARIAM AREA SHOULD BE PLANNED TO CONCIDE WITH THE PROVINCIAL FISHERIES WINDOW FOR IN STREAM WORKS. THE WINDOW IS JUNE 15 SEPTEMBER 16 NO CONSTRUCTION ACTIVITY OF JUND DISTURBANCE IS TO OCCUP WITH A JUNE TO THE CONCIDENCE OF THE PROVINCIAL FRANCISCO FOR THE

- SILTISEDIMENT FENCE BARRIER PROVIDE TEMPORARY ERGORD AND SEDIMENTATION CONTROL MEASURES TO PRIVENT SQL BROSION AND DISCHARGE OF SQL SEARING WATER SANGEY OR MEASURED BY A DATE OF THE SANGEY OF THE SA

 - WATER SAYS FOR ARRESTED LIST TO ADJOINT PROPERTY SAYD WANDAMYS THAT COMPLIES WITH EAR AUTROCADE CONTROLLED ATTER CLEARING BUT PRICE TO AUTROCADE ATTER CLEARING BUT PRICE TO GROUPED ATTER CLEARING BUT PRICE TO GROUPED ATTER CLEARING BUT PRICE TO GROUPED ATTER CLEARING BUT PRICE TO GROUPED ATTER CLEARING BUT PRICE TO GROUPED ATTER CLEARING BUT PRICE TO GROUPED AND AUTROCADE ATTER CLEARING BUT PRICE TO GROUPED AND AUTROCADE AND AUTROCADE ATTER CLEARING BUT PRICE TO GROUPED AND AUTROCADE AND AUTROCADE ATTER CLEARING BUT PRICE TO GROUPED AND AUTROCADE AND AUTRO

REVIEWED Style Columnia 2025-01-03

3494 WISHART ROAD WALKING STICK DEVELOPMENTS LTD.

SHEET 2 OF 9

369-02

DATE SIGN No. 2004-08-09 NOC DATE SICK

REVISIONS

DESIGN: ENGINEER:

DEVELOPMENTS LTD.

WALKING STICK



PROJECT ENGINEERS LTD.
TIL 20/ASS/2015 WWW.007CLGA
BUTE ITS SET ASSESSED WITH SET AS


DO NOT SCALE THE DRAWING


DRAWN BY: DESIGN: ENGINEER:


WALKING STICK DEVELOPMENTS LTD.

PRIVATE ROAD - EARTHWORKS

CN POINT PROJECT No.
369-02
GOVERNING AUTHORITY FILE No.
TBD.
SHEET 3 OF 9
REV.







- 2. ALL EARTHWORKS TO BE DONE UNDER THE SUPERVISION OF A GEOTECHNICAL ENGINEER.
- ALL RETAINING STRUCTURES OVER 12th HIGH, SLOPES OVER 30°, AND FILLS TO BE CERTIFIED BY GEOTECHNICAL ENGINEER.
- 4. CENTER LINE ELEVATIONS SHOWN ARE TO TOP OF ASPHALT.








No.	ISSUED DESCRIPTION	DATE	SION	No.	REVISIONS DESCRIPTION	DATE	SIGN
100	ISSUED FOR TO'S APPROVAL	2024-08-09	NOC				
2	ISSUED FOR DEVELOPMENT PERMIT	2024-10-25	JEH				
\$	ISSUED FOR OFFSITE APPROVAL	2025-01-03	STR				
2850 P		19-2000000	4000				
100		(F)		2 2			
		- 1					
Z-01		- 1					





WALKING STICK DEVELOPMENTS LTD.


3494 WISHART ROAD WALKING STICK DEVELOPMENTS LTD. ROAD SECTIONS

ON POINT PROJECT No. 369-02 GOVERNING AUTHORITY FILE NO. TBD. SHEET 5 OF 9 REV......









Walking Stick Developments Inc.

Erosion and Sediment Control Plan

3494 Wishart Road - Townhouse Development

The primary focus of the erosion and sediment control plan is to prevent erosion. If there is no erosion there will be minimal to no sediment substantially reducing the risk of sediment leaving the property.

General Mitigation Techniques to Prevent Erosion and Manage Sediment

- All sediment control barriers and structures will be inspected regularly and maintained/repaired as necessary under the supervision and direction of the project biologist.
- Weather advisories will be carefully monitored so that work can be scheduled to avoid wet and rainy periods that may result in a high surface flow rate that could lead to an increase in erosion and sedimentation.
- All catch basins will have a sediment "CB sock" installed to prevent any runoff into the storm system. The CB socks will be regularly inspected.
- Silt fencing composed of geotextile fabric will be installed along the East boundary (low point) of the property. Preventing any sediment from entering the storm water ditch that runs along the Western edge of Wishart Road.
- Gravel construction entrances will be built off of Wishart Road and at the Delora Dr extension point.
- Material stockpiles will be kept in flat areas whenever possible and at least 15 metres from any natural water course.
- Construction equipment and tools will be cleaned at least 30 metres from any water features.


Erosion and Sediment Control in Restoration Areas

- To reduce risk of erosion and sedimentation during restoration activities work will be scheduled to avoid periods of heavy rainfall (>20 mm in 24 hrs.) and re-plant bare areas promptly after invasive species removal.
- No large heavy equipment is to be used in the restoration area. Invasive vegetation is to be removed with hand tools or a mini excavator with a skilled operator.
- The amount of time soil is exposed will be minimized followed by seeding and planting as soon possible after the removal of invasive species.

The attached site plans for 3494 Wishart Road display the location of the erosion and sediment control features and structures.

Sincerely,

David Lunn, P. Eng





SHEET 2 OF 8